



PUNJAB STATE TRANSMISSION CORPORATION LIMITED

(Regd.office: PSEB Head office, The Mall Patiala-147001
Corporate Identity Number:U40109PB2010SGC033814 www.pstcl.org
O/o Additional S.E.TLSC, Division, PSTCL, Patiala Tel.No.&Fax No.0175-2363312 E-mail:srxen-tlss-pta@pstcl.org

TENDER NOTICE

1. Office of : **ADDL. Superintending Engineer, TLSC Division, Ablowal, Patiala Ph.0175-2363312.**
2. Name of work : Laying of tower foundations, Erection of Towers, Stringing, Sagging & shifting of 220 KV Muksar-Bajakhana line from Amritsar Bathinda Road NH-15 (117.57 Km to 287.215 Km) –Deposit work
3. Tender Enq. No. : **6 /TLSC/P/2015-16.**
4. Last Date & Time for :
 - (a) Sale of Tender documents : **21.09.2015 upto 02.30 p.m.**
 - (b) Receipt of tender : **21.09.2015 upto 03.00 p.m.**
 - (c) Opening of tender : **21.09.2015 upto 03.30 p.m.**
5. Cost of specifications : **Rs.500/-**
6. Completion Period : **2 months**

For further details kindly visit PSTCL website www.pstcl.org


Addl. Superintending Engineer,
TLSC, Division, Patiala.



ਪੰਜਾਬ ਰਾਜ ਟਰਾਂਸਮਿਸ਼ਨ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮਿਟਡ

(ਰਜਿ ਦਫਤਰ ਪੀ ਐਸ ਈ.ਬੀ. ਹੈਡ ਆਫਿਸ, ਦੀ ਮਾਲ ਪਟਿਆਲਾ-147001)

ਕਾਰਪੋਰੇਟ ਐਡਵਾਈਜ਼ਰੀ ਨੰਬਰ: ਯੂ40109ਪੀਬੀ2010ਐਸਜੀਸੀ033814 www.pstcl.org

o/o ਵਪੀਕ ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ ਟੀ.ਐਲ.ਐਸ.ਸੀ ਮੰਡਲ, ਪਟਿਆਲਾ ਟੈਲੀਫ਼ੋਨ/ਫੈਕਸ: 0175-2363312 srxen-tlss@pstcl.org

ਟੈਂਡਰ ਨੋਟਿਸ

ਟੈਂਡਰ ਇੰਨਕੁਆਰੀ ਨੰ: 06/ਟੀਐਲਐਸਸੀ/ਪਟਿਆਲਾ/2015-16

ਕੰਮ ਦਾ ਨਾਂ : Laying of tower foundations, Erection of Towers, Stringing, Sagging & shifting of
220 KV Muktsar-Bajakhana line from Amritsar Bathinda Road NH-15 (117.57
Km to 287.215 Km) –Deposit work

ਟੈਂਡਰ ਸਬੰਧੀ ਮਿਤੀ ਅਤੇ ਸਮਾਂ:

- ੳ) : ਟੈਂਡਰ ਦਸਤਾਵੇਜ਼ ਵੇਚਣ ਦੀ ਮਿਤੀ: 21 ਸਤੰਬਰ, 2015 ਸਮਾਂ 02.30 ਵਜੇ ਤੱਕ
ਅ) : ਟੈਂਡਰ ਪ੍ਰਾਪਤੀ ਦੀ ਮਿਤੀ : 21 ਸਤੰਬਰ, 2015 ਸਮਾਂ 03.00 ਵਜੇ ਤੱਕ
ੲ) : ਟੈਂਡਰ ਖੁੱਲਣ ਦੀ ਮਿਤੀ : 21 ਸਤੰਬਰ, 2015 ਸਮਾਂ 03.30 ਵਜੇ ਤੱਕ

ਸਪੈਸੀਫਿਕੇਸ਼ਨ ਦੀ ਕੀਮਤ: ਟੈਂਡਰ ਡਾਕੂਮੈਂਟ ਦੀ ਕੀਮਤ : 500/-

ਕੰਪਲੀਸ਼ਨ ਸਮਾਂ : 02 ਮਹੀਨੇ

ਨੋਟ: ਹੋਰ ਵੇਰਵੇ ਪੀਐਸਟੀਸੀਐਲ ਦੀ ਵੈਬ ਸਾਈਟ www.pstcl.org ਤੇ ਵੇਖੇ ਜਾ ਸਕਦੇ ਹਨ।

ਵਪੀਕ ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ, ਟੀਐਲਐਸਸੀ ਮੰਡਲ ਪਟਿਆਲਾ

PUNJAB STATE TRANSMISSION CORPORATION LTD


Laying of tower foundations, Erection of Towers, Stringing, Sagging & shifting of 220 KV Muktsar - Bajakhana line from Amritsar Bathinda road NH-15 (117.57 Km to 287.215 Km.) - Deposit work

Sr. No.	Description	Quantity/ Unit	Cost of work based on unit rate approved	Rate to be given by the bidder
1.	Construction of Tower foundations on lump sum basis as per PSEB drawings (Now PSTCL) including excavation, placement of steel reinforcement, concreting (M-20 grade), stub setting, form work, centering, shoring, shuttering, back filling & other allied works required for setting stubs, including the cost of sand & gravel. The stub setting templates will be provided free of cost (Latest amended drawings to be followed where-ever applicable)			
	Tower type 'C' classified as			
	2D60° Open pit normal foundation upto 6 Mtr. Extension (CW/DT-1303) -Narrow Base	2 Nos.	2x209150.00 = 418300.00	
2.	Transportation & erection of Towers complete with all fittings including tack welding (welding rods to be supplied by the contractor) and Zinc rich paint touching wherever required(zinc paint to be supplied by the contractor) including earthing of towers. Installation of danger plates, number plates, phase plates, circuit plates, Bird Guard & anti climbing devices. Etc. etc. on tonnage basis.	30.525 MT	30.525 x 7521.00 = 229579.00	
3.	Transportation, installation of insulator strings complete with hardware installation and stringing & sagging of Conductor 0.4 Sq." Zebra including fixing of Conductor accessories etc. DC on DC towers complete in all respects.	0.350 Km Double Circuit	0.350 x 154780.00 = 54173.00	
4.	Transportation, installation and stringing & sagging of Earthwire (7/3.15mm) including fixing of Earthwire accessories for the line complete in all respects	0.350 Km.	0.350 x 7412.00 = 2594.00	
5.	Dismantlement 2D-30° + 6 Mtr. = 1 No.	8.960 MT	8.960 x 7521/2 = 33694.00	
6.	Dismantlement of 0.4 Sq." conductor DC on DC	0.350 Km. D/C	0.350x 154780/2 = 27087.00	
7.	Dismantlement of earth wire 7/3.15mm	0.350 Km.	0.350 x 7412/2 = 1297.00	

Sr. No.	Description	Quantity/ Unit	Cost of work based on unit rate approved	Rate to be given by the bidder
8.	Dismantlement & re-sagging of 0.4 Sq." Conductor DC on DC	0.320 Km. D/C	0.320 x 114303.00 = 36577.00	
9	Dismantlement & re-sagging of earth wire 7./3.15mm	0.320 Km.	0.320x 3973.00 = 1271.00	
10.	Check survey and marking of towers For Angle Towers	2 Nos.	2 x1500 = 3000.00	
Total:-			=807572.00	

Earnest Money : Minimum 16500/-
Tender cost : Rs. 500 /-
Completion Date : 2 months from the issue of LOI

1. The above rates are exclusive of Cement & Steel but inclusive of sand, bajri, Centering/shuttering, transportation of material, T&P etc. Cement & steel as per actual consumption will be provided by the Department free of cost, but carriage from Store to the site of work as loading/un-loading of the same has been included in the rates.
2. Dewatering in case of semi-submerged & fully submerged foundations where-ever required shall be paid extra as per actuals to be certified by the concerned Addl. S.E./Sr.Xen, TLSC Division as per prevailing practice. However, the rates of dewatering with pumps for Five Nos. (5 Nos.) has been approved as Rs.453.00 (Rs.Four hundred fifty three only) per hour.
3. The rates approved are inclusive of all type of taxes (EPF, Labour cess, VAT etc.) but exclusive of Service Tax. The service tax as applicable will be paid extra on production of receipt of actual payment.
4. For dismantlement, the rates @ 50% of the approved rates will be allowed as per prevailing practice.
5. For any foundation which has not been covered in the rates approved by PSTCL, the same will be allowed on the same pattern of AOR with the prior approval of CE/TS, PSTCL, Patiala.
6. All terms & conditions of rate contract & specification of works (to which they relate) approved by the PSTCL shall remain unchanged in any circumstance if these are written in-correctly due to inadvertence at any stage.
7. Statutory taxes should be paid after allowing abetments/discounts/exemptions permissible under the relevant act so as to ensure that there is a least payment for PSTCL under the provision of law.
8. Guidelines issued by PSTCL under FR Circular No.1&2/2012 shall also be applicable.
9. The above rates shall remain effective for 120 days from the date of closing/filling of tender.


Deputy Chief Engineer,
TLSC Circle, PSTCL,
Patiala