



PUNJAB STATE TRANSMISSION CORPORATION LIMITED

(Regd.office: PSEB Head office, The Mall Patiala-147001
Corporate Identity Number:U40109PB2010SGC033814 www.pstcl.org
O/o Additional S.E.TLSC, Division, PSTCL, Patiala Tel.No.&Fax No.0175-2363312 E-mail:srxen-tlss-pta@pstcl.org

TENDER NOTICE

Tender Enquiry No. 15 /TLSC/P/2015-16/

Dated : 19.11.2015

Name of work : **Laying of tower foundations, Erection of Tower Stringing, Sagging
for raising of Height of 132KV Muksar-Malout 'H' Rail pole line in
the land of Sh.Maninder Singh of Muksar(Deposit Work)
Amount Rs. 3,71,148/-**

1. Tender Enq. No. : **15/TLSC/P/2015-16.**
2. Last Date & Time for :
 - (a) Sale of Tender documents : **14.12.2015 upto 2.30 p.m.**
 - (b) Receipt of tender : **14.12.2015 upto 3.00 p.m.**
 - (c) Opening of tender : **14.12.2015 upto 3.30 p.m.**
3. Cost of specifications : **Rs.500/-**

For further details kindly visit PSTCL website www.pstcl.org

Addl. Superintending Engineer, TLSC, Division, Patiala.



ਪੰਜਾਬ ਰਾਜ ਟਰਾਂਸਮਿਸ਼ਨ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮਿਟਡ
(ਰਜਿ ਦਫਤਰ ਪੀ ਐਸ ਈ.ਬੀ. ਹੈਡ ਆਫਿਸ, ਦੀ ਮਾਲ ਪਟਿਆਲਾ-147001)
ਕਾਰਪੋਰੇਟ ਐਡਟਿਟੀ ਨੰਬਰ:ਯੂ40109ਪੀਬੀ2010ਐਸਜੀਸੀ033814 www.pstcl.org
o/o ਵਪੀਕ ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ ਟੀ.ਐਲ.ਐਸ.ਸੀ ਮੰਡਲ, ਪਟਿਆਲਾ ਟੈਲੀਫੂਨ/ਫੈਕਸ:0175-2363312 srxen-tlss@pstcl.org

ਟੈਂਡਰ ਨੋਟਿਸ

ਟੈਂਡਰ ਇੰਨਕੁਆਰੀ ਨੰ:15/ਟੀਐਲਐਸਸੀ/ਪਟਿਆਲਾ/2015-16

ਕੰਮ ਦਾ ਨਾਂ : Laying of tower foundations, Erection of Tower Stringing, Sagging
for raising of Height of 132KV Muktsar-Malout 'H' Rail pole line in
the land of Sh.Maninder Singh of Muktsar(Deposit Work)
Amount Rs. 3,71,148/-

ਟੈਂਡਰ ਸਬੰਧੀ ਮਿਤੀ ਅਤੇ ਸਮਾਂ:

ੳ) : ਟੈਂਡਰ ਦਸਤਾਵੇਜ਼ ਵੇਚਣ ਦੀ ਮਿਤੀ: 14 ਦਸੰਬਰ, 2015 ਸਮਾਂ 02.30 ਵਜੇ ਤੱਕ
ਅ) : ਟੈਂਡਰ ਪ੍ਰਾਪਤੀ ਦੀ ਮਿਤੀ : 14 ਦਸੰਬਰ, 2015 ਸਮਾਂ 03.00 ਵਜੇ ਤੱਕ
ੲ) : ਟੈਂਡਰ ਖੁੱਲਣ ਦੀ ਮਿਤੀ 14 ਦਸੰਬਰ, 2015 ਸਮਾਂ 03.30 ਵਜੇ ਤੱਕ

ਸਪੈਸੀਫਿਕੇਸ਼ਨ ਦੀ ਕੀਮਤ: ਟੈਂਡਰ ਡਾਕੂਮੈਂਟ ਦੀ ਕੀਮਤ : 500/-

ਨੋਟ: ਹੋਰ ਵੇਰਵੇ ਪੀਐਸਟੀਸੀਐਲ ਦੀ ਵੈਬ ਸਾਈਟ www.pstcl.org ਤੇ ਵੇਖੇ ਜਾ ਸਕਦੇ ਹਨ।

ਵਪੀਕ ਨਿਗਰਾਨ ਇੰਜੀਨੀਅਰ,
ਟੀ.ਐਲ.ਐਸ.ਸੀ ਮੰਡਲ,
ਪੀ.ਐਸ.ਟੀ.ਮ.ਮ.ਲ. ਪਟਿਆਲਾ

PUNJAB STATE TRANSMISSION CORPORATION LIMITED
Head Office : PSEB Head Office, The Mall, Patiala 147 001.
Office of ADDL. Superintending Engineer, TLSC Division,
Ablowal, Patiala Ph.0175-2363312

Enquiry No.15/TLSC/P/2015-16/

Dated: 19.11.2015

To

Regd.

Sub: **Tender Enquiry.**

Sealed quotations are invited from approved firms/contractors for the work mentioned below duly completed should reach this office on or before 14.12.2015 at 3.00 PM and will be opened on the same day at 3.30 PM if there happens to be a holiday, the same will be receipt/opened on the next working day in the presence of their representatives.

S.No.	Description	QTY.	Remarks
1.	Laying of Tower Foundations, Erection of tower stringing, sagging for raising of height of 132KV Muktsar-Malaut 'H' rail pole line in the land of Sh.Maninder Singh of Muktsar (Deposit Work)	Qty. & Price bid proforma attached as annexure-1	Earnest Money as per clause-2

Completion period : 2 months from the issue of LOI.

Cost of tender document Rs.500/-

TERMS & CONDITIONS

1. The quotation received after due date & time will be rejected.
2. The quoted rate should be valid for 120 days from the date of opening of tender.
3. The earnest money 2% or minimum Rs.7,500/-, whichever is higher, will be deposited in the shape of PSTCL cash receipt/BA-16 or demand draft in favour of Sr.XEN/TLSC Division, PSTCL, Patiala properly pledged subject to max. Rs.5,00,000/-. Earnest money will not be accepted in cheque or in any other form except as detailed above.
4. Tenders will be submitted in two parts as detailed in the specification.
5. All the T&P/machinery required to carry out the work is to be arranged by the Vendor.
6. Conditional, telegraphic and incomplete quotations will be rejected.
7. The tender issuing authority reserves the right to reject any or all quotations without assigning any reason.
8. The required drawings can be seen on any working day in the office of the undersigned.
9. PSTCL reserves the right to split the work among more than one contractor or to increase or decrease the scope of work at the time of award of contract.

Addl. Superintending Engineer,
TLSC, Division, Patiala

C.C.:

1. Dy. Chief Engineer/TLSC Circle, PSTCL, Patiala
2. AEE TLSC S/D, PSTCL, Bathinda.

PUNJAB STATE TRANSMISSION CORPORATION LTD


Laying of tower foundations, Erection of Tower Stringing, Sagging for raising of height of 132 KV Muktsar - Malaut 'H' rail pole line in the land of Sh.Maninder Singh of Muktsar (Deposit work).

Sr. No.	Description	Quantity/ Unit	Cost of work based on unit rate approved	Rate to be given by the bidder
1.	Construction of Tower foundations on lump sum basis as per PSEB drawings (Now PSTCL) including excavation, placement of steel reinforcement, concreting (M-20 grade), stub setting, form work, centering, shoring, shuttering, back filling & other allied works required for setting stubs, including the cost of sand & gravel. The stub setting templates will be provided free of cost (Latest amended drawings to be followed where-ever applicable)			
	Tower type 'C' classified as			
	2D60° Open pit normal foundation upto 6 Mtr. Extension (CW/DT-1303) -Narrow Base	1 Nos.	1x209150.00 = 209150.00	
2.	Transportation & erection of Towers complete with all fittings including tack welding (welding rods to be supplied by the contractor) and Zinc rich paint touching wherever required(zinc paint to be supplied by the contractor) including earthing of towers. Installation of danger plates, number plates, phase plates, circuit plates, Bird Guard & anti climbing devices. Etc. etc. on tonnage basis.	13.334 MT	13.334 x 7521.00 = 100285.00	
3.	Transportation, installation of insulator strings complete with hardware installation and stringing & sagging of Conductor 0.2 Sq." Panther including fixing of Conductor accessories etc. SC on DC towers complete in all respects.	0.529 Km Single Circuit	0.529 x 48396.00 = 25601.00	
5.	Dismantlement of 'H' Rail Pole = 5 Nos. (5x2x580)	5.800 MT	5.800 x 7521/2 = 21811.00	
6.	Dismantlement of 0.2 Sq." conductor SC on DC	0.529 Km. S/C	0.529 x 48396/2 = 12801.00	
7.	Check survey and marking of towers For Angle Towers	1 Nos.	1 x1500 = 1500.00	
	Total:-		371148.00	

Earnest Money : Minimum 7500/-
Tender cost : Rs. 500 /-
Completion Date : 2 months from the issue of LOI

- The above rates are exclusive of Cement & Steel but inclusive of sand, bajri, Centering/shuttering, transportation of material, T&P etc. Cement & steel as per actual consumption will be provided by the Department free of cost, but carriage from Store to the site of work as loading/un-loading of the same has been included in the rates.

2. Dewatering in case of semi-submerged & fully submerged foundations where-ever required shall be paid extra as per actuals to be certified by the concerned Addl. S.E./Sr.Xen, TLSC Division as per prevailing practice. However, the rates of dewatering with pumps for Five Nos. (5 Nos.) has been approved as Rs.453.00 (Rs.Four hundred fifty three only) per hour.
3. The rates approved are inclusive of all type of taxes (EPF, Labour cess, VAT etc.) but exclusive of Service Tax. The service tax as applicable will be paid extra on production of receipt of actual payment.
4. For dismantlement, the rates @ 50% of the approved rates will be allowed as per prevailing practice.
5. For any foundation which has not been covered in the rates approved by PSTCL, the same will be allowed on the same pattern of AOR with the prior approval of CE/TS, PSTCL, Patiala.
6. All terms & conditions of rate contract & specification of works (to which they relate) approved by the PSTCL shall remain unchanged in any circumstance if these are written in-correctly due to inadvertence at any stage.
7. Statutory taxes should be paid after allowing abetments/discounts/exemptions permissible under the relevant act so as to ensure that there is a least payment for PSTCL under the provision of law.
8. Guidelines issued by PSTCL under FR Circular No.1&2/2012 shall also be applicable.
9. The above rates shall remain effective for 120 days from the date of closing/filing of tender.


ADDL.S.E.,
TLSC Division, PSTCL,
Patiala