

DNIT for Repair of Sump and trench at 220 kV S/S Kartarpur

S.no	Description of an Item	Qty	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Earthwork In Excavation In all kind of soil	6.92	Cum	6.6	162.50	
2	First class brick work laid in cement sand mortar 1:6 in foundation and plinth.	12.82	Cum	11.3(i)	4084.52	
3	12.5 mm thick cement plaster 1:5	113	Sqm	15.10	136.48	
4	20 mm thick cement plaster 1:5	15.65	Sqm	15.21	183.10	
5	PCC 1:6:12 with 40 mm stone aggregate	5.94	Cum	10.8(b)(ii)	2309.18	
6	Conglomerate floor 50 mm thick cement concrete 1:2:4	41.35	Sqm	14.7	222.03	
7	Providing and laying, jointing fixing and testing G.I. Pipe lines B-Class including cost of specials such as tees, bends, sockets, elbows etc. testing, cutting, threading inside building complete 32 mm i/d	50	MTR	28.36(d)	426.26	
8	Providing, fixing and jointing G.I union complete on all respect 32 mm i/d G.I union	3	No	28.40(d)	219.14	
9	Providing, Stringing out U.P.V.C. Pipes casting as per IS:15328-2003 class-SN-8 along the trenches and laying the same in Trenches to correct alignment and gradients, cutting and jointing including cost of specials complete as per specifications. 110mm o/d pipe	50	MTR	30.74(iii)b	265.88	
10	Providing and Fixing non clog pump of 3 BHP 3-Phase of Crompton make	2	no	M.Rate	31497.00	
11	Control Panel comprising Switch Starter	2	no	M.Rate	2860.00	
12	Control Panel Fitting on wooden mounted base and underground fitting of PVC Cable	2	no	M.Rate	850.00	
13	PVC Submersible cable 3 core 2.5 Sq. mm. App Rate	90	Rmt	M.Rate	71.50	
14	RCC slab cover 1110x340x50mm (44"x13")	2860	sq.Inch	Nos	1.00	
15	Extra Carriage for coarse sand , coarse aggregate and Stone Metal as per AOR	11.88	Cum	Annex	437.48	
16	Extra Carriage for Fine sand as per AOR	5.09	Cum	Annex	256.80	

17	Extra carriage for cement	2.80	mt	Annex	211.33	
18(i)	Dif. In material rates for crushed bajri 13.2mm	0.93	Cum	Annex	-203.64	
(ii)	Dif. In material rates for crushed bajri 11.2mm	0.93	Cum	Annex	-121.11	
(iii)	Dif. In material rates for coarse sand	4.14	Cum	Annex	14.86	
(iv)	Dif. In material rates for stone metal 40mm	5.88	Cum	Annex	-182.82	
(v)	Dif. In material rates for bricks	6.15	No.s	Annex	325.37	

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowlal store.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – In – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.

- 5 Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor