DNIT for Replacement of 1 no. of 66 kv SF -6 Breaker foundation at 220 kv s/s Kotla Jangan.

s No	Description of an Item	QTY	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Earthwork In Excavation in all kind of soil	1.82	Cum	6.6	162.5	
2	PCC 1:6:12 with 40 mm stone aggregate	0.12	Cum	10.7(b)(ii)	2209.18	
3	Cold Twisted deformed bars FE 500 for RCC work including cutting, bending and placing in position in complete	0.32	Qtl	18.18	780.36	
4	Shuttering or faces of concrete foundation	0.57	Sqm	9.10	187.50	
5	Centring and shuttering for Column	4.42	Sqm	9.40	425.89	
6	RCC M20	0.86	cum	10.15	2809.51	
7	Fixing of template	1.00	No	NS	200.00	
8	Extra carriage for fine sand as per	0.06	Cum	Annexure	256.80	
9	Extra carriage and difference of material	0.37	Cum	Annexure	269.10	
10	for crusher 13.2 mm Extra carriage and difference of material	0.37	Cum	Annexure	319.10	
11	for crusher 11.2 mm Extra carriage and difference of material	0.37	Cum	Annexure	400.44	
12	Extra carriage and difference of material	0.12	Cum	Annexure	274.05	
13	for stone metal 40 mm Extra carriage for Cement	0.30	MT	Annexure	172.54	

Notes: -

- These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowal store as per availability.
- PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
- GST will be applicable as per Govt. norms and will be paid extra.
- Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.