

Punjab State Transmission Corporation Limited

DNIT for Repair of Water Supply System at 132 KV S/Stn Sakatri Bagh

S.No	Qty	Description of Item	Unit	CSR Ref	Deptt Rates	Rates To be Quoted By Contractor
1	86.2	Boring with casing pipe for tubewell in all soils complete in all respect.Boring with 150 mm I/d Housing Pipe	Rmt	28.72a	762.43	
2	86.2	Providing, Laying, fixing & jointing of P.V.C. Pipes as per ISI-4985 (ISI marked with the prior approval of Engineer-in-Charge) along the Trenches and laying the same in Trenches to correct alignment and gradients, cutting, jointing and testing complete as per specifications.110mm o/d pipe of 8 Kgf. / sqcm	Rmt	28.13viii	442.87	
3	34.48	Providing and laying, jointing, fixing, testing G.I. Pipe Lines B- Class, including cost of Specials such as tees, bends, sockets elbow etc., cutting, threading and testing in trenches in the ground complete 40 mm I/d	Rmt	28.36e	485.12	
4	1	Providing & Fixing 2 BHP Submersible Pump complete in all respects of ISI Marked or equivalent Make(Crompton etc) . Control Panel comprising of switch starter, Amp meter, Volt Meter,Capacitor .Fitting of Control Panel on Wall Rate approved as per Est.no.83076/2018-19	Each	M.Rate	18150	
5	50	PVC Submersible cable 3 core 2.5 Sq.mm App.Rate	Rmt	M.Rate	71.5	
6	20	Providing and laying, jointing, fixing, testing G.I. Pipe Lines B- Class, including cost of Specials such as tees, bends, sockets elbow etc., cutting, threading and testing in trenches in the ground complete 20mm I/d	Rmt	28.36b	224.77	
7	2	Providing, fixing and jointing Union Couplings in G.I. Pipe lines.20mm I/d	Each	28.40b	134.67	
8	2	Providing, fixing and jointing gun-metal peet valves with hand wheels, on G.I. Pipe lines laid in the ground Including all carriages complete.20mm I/d	Each	28.43c	502.38	
9	20	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes as per IS 15778 (ISI marked with the prior approval of Engineer-in Charge)25mm	Rmt	28.19c	255.13	

Notes: -

1. These rates are through rates exclusive of Cement & Steel.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er - In - Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor