

# Punjab State Transmission Corporation Limited

From:

Sr. XEN/ P&M  
Civil MTC. Division,  
Jalandhar.

Limited Tender Enquiry No.	42/2023-24, 43/2023-24, 44/2023-24, 45/2023-24, 46/2023-24,
Date of Receipt of Tenders	28.08.2023 up to 01:00PM
Date of opening of Tenders	28.08.2023 at 03.00 PM

To:

M/s As per overleaf.

Memo No 1532/21

Dated 1-10-2023

Subject: Limited TE No.- 42/2023-24 ,43/2023-24 ,44/2023-24 ,45/2023-24 ,46/2023-24.

You are requested to quote your lowest rates for the execution of the following works. Quotations should reach in the Office of the undersigned before 01.00 PM on due date. If this day happens to be a holiday, the quotation can be submitted on the following working day and the same shall be opened on that day. The Quotations received at the above mentioned date and time shall be opened at 03.00 PM in the presence of committee of officers/officials of the department and representatives of the contractors who want to be present.


Limited TE No.	Description of work	Estimated Cost	Earnest Money (Rs.)	Time for completion of work.
42/2023-24	Repair of store office at 220kv s/s Jamsher.	2.55 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000.	45 Days
43/2023-24	Repair of control room building at 220kv s/s Chohla sahib.	2.50 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	45 Days
44/2023-24	Repair of CO&C Building & switch house building at 132kv s/s Batala.	3.95 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	60 Days

45/2023-24	Repair and Maintenance of sub division office of civil works PSTCL, Ludhiana.	1.90 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	45 Days
46/2023-24	Replacement of submersible pump motor at 220kv s/s Dasuya.	28,000/-	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	30 Days

**General Terms & Conditions:-**

1. The Tender documents cost is not charged as per Financial Advisor, PSTCL, Patiala(Budget Section) O/o No: 10 dt: 22-2-18 and Earnest Money need to be paid in the form of cash or Demand Draft drawn on any scheduled bank in the favour of Senior executive engineer, P&M Civil Maintenance Division, PSTCL Jalandhar.
2. Earnest money shall be 2% of tender value with minimum of Rs.5000/- whichever is higher. Earnest money shall be nil for work order below Rs.50,000/- as per Works Regulations. The **Earnest Money along with Documents** should be kept in envelope duly sealed super-scribed "**EARNEST MONEY**" and Quotation should be kept in separate envelope duly sealed super-scribed "**QUOTATION**".
3. Quotations not accompanying the EMD as per sr. no. 2 will not be entertained.
4. Tenders for part work, Conditional tenders, telegraphic tender through fax or tenders not on prescribed forms of tenders without earnest money in the required shape shall not be accepted.
5. A set of tender documents (non-transferable) containing technical specifications, general instructions, terms & conditions can be downloaded from [www.pstcl.org](http://www.pstcl.org) or obtained from the office of Sr. Xen P&M Divn, PSTCL Jalandhar by dated 28.08.2023 up to 01:00 PM
6. Work shall be carried out as per PWD specifications to meet with the requirements of the work at site to the entire satisfaction of the Engineer-in-Charge.
7. GST is applicable as per Govt. norms.
8. The quoted Rate shall be valid up to 120 days and shall remain firm through to the completion of work
9. If the work is not completed within stipulated period, PSTCL shall impose 0.5% penalty per week subject to the maximum of 5% of the Total amount.
10. Security Deposit: 5% of the Gross Value of the work done will be deducted from the running bills as Security Deposit. No interest shall be payable to contractors on the amount of security deposit.
11. Income Tax, Labour cess shall be deducted at the source as per prevailing rules and rates.
12. All statutory rules and regulations such as EPF regulations, Labour Rules and Regulations, wages regulations etc. shall be followed by the contractor. The contractor will be fully responsible for any kind of penalty levied by Central/ State Govt. or any other agency for not following the statutory rules and regulation.
13. The quotation should accompany PAN Proof, GST Registration proof and a valid registration of the firm with Pb. PWD, MES, PSPCL, and PSTCL etc.
14. Payment for the work done will be made by Sr. XEN, Civil Maintenance Division, PSTCL Jalandhar.
15. The Tenderer should possess the requisite documents before the date of publishing of this Tender.
16. The undersigned reserves the right to cancel the aforesaid tender at any stage without assigning any reason.
17. In case the date of opening of tenders happens to be a holiday, the tenders will be received and opened on the next working day at the same time.
18. The competent authority reserves the right to increase/decrease the scope of work or also reject any or all the tenders so received without assigning any reason whatsoever.

19. Bidders should note that in case of award of contract they shall themselves be responsible for compliance of various provisions of EPF Act 1952 amended up to date as principal employer, GST which ever are applicable. All obligations arising on this account shall be sole responsibility of the contractor.
20. The terms and conditions of **PSEB WORK REGULATIONS 1997 along with Amendments** will be applicable on this Tender.
21. Tenders received after the due date & time, even if posted before the due date of opening shall not be entertained at all.


  
Sr. XEN / Civil  
Civil Mtc Division,  
PSTCL, Jalandhar

Endst No. 1537) 22

Date 10/08/2020

Copy of above is forwarded to the following for information and necessary action

- 1 Dy Chief / Civil, P&M Circle, PSTCL, Jalandhar.
2. Notice Board.

  
Sr. XEN / Civil  
Civil Mtc Division,  
PSTCL, Jalandhar (atn)

**DNIT for Repair of Store Office at 220 kv s/s Jamsher under Addl.SE /Store & Disposal Patiala**

S No	Description of an item	QTY	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	First class brick work in cement sand mortar 1:5 above plinth level as per CSR ref11.6	2.76	Cum	11.6	4088.20	
2	12.5mm thick cement plaster 1:4	33.96	Sqm	15.9	136.67	
3	Providing and laying vitrified floor tiles of 600mm*600mm size in light colour shades made using Double Charge technology (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 fine sand), complete. ( Design is homogenous throughout the tile body )	87.32	SQM	14.113	887.58	
4	Removing Doors and Windows (Steel or wood) with chowkhats by making recesses in walls when the wall is not to be dismantled					
a	Window of area 3 sqm and below	1	No	8.26(b)	126.79	
5	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate z sections and other sections Jindal, Hindalco, Mahavir or equivalent make approved by Engineer in Charge					
	For fixed portion and chaukhats	103.1	KG	17.45(a)	314.29	
6	For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and labour for fixing of fittings wherever required including the cost of PVC Plug / neoprene gasket required	89.01	Kg	17.45(b)	328.57	
7	Providing and fixing 12mm thick prelaminate particle board flat pressed three layer or graded wood particle board in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless	9.76	sqm	17.46(i)	853.57	
8	Cost of Aluminium fittings complete for doors, windows such as tower bolts, handless and screw etc. for these fittings (Excluding sliding bolt)	24.45	sqm	17.23(ii)	99.11	
9	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC Plug/ neoprene gasket etc. complete					
	Float glass panes of 5.5 mm thickness	0.81	sqm	17.47(i)	924.1071	
10	P/F Wire gauge 12x12 size in aluminium section etc. complete as per NS item	2.025	sqm	NS	450.39	
11	Wiring fan point without fan box in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade with step type electronic fan regulator 100watts.	1	No	34.05(i)a	876.12	
12	Wiring light point in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade.	3	No	34.05(ii)	612.72	
13	Wiring call-bell point in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts including the cost of bell push, electronic buzzer & powder coated concealed metal box for electronic buzzer).	1	No	33.05(iii)	564.73	
14	Wiring 3 pin 6 Amp. wall socket (Shuttered) point in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade complete with FRLS cable (ISI marked) overall 1 sq. mm, 1100volts grade.	3	No	34.05(iv)	466.52	
15	Supply and erection of PVC insulated single core FRLS copper conductor cable ISI marked left bare in pipe or casing of suitable size excluding the cost of supply and erection of pipe or casing. PVC insulated copper conductor single core FRLS cable (ISI marked) overall 2.5 sq.mm, 1100volts grade	80	Rm	34.09(iii)	31.34	
16	PVC insulated copper conductor single core FRLS cable (ISI marked) overall 4 sq.mm, 1100volts grade	40	Rm	34.09(iv)	45.27	

17	Wiring 3 pin 16/20 amp. power plug control (shuttered) and switch.	2	No	34.05(vi)	356.03	
18	Providing & Fixing in position 15 mm i/d bib cock of cp braas without flange (as approved by the Engineer-in-charge).	2	No	30.65(a)(ii)	818.75	
19	Providing & Fixing in position stop cock / Angle valve cp brass(as approved by the Engineer-in-charge) C.P.brass 15mm stop cock Male and female end	2	No	30.66(a)	716.96	
20	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two coats)	158.00	Sqm	16.63	79.46	
21	Preparation of plastered or concrete surface for painting (including sand papering the surface) using ready mixed cement based wall putty by applying two coats to get required finish	39.501	sqm	16.65	71.43	
22	Cement concrete 1:2:4 With stone ballast or shingle mixing by mechanical means using concrete mixer volumetric type	2.16	cum	10.13a(ii)	2431.73	
23	Centering and shuttering for flat surfaces such as suspended floors, roofs, landings, chajjas, shelves etc.	21.60	Sqm	9.80	475.00	
24	Cold twisted deformed (Ribbed/ Tor steel) Bars (Fe 500 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including bending and binding placing in position complete. (Only Labour Rate)	2.16	qtl	18.18	780.36	
25	Extra Carriage and Difference of material for coarse sand	2.63	Cum	Annexure	339.54	
26	Extra Carriage and Difference of material for coarse aggregate 13.2 mm	0.97	Cum	Annexure	261.28	
27	Extra Carriage and Difference of material for coarse aggregate 11.2 mm	0.97	Cum	Annexure	311.30	
29	Extra carriage for fine sand	2.68	Cum	Annexure	256.80	

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowlal store as per availability.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er - in - Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor