

Punjab State Transmission Corporation Limited

From:

Sr. XEN/ P&M
Civil MTC. Division,
Jalandhar.

Limited Tender Enquiry No.	42/2023-24, 43/2023-24, 44/2023-24, 45/2023-24, 46/2023-24,
Date of Receipt of Tenders	28.08.2023 up to 01:00PM
Date of opening of Tenders	28.08.2023 at 03.00 PM

To:

M/s As per overleaf.

Memo No 1532/31

Dated 10/08/2023

Subject: Limited TE No.- 42/2023-24 ,43/2023-24 ,44/2023-24 ,45/2023-24 ,46/2023-24.

You are requested to quote your lowest rates for the execution of the following works. Quotations should reach in the Office of the undersigned before 01.00 PM on due date. If this day happens to be a holiday, the quotation can be submitted on the following working day and the same shall be opened on that day. The Quotations received at the above mentioned date and time shall be opened at 03.00 PM in the presence of committee of officers/officials of the department and representatives of the contractors who want to be present.


Limited TE No.	Description of work	Estimated Cost	Earnest Money (Rs.)	Time for completion of work.
42/2023-24	Repair of store office at 220kv s/s Jamsher.	2.55 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000.	45 Days
43/2023-24	Repair of control room building at 220kv s/s Chohla sahib.	2.50 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	45 Days
44/2023-24	Repair of CO&C Building & switch house building at 132kv s/s Batala.	3.95 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	60 Days

45/2023-24	Repair and Maintenance of sub division office of civil works PSTCL, Ludhiana.	1.90 Lakh	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	45 Days
46/2023-24	Replacement of submersible pump motor at 220kv s/s Dasuya.	28,000/-	2 % of tender value rounded off to a multiple of Rs.10 on the higher side, subject to minimum Rs.5000	30 Days

General Terms & Conditions:-

1. The Tender documents cost is not charged as per Financial Advisor, PSTCL, Patiala(Budget Section) O/o No: 10 dt: 22-2-18 and Earnest Money need to be paid in the form of cash or Demand Draft drawn on any scheduled bank in the favour of Senior executive engineer, P&M Civil Maintenance Division, PSTCL Jalandhar.
2. Earnest money shall be 2% of tender value with minimum of Rs.5000/- whichever is higher. Earnest money shall be nil for work order below Rs.50,000/- as per Works Regulations. The **Earnest Money along with Documents** should be kept in envelope duly sealed super-scribed "**EARNEST MONEY**" and **Quotation** should be kept in separate envelope duly sealed super-scribed "**QUOTATION**".
3. Quotations not accompanying the EMD as per sr. no. 2 will not be entertained.
4. Tenders for part work, Conditional tenders, telegraphic tender through fax or tenders not on prescribed forms of tenders without earnest money in the required shape shall not be accepted.
5. A set of tender documents (non-transferable) containing technical specifications, general instructions, terms & conditions can be downloaded from www.pstcl.org or obtained from the office of Sr. Xen P&M Divn, PSTCL Jalandhar by dated 28.08.2023 up to 01:00 PM
6. Work shall be carried out as per PWD specifications to meet with the requirements of the work at site to the entire satisfaction of the Engineer-in-Charge.
7. GST is applicable as per Govt. norms.
8. The quoted Rate shall be valid up to 120 days and shall remain firm through to the completion of work
9. If the work is not completed within stipulated period,PSTCL shall impose 0.5% penalty per week subject to the maximum of 5% of the Total amount.
10. Security Deposit: 5% of the Gross Value of the work done will be deducted from the running bills as Security Deposit. No interest shall be payable to contractors on the amount of security deposit.
11. Income Tax, Labour cess shall be deducted at the source as per prevailing rules and rates.
12. All statutory rules and regulations such as EPF regulations, Labour Rules and Regulations, wages regulations etc. shall be followed by the contractor. The contractor will be fully responsible for any kind of penalty levied by Central/ State Govt. or any other agency for not following the statutory rules and regulation.
13. The quotation should accompany PAN Proof, GST Registration proof and a valid registration of the firm with Pb. PWD, MES, PSPCL, and PSTCL etc.
14. Payment for the work done will be made by Sr. XEN, Civil Maintenance Division, PSTCL Jalandhar.
15. The Tenderer should possess the requisite documents before the date of publishing of this Tender.
16. The undersigned reserves the right to cancel the aforesaid tender at any stage without assigning any reason.
17. In case the date of opening of tenders happens to be a holiday, the tenders will be received and opened on the next working day at the same time.
18. The competent authority reserves the right to increase/decrease the scope of work or also reject any or all the tenders so received without assigning any reason whatsoever.

19. Bidders should note that in case of award of contract they shall themselves be responsible for compliance of various provisions of EPF Act 1952 amended up to date as principal employer, GST which ever are applicable. All obligations arising on this account shall be sole responsibility of the contractor.
20. The terms and conditions of PSEB WORK REGULATIONS 1997 along with Amendments will be applicable on this Tender.
21. Tenders received after the due date & time, even if posted before the due date of opening shall not be entertained at all.





Sr. XEN / Civil
Civil Mtc Division,
PSTCL, Jalandhar

Date 10/08/20

Endst No. 1537/22

Copy of above is forwarded to the following for information and necessary action

- 1 Dy Chief /Civil, P&M Circle, PSTCL, Jalandhar.
2. Notice Board.


Sr. XEN / Civil
Civil Mtc Division,
PSTCL, Jalandhar  

Punjab State Transmission Corporation Limited
DNIT for Repair and Renovation of COC Building and SHB at 132 kv s/s Batala

S No	Qty	Description of an Item	Unit	CSR Ref	Departmental rate	Rate to be quoted by contractor
1	29.98	Dismantling of floor tiles at any floor of the building, laid in cement mortar including dismantling of cement concrete base	sqm	30.95	96.43	
2	35.2	Dismantling of wall tiles at any floor of the building, laid in cement mortar including scraping of cement plaster and disposal of malba at a suitable place within a distance of 100 Mtrs of the complex complete in all respect.	sqm	30.94	92.86	
3	29.98	12.5 mm thick cement plaster 1:4	sqm	15.9	136.67	
4	29.98	P/FAnti-skid floor tiles 10mm thick in flooring skirting and dado in 12.5mm thick cement plaster 1:3 in base and jointed with whitecement slurry in joints including corners angles and beading	sqm	14.72	557.22	
5	35.2	Providing and fixing 1st quality ceramic glazed wall tiles conforming to fsize 300x450 mm assteps and dados over 12 mm thick bed of cement Mortar 1:4approved by Engineer-in-Charge in	sqm	14.127	677.74	
6	29.98	Dismantling cement conglomerate floors 25mm to 50mm thick including concrete base.	sqm	8.16	97.32	
7	81.82	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate z sections and other sectionsJindal, Hindalco, Mahavir or equivalent make approved by Engineer in Charge	kg	17.45(a)	314.28	
8	36.69	For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and labour for fixing of fittings wherever required including the cost of PVC Plug / neoprene gasket required	kg	17.45(b)	328.57	
9	3.67	Providing and fixing 12mm thick prelaminate particle board flat pressed three layer or graded wood particle board in paneling fixed in aluminium doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete	sqm	17.46(i)	853.57	
10	10.94	Cost of Aluminium fittings complete for doors, windows such as tower bolts, handless and screw etc. for these fittings (Excluding sliding bolt)	sqm	17.23(ii)	99.11	
11	7.56	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC Plug/ neoprene gasket etc. complete	sqm	17.47(i)	924.1	
12	1.96	P/F Wire gauge 12x12 size in aluminium section etc. complete as per NS item	sqm	ns	450.39	
13	6	Wiring light point in PVC insulated copper conductor singl core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade.	no	34.05(ii)	612.73	
14	8	Wiring 3 pin 6 Amp. wall socket (Shuttered) point in PVCinsulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade complete with FRLS cable (ISI marked) overall 1 sq. mm, 1100volts grade.	no	34.05(iv)	466.52	

15	40	PVC insulated copper conductor single core FRLS cable (ISI marked) overall 4 sq.mm, 1100volts grade	mm	34.09(iv)	45.27	
16	4	Wiring 3 pin 16/20 amp. power plug control (shuttered) and switch.	no	34.05(vi)	356.03	
17	1	Sheet metal double door S.P. & N. distribution board (dust protected) provided with bus bar, neutral link and din bar, suitable for incorporating MCB's/ RCBO/ RCCB's, 12way each as per csr	no	33.17(iii)	1523.75	
18	10	Providing and laying, jointing fixing and testing G.I. Pipe lines B-Class including cost of specials such as tees, bends, sockets, elbows etc. testing, cutting, threading Inside building complet15mm i/d	mtr	28.36(a)	184.94	
19	85	Providing and laying, jointing fixing and testing G.I. Pipe lines B-Class including cost of specials such as tees, bends, sockets, elbows etc. testing, cutting, threading Inside building complet25mmi/d	mtr	28.36(b)	327.12	
20	10	Providing and laying, jointing fixing and testing G.I. Pipe lines B-Class including cost of specials such as tees, bends, sockets, elbows etc. testing, cutting, threading Inside building complet20mmi/d	mtr	28.36(b)	230.7	
21	2	Providing, fixing and jointing G.I union complete on all respect15mm i/d G.I union	no	28.40(a)	81.25	
22	5	Providing, fixing and jointing G.I union complete on all respect20mm i/d G.I union	no	28.40(b)	134.67	
23	3	Providing, fixing and jointing gun-metal peet valves (Heavy Pattern) with hand wheels, on G.I. Pipe lines laid in the ground or inside buildings including all carriages complete.20mm i/d G.I union	no	28.43(b)	502.38	
24	4	Providing and fixing in position Chinaware European type water closet P trap or S trap (to the approval of the Engineer-in-charge) suite-consisting of 10 ltr. PVC flushing cistern supported on angle iron bracket, short bend 32 mm dia	no	30.4	4267.86	
25	4	Providing and fixing jet spray with 2'-6" long PVC pipe.With C.P. Brass nut	no	30.8(a)	425	
26	3	Providing and fixing in position best Indian make white ordinary lavatory suites consisting of C.P. brass waste 32mm dia, pair of angle iron bracket with one C.P. brass tap complete.Size 550 mm x 400 mm	no	30.32(ii)	3226.79	
27	2	Providing & fixing in position best Indian make (to be approval of the Engineer-incharge) vitreous Chinaware white flat back or angular lipped front urinal size 440 x 315 x 265 mm C.P. brass flexible tube connection 450 mm long.	no	30.15	2666.96	
28	6	Providing & Fixing in postion 15 mm i/d bib cock of cp braas without flange (as approved by the Engineer-in-charge).	no	30.65(a)(ii)	818.75	
29	30	Providing, Stringing out U.P.V.C. Pipes casting asper IS:15328-2003 class-SN-8 along the trenches and laying the same in Trenches to correct alignment and gradients, cutting and jointing including cost of specials complete as per specifications.110mm o/d pipe	mtr	30.74(iii)b	265.88	
30	6	Providing & Fixing in postion stop cock / Angle valve cp brass(as approved by the Engineer-incharge) C.P.brass 15mm stop cock Male and female end	no	30.66(a)	716.96	

31	2	Providing & Fixing in position best indian make bevelled edge 5mm thick mirror mounted on 4mm thick Cardboard sheet ground fixed in position by means of 4 nos. chromium plated brass screws and washers .Size 600mmx450mm	no	30.61(a)	1070.53	
32	2	Providing and fixing in position towel rails of approved make including cutting and making good the walls etc CP brass Rails size 15mm dia	no	30.58(a)	1374.11	
33	2	Providing and fixing in position gully traps fixed in cement concrete 1:4:8 complete with Grating 150mm x 150mm, 100mm internal Diametre S.W.gully trap with H.C.I. grating and cast iron cover weighing approximately 7.26 kg. and frame clear opening 300mm x 300mm and out of side size 330mm x330mm	no	30.99(a)	1635.71	
34	6	Providing and fixing in position S.S grating with Frame of approved brand	no	30.80	98.8	
35	614.51	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two coats)	sqm	16.63	79.46	
35	153.62	{Preparation of Plastered or concrete surface for paining using ready mixed cement based wall putty by applying to coat to get required finish	sqm	16.65	71.43	
37	307.26	Scraping White wash and colour wash	sqm	8.31 a	6.25	
38	519.4	finishing wall with acrylic smooth exterior paint of reqired shade with two coat applied @ 1.67 litre/10 sqm over and including base coat of water proofing cement paint applied @ 2.20 kg/	sqm	16.59	107.14	
39	2	Supplying and Fixing exhaust fan 12" crompton make as per NS item	no	NS	1772	
41	1.52	Extra carriage for fine sand	cum	Annex	256.8	
42	0.65	Extra Carriage for cement	mt	Annex	380.45	

Notes: -

1. These rates are through rates exclusive of cement and steel that shall be issued by the PSTCL from Jamsher/Ablowal store free of cost as per availability
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er - in - Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor