

DNIT for Replacement of Plinth for sub station Transformer for various Sub Stations under P&M Circle ,Amritsar.

S.No	Qty	Description	UNIT	CSR ref	Departmental Rate	Rate to be quoted by contractor
1	10.13	Dismantling Concrete Cement concrete plain 1:3:6 mix	cum	8.6 c	871.43	
2	10.86	Earth work in excavation in foundations trenches etc. in all kinds of soil where Pick-Jumper work is not involved and not exceeding 2.0 metres depth including dressing of bottom and sides of trenches, stacking the excavated soil clear from the edge of excavation and subsequent filling around masonry in 15	cum	6.6	162.5	
3	2.52	Cement concrete 1:5:10 With stone aggregate 40mm gauge mixing by mechanical means using concrete mixer volumetric type	cum	10.9bil	2304.99	
4	11.77	Cement concrete 1:2:4 With stone ballast or shingle mixing by mechanical means using concrete mixer volumetric type	cum	10.13ail	2429.79	
	17.28	Shuttering for faces of concrete foundations and foundation beam & plinth beam (vertical or battering)	sqm	9.1	187.5	
6	24.48	Centering and shuttering for columns (Square or rectangular or poly gonal in plain)	sqm	9.4	425.89	
7	3.78	Cold twisted detormed (Ribbed/ Tor steel) Bars (Fe 500 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including bending and binding placing in position complete. (Only Labour Rate)	qtl	18.18	780.36	
8	3.96	First class burnt brick work laid in cement sand mortar 1:5 in foundation and plinth	cum	11.5	4087.77	
9	22.95	12.5 mm thick cement plaster 1:5	sqm	15.10	136.45	
10	8.8	20 mm thick cement plaster 1:5	sqm	15.21	183.06	
11	31.75	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two or more coats)	sqm	16.63	79.46	
12	81	Providing & Fixing of 10 gauge welded mesh of 25mm x 25mm size fixed on steel glazing with MS flat 20mm x 6mm beeding complete in all respect including painting two coats with Synthetic Enamel Paint and Priming Coat	sqm	18.31	584.82	
13	14.5755	Steel work fixed independently without connecting plates including cutting hoisting and fixing in position FLATS	qtl	18.1(b)	5416	
14	2.03	Steel work fixed independently without connecting plates including cutting hoisting and fixing in position Tees, angles & channels	qtl	18.1(c)	5294.64	
15	26.2	Applying priming coat with metal primer on new steel or iron work including preparation of surface.	sqm	16.20	21.43	
16	26.2	Painting two or more coats excluding priming coat with ready mixed paint for metallic surfaces in all shades on steel or Iron work	sqm	16.21	57.14	

17	3	Providing and Fixing of U/C Fencing Gate 1.00 mtr wide for station Transformer.	No.	N.S.	3073	
18	18	Less Iron Scrap	kg	N.S.	-20	
19	5.3	Extra Carriage and difference of material for coarse sand	Cum	AOR	350.29	
20	5.3	Extra Carriage and difference of material for crusher 13.2mm	Cum	AOR	131.79	
21	5.3	Extra Carriage and difference of material for crusher 11.2mm	Cum	AOR	214.33	
22	2.47	Extra Carriage and difference of material for stone metal 40mm	Cum	AOR	136.75	
23	2.8	Extra Carriage for Fine sand	Cum	AOR	256.8	
24	4.65	Extra Carriage for Cement	MT	AOR	439.56	
25	0.3	Extra Carriage of Steel	MT	AOR	286.03	

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowl store.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor