

DNIT for Maintenance of TLSC Civil Sub-Division Office Jalandhar

| S No | Description of an Item | QTY | Unit | CSR Ref | Total Rate | Rate to be quoted by contractor |
|------|---|--------|------|-----------|------------|---------------------------------|
| 1 | Providing and laying vitrified floor tiles of 600mm*600mm size in light colour shades made using Double Charge technology (thickness to be specified by the manufacturer) with water absorption's less than 0.08% and conforming to IS : 15622 of approved make in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 fine sand), complete. (Design is homogenous throughout the tile body). | 44.00 | SQM | 14.113 | 887.58 | |
| 2 | Scraping of Cement Plaster | 232.20 | Sqm | 8.31(c) | 32.14 | |
| 3 | 12.5mm thick cement plaster 1:4 | 232.20 | Sqm | 15.9 | 136.67 | |
| 4 | P/Anti-skid floor tiles 10mm thick in flooring skirting and dado in 12.5mm thick cement plaster 1:3 in base and jointed with whitecement slurry in joints including corners angles and beading | 6.25 | Sqm | 14.72 | 557.22 | |
| 5 | Providing and fixing 1st quality ceramic glazed wall tiles conforming to fsize 300x450 mm assteps and dados over 12 mm thick bed of cement Mortar 1:4approved by Engineer-in- | 18.00 | Sqm | 14.127 | 677.74 | |
| 6 | Removing Doors and Windows (Steel or wood) with chowkhats by making recesses in walls when the wall is not to be dismantled | | | | | |
| a | Door of area 3 sqm and below | 6 | No | 8.26(a) | 199.11 | |
| b | Window of area 3 sqm and below | 5 | No | 8.26(b) | 126.79 | |
| 7 | Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate z sections and other sectionsJindal, Hindalco, Mahavir or equivalent make approved by Engineer in Charge | 148.58 | KG | 17.45(a) | 314.29 | |
| 8 | For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and labour for fixing of fittings wherever required including the cost of PVC Plug / neoprene gasket required | 202.16 | Kg | 17.45(b) | 328.57 | |
| 9 | Providing and fixing 12mm thick prelaminate particle board flat pressed three layer or graded wood particle board in paneling fixed in aluminium doors, windows shutters and partition | 3.44 | sqm | 17.46(i) | 853.57 | |
| 10 | Cost of Aluminium fittings complete for doors, windows such as tower bolts, handless and screw etc. for these fittings (Excluding sliding | 21.72 | sqm | 17.23(ii) | 99.11 | |
| 11 | Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC Plug/ neoprene gasket etc. complete | 9.21 | sqm | 17.47(i) | 924.107 | |
| 12 | P/F Wire gauge 12x12 size in aluminium section etc. complete as per NS item | 6.3525 | sqm | NS | 450.39 | |
| 13 | Wiring fan point without fan box in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade with step type electronic fan regulator 100watts.(Rs.785x25%)=981.25 | 3 | No | 34.05(i)a | 876.12 | |

| | | | | | | |
|----|---|-----|----|--------------|---------|--|
| 14 | Wiring light point in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade. | 6 | No | 34.05(ii) | 612.72 | |
| 15 | Wiring 3 pin 6 Amp. wall socket (Shuttered) point in PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, 1100volts grade complete with FRLS cable (ISI marked) overall 1 sq. mm, 1100volts grade. | 6 | No | 34.05(iv) | 466.52 | |
| 16 | Wiring 3 pin 16/20 amp. power plug control (shuttered) and switch. | 4 | No | 34.05(vi) | 356.03 | |
| 36 | PVC insulated copper conductor single core FRLS cable (ISI marked) overall 1.5 sq. mm, | 100 | Rm | 34.09(ii) | 20.89 | |
| 17 | Supply and erection of PVC insulated single core FRLS copper conductor cable ISI marked left bare in pipe or casing of suitable size excluding the cost of supply and erection of pipe or casing. PVC insulated copper conductor single core FRLS cable (ISI marked) overall 2.5 sq. mm, 1100volts grade. Supply and erection of PVC insulated single core FRLS copper conductor cable ISI marked left bare in pipe or casing of suitable size excluding the cost of supply and erection of pipe or casing. PVC insulated copper conductor single core FRLS cable (ISI marked) overall 2.5 sq. mm, 1100volts grade. Supply and erection of PVC insulated single core FRLS copper conductor cable ISI marked left bare in pipe or casing of suitable size excluding the cost of supply and erection of pipe or casing. PVC insulated copper conductor single core FRLS cable (ISI marked) overall 2.5 sq. mm, 1100volts grade. | 100 | Rm | 34.09(iii) | 31.34 | |
| 18 | Supplying and Erection of Miniature circuit breaker single pole 0.5 to 4amp. (Breaking capacity 10kA, Curve-C) suitable for 240/ 415 | 3 | no | 34.16a(i) | 251.92 | |
| 19 | Providing, fixing and jointing gun-metal peet valves (Heavy Pattern) with hand wheels, on G.I. Pipe lines laid in the ground or inside buildings including all carriages complete. 20mm i/d G.I union | 1 | No | 28.43(b) | 502.38 | |
| 20 | Providing and fixing in position Chinaware European type water closet P trap or S trap (to the approval of the Engineer-in-charge) suite-consisting of 10 ltr. PVC flushing cistern supported on angle iron bracket, short bend 32 mm dia | 1 | No | 30.4 | 4267.86 | |
| 21 | Providing and fixing jet spray with 2'-6" long PVC pipe. With C.P. Brass nut | 1 | no | 30.8(a) | 425 | |
| 22 | Providing and fixing in position best Indian make white ordinary lavatory suites consisting of C.P. brass waste 32mm dia, pair of angle iron bracket with one C.P. brass tap complete. Size 550 mm x 400 mm | 1 | No | 30.32(ii) | 3226.79 | |
| 23 | Providing & fixing in position best Indian make (to be approval of the Engineer-in-charge) vitreous Chinaware white flat back or angular lipped front urinal size 440 x 315 x 265 mm C.P. brass flexible tube connection 450 mm long. | 1 | No | 30.15 | 2666.96 | |
| 24 | Providing & Fixing in position 15 mm i/d bib cock of cp braas without flange (as approved by the Engineer-in-charge). | 3 | No | 30.65(a)(ii) | 818.75 | |

| | | | | | | |
|----|--|----------|-----|-------------|---------|--|
| 25 | Providing, Stringing out U.P.V.C. Pipes casting as per IS:15328-2003 class-SN-8 along the trenches and laying the same in Trenches to correct alignment and gradients, cutting and jointing including cost of specials complete as per specifications. 110mm o/d pipe | 15 | MTR | 30.74(iii)b | 265.88 | |
| 26 | Providing & Fixing in position stop cock / Angle valve cp brass(as approved by the Engineer-incharge) C.P.brass 15mm stop cock Male and female end Providing & Fixing in position stop cock / Angle valve cp brass(as approved by the Engineer-incharge) C.P.brass 15mm stop cock Male and female end Providing & Fixing in position stop cock / Angle valve cp brass(as approved by the Engineer-incharge) C.P.brass 15mm stop cock Male and female end | 3 | No | 30.66(a) | 716.96 | |
| 27 | Providing and fixing in position tower rails or approved make including cutting and making good the walls etc CP brass Rails size 15mm dia 600mm long | 1 | no | 30.58(a) | 1374.11 | |
| 28 | Providing and fixing in position S.S grating with Frame of approved brand | 3 | No | 30.80 | 98.80 | |
| 29 | Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two coats) | 341.33 | Sqm | 16.63 | 79.46 | |
| 30 | Preparation of plastered or concrete surface for painting (including sand papering the surface) using ready mixed cement based wall putty by applying two coats to get required finish | 170.6625 | sqm | 16.65 | 71.43 | |
| 31 | Supplying and Fixing exhaust fan 12" crompton make as per NS item | 1.00 | no | NS | 1772.00 | |
| 32 | Providing and laying 3 layer PPR pipe of 25 mm dia | 25.00 | mtr | 28.39A(c) | 171.28 | |
| 33 | Providing and laying 3 layer PPR pipe of 20 mm dia | 15.00 | mtr | 28.39A(b) | 135.48 | |
| 34 | Supplying and Fixing Ceiling fan 1400mm sweep of crompton make as per NS item | 2.00 | no | NS | 1506.00 | |
| 35 | Supply & Fixing General purpose tube fitting of crompton make on wall model no. DIL B124 14 EB9 (1*36 WATT) | 5.00 | no | NS | 410.00 | |
| 37 | Extra carriage for fine sand | 5.17 | Cum | Annex | 256.80 | |
| 38 | Extra Carriage for cement | 1.95 | MT | Annex | 138.43 | |

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowlal store(As per Availability).
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er - In - Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor