

**DNIT for Replacement of 1 set of 220 kv Breaker foundation at 220 kv s/s Kartarpur.**

S No	Description of an Item	QTY	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Earthwork In Excavation in all kind of soil	10.21	Cum	6.6	162.50	
2	PCC 1:6:12 with 40 mm stone aggregate	0.97	Cum	10.8(b)(ii)	2309.18	
3	Cold Twisted deformed bars FE 500 for RCC work including cutting ,bending and placing in position in complete	2.18	Qtl	18.18	780.36	
4	Shuttering or faces of concrete foundation	3.60	Sqm	9.1	187.5	
5	Centring and shuttering for Column	15.84	Sqm	9.4	425.89	
6	RCC M20	5.71	cum	10.15	2809.51	
7	Fixing of template	4	No	NS	200	
8	Extra Carriage for Cement	2.05	MT	Annexure	313.21	
9	Extra Carriage for Steel	0.218	MT	Annexure	152.63	
10	Extra Carriage for coarse sand	2.46	Cum	Annexure	404.85	
11	Extra Carriage for coarse aggregate 13.2 mm	2.43	Cum	Annexure	230.10	
12	Extra Carriage for coarse aggregate 11.2 mm	2.43	Cum	Annexure	281.65	
13	Extra Carriage for Stone Ballast 40 mm	0.96	Cum	Annexure	235.05	
14	Extra carriage for fine sand	0.48	Cum	Annexure	256.80	

**Notes:-**

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowlal store.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

**Signature of vendor**