

DNIT FOR Repair & Maintenance of SHB 220kV Sub-Station Jadla

S No.	Qty.	Description of Item	Units	CSR Ref	CSR/ Deptt Rates	Rate to be quoted by contractor
1	420.48	Regrading terracing of mud plaster covered with tiles or bricks in cement by dismantling tiles or bricks, removing mud plaster, preparing the surface of mud plaster to proper, slope, relaying mud plaster Gobri leaping and tiles or bricks grouted in cement mortar 1:3 (1 cement and 3 fine sand)	Sqm	31.11	348.68	
2	3.89	Replacement of worn out tiles with new one	1000 No.s	NS	6166.05	
3	420.48	Providing and fixing polythene sheet	Sqm	NS	20.00	
4	3.53	Dismantling concrete:- Reinforced cement concrete	cum	8.6 e	1967.86	
5	3.53	Reinforced cement concrete M-20 mechanically batch mixed using batch type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centring and shuttering in foundation and plinth.	cum	10.15	2807.51	
6	2.68	Shuttering for faces of concrete foundations and foundation beam & plinth beam (vertical or battering)	sqm	9.6	339.29	
7	28.20	Centering and shuttering for flat surfaces such as suspended floors, roofs, landings, chajjas, shelves etc.	sqm	9.8	475.00	
8	2.82	Cold twisted deformed (Ribbed/ Tor steel) Bars (Fe 500 grade as per IS 1786-2008) , for R.C.C works, where not including in the complete rate of RCC including bending and binding placing in position complete	qtl	18.18	780.36	
9	1000	Providing & fixing of Water Storage Tank	LTR	30.97 a li	9.64	
10	6	Providing & Fixing in position stop cock / Angle valve of approved make (to the approval of Engineer-in-charge) complete in all respect. C.P.brass 15mm stop cock Male and female end	No.	30.66 a	716.96	

11	50	Providing and laying, jointing, fixing, testing ISI Marked G.I. Pipe (as per IS 1239) BClass, including cost of Specials such as tees, bends, sockets elbow etc., cutting, threading and testing in trenches in the ground complete. 15mm i/d	Mtr	28.36 a	184.94	
12	10	Providing, fixing and jointing G.I Union Couplings(of approved make with the approval EIC) as per IS 1879 in G.I. Pipe lines complete in all respect. 15mm i/d G.I. Union	No.	28.40 a	81.25	
13	12	P/F Anti-skid floor tiles 10mm thick in flooring skirting and dado in 12.5mm thick cement plaster 1:3 in base and jointed with white cement slurry in joints including corners angles and beading	sqm	14.72	557.22	
14	2	P/F in position chinaware European type water closet P trap or S trap (to the approval of the Engg.-in-charge) suite-consisting of 10 ltr. PVC flushing cistern supported on angle iron bracket, short bend 32mm dia	No.	30.4	4267.86	
15	8	Providing & Fixing in position C.I.bib cock as per IS:210 with stainless steel spindle of approved make (to the approval of Engineer-incharge) complete in all respect.	No.	3.65 a	166.96	
16		Extra carriage and difference of rates				
(i)	2	Cement	MT	Annex	357.32	
(ii)	2.25	Fine sand	cum	Annex	256.80	
(iii)	1.52	Coarse sand	cum	Annex	225.66	
(iv)	1.5	crusher 13.2mm	cum	Annex	342.62	

(v)	1.5	crusher 11.2mm	cum	Annex	348.47	
(vi)	3.89	bricks/tiles	No.	Annex	875.58	
(vii)	0.28	steel	MT	Annex	264.67	

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowlal store as per availability.
 2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
 3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
 4. GST will be applicable as per Govt. norms and will be paid extra.
- Rates of taxes and duties if any applicable must be mentioned clearly otherwise
- 5 maximum rate shall be taken into account for evaluation

Signature of vendor