Estimate for Repair Of Old U Fencing at 220 kv s/s Jamsher.									
SN		Qty	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor			
1	Dismantling of brick work in cement	6.04	cum	8.5(b)	608.93				
2	Scraping of bricks Dismantled from brick work	1.160	1000nos	8.31(e)	1410.71				
3	Dismantling of concrete for Removal of Old Angle	0.93	Cum	8.6 (d)	1218.75				
4	PF/ Angle iron post 75x75x8 3.12 mtr @4.50kg/Rm	138.84	kg	NS	63				
5	P/F Angle iron post 50x50x6 mm 3.12 mtr. Long @4.50kg/Rm (15+12)	351.00	kg	NS	63				
6	P/F Angle iron post 50x50x6 mm 2.60 mtr. Long @4.50kg/Rm (20+8)	117.00	kg	NS	63				
7	First class brick work in cement sand mortar 1:5 above plinth level	4.23	Cum	11.6	4211.42				
8	Centring and shuttering of block for grouting of Angle Iron	8.10	Sqm	9.8	475.00				
9	Cement concrete 1:2:4 for grouting of Angles as per CSR 10.13	2.76	Cum	10.13(i)	2331.73				
10	12.5 MM thick cement plaster 1:5 OLD Toe Wall	290.50	sqm	15.10	136.48				
11	Priming coat over mettalic surface including preperation of surface with special quality paint.	21.94	Sqm	16.20	21.43				
12	Scraping of Old Paint form Angles for new one	64	Sqm	16.36	90.18				
13	Painting two coats with aluminium paint of special quality	85.94	Sqm	16.25 (a)	56.25				
14	P/F wire netting mesh of G.I. ,12 Gauge 50x50 Mesh 180 cm high complete as per NS Item	350.00	Rmt	NS	426				
15	P/F Barbed wire 4 rows over angle for U-Fencing complete AS per NS item	350.00	Rmt	NS	88	,			
16 16	Clearing jungle manually including uprooting rank vegetation, grass, woody vegetation up to 30 cm girth measured at height of 1 m above ground level and removal of rubbish up to distance of 50 m outside the periphery of the area cleared	700.00	Sqm	32.4 C	7.11				
17	Extra carriage for fine sand as per AOR	5.71	Cum	Annexure	256.80				
40	Extra carriage for Aggregate as per	3.72	Cum	Annexure	463.38				
19	ecover of scrap	100.00	kg	Annexure	-20.00				
20 '	ecovery of bricks (5350+10%+1%)	1.160	nos	Annexure	-5943.85				

23	Difference in material rates for crushed bajri 13.2 mm	1.24	cum	Annexure	-203.60	
23	Difference in material rates crushed bajri 113.2 mm	1.24	cum	Annexure	-121.11	zi en ik
23	Difference in material rates coarse sand	1.24	cum	Annexure	14.86	
23	Difference in material rates bricks	4.421	nos	Annexure	865.00	

Notes: -

- 1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowal store as per availability.
- 2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er in Charge.
- 4. GST will be applicable as per Govt. norms and will be paid extra.
- Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor