

DNIT for Stub strengthening, repair of rusted offchutes, raising of muff concrete of various 132/220 KV towers under AEE/TL, Makhu.

Detail of Quantity and Amount

S No	QTY	Description of an Item	Unit	CSR Ref	CSR Rate	Rate to be quoted by contractor
1	6	Repair & raising of single offchute including welding of rusted/damaged angle iron offchutes of transmission towers (size 230x230x1250 mm)	each	AOR	4119.00	
2	17	Repair & raising of Muffe concrete 300x300x1Mtr high	each	AOR	4806.00	
3	14	Repair & raising of Muffe concrete of 220 450x450x300mm high	each	AOR	1102.00	
4	27	STUB STRENGTHING OF RUSTED TOWER LEGS ,DISMANTLING AND REMAKING THE CONCRETE STUBS of size 300x300 mm x1 mt	each	AOR	7861.00	

Notes: -

1. These rates are through rates inclusive of Cement & Steel.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra by PSTCL.

5 Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor