

**DNIT for Replacement of 6 Nos. 132 KV PT foundations and 2 Nos. M-Box Foundations at 220 kv S/S Sarna.**

S No	Description of an Item	QTY	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Earthwork In Excavation In all kind of soil	10.97	Cum	6.6	162.50	
2	PCC 1:6:12 with 40 mm stone aggregate	2.18	Cum	10.8b(II)	2309.18	
3	Supply of MS Bolts 20mm dia	62.7	KG	18.15	69.64	
4	Centring and shuttering for Column	37.29	Sqm	9.4	425.89	
5	Cement concrete 1:2:4	10.02	cum	10.13 a ii	2431.73	
6	Fixing of template	6	No	NS	200.00	
7	Extra carriage for fine sand as per AOR	1.08	Cum	Annexure	256.80	
8	Extra carriage and difference of material for crusher 13.2 mm	4.51	Cum	Annexure	-42.78	
9	Extra carriage and difference of material for crusher 11.2 mm	4.51	Cum	Annexure	-31.96	
10	Extra carriage and difference of material for coarse sand	4.51	Cum	Annexure	128.22	
11	Extra carriage and difference of material for stone metal 40 mm	2.16	Cum	Annexure	-100.57	
12	Extra carriage for Cement	3.55	MT	Annexure	529.51	

**Notes: -**

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowal store as per availability.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.

5 Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

**Signature of vendor**