

DNIT for protection of Tower No.61 of 220 KV GVK Bottianwala line.

S No	Description of an item	QTY	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Earth work in excavation in foundations, trenches etc. in all kinds of soil where pick jumper work is not involved and not exceeding 2.0 metres dep Retaining Wall	38.84	cum	6.6	162.50	
2	Cement Concrete 1:8:16 with 40mm gauge stone aggregate. Retaining Wall	4.91	cum	10.6 b(II)	2310.69	
3	First class burnt brick work laid in cement sand mortar 1:6 in foundation and plinth. Retaining Wall	29.34	cum	11.3(i)	4084.52	
4	First class burnt brick work laid in cement sand mortar 1:6 above foundation and	19.65	cum	11.4(i)	4206.84	
5	Conglomerate floor 50 mm thick cement concrete topping 1:2:4	100.00	Sqm	14.7	223.37	
6	Extra Carriage for coarse sand	14.50	Cum	Annexure	463.7	
7	Extra Carriage for coarse aggregate 13.2 mm	2.25	Cum	Annexure	325.27	
8	Extra Carriage for coarse aggregate 11.2 mm	2.25	Cum	Annexure	354.18	
9	Extra Carriage for Stone Ballast 40 mm	4.91	Cum	Annexure	323.7	
10	Extra carriage for fine sand	2.46	Cum	Annexure	256.8	
11	Extra carriage for Cement	5.01	MT	Annexure	388.16	
12	Difference of material rate for bricks	23.52	No.s	Annexure	642.79	

Notes: -

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsheer/ablowal store.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise

Signature of vendor