

**Punjab State Transmission Corporation Limited**

**DNIT for Replacement of 1 Set 66 kv SF-6 Breaker foundation at 220 KV S/Stn Butari under P&M Division Butari**

S.no	Qty	Description of an Item	Unit	CSR REF	Deptt Rate	Rate to be quoted by contractor
1	4.32	Earth work in excavation in foundations trenches etc. as per CSR Ref No 6.6	Cum	6.6	162.50	
2	0.29	PCC 1:6:12 with 40 mm stone aggregate as per CSR Ref No 10.8b i	Cum	10.8 B I	2209.18	
3	0.13	Cold Twisted deformed bars FE 500 for RCC work including cutting ,bending and placing in position in complete as per CSR Ref No 18.18	Qtl	18.18	780.36	
4	2.64	Shuttering or faces of concrete foundation as per CSR Ref No 9.1	Sqm	9.1	187.50	
5	9.60	Centering and shuttering for Column as per CSR Ref No 9.4	Sqm	9.4	425.89	
6	2.48	RCC M20 as per CSR Ref No 10.15	Cum	10.15	2809.57	
7	2.00	Fixing of template NS Item	Each	NS	200.00	
10	1.42	Extra Carriage and difference of material for coarse sand	Cum	AOR	516.80	
11	1.42	Extra Carriage and difference of material for crusher 13.2mm	Cum	AOR	336.87	
12	1.42	Extra Carriage and difference of material for crusher 11.2mm	Cum	AOR	364.23	
13	0.20	Extra Carriage and difference of material for stone metal 40mm	cum	AOR	326.57	
14	0.10	Extra Carriage for Fine sand	Cum	AOR	256.80	
15	0.85	Extra Carriage for Cement	MT	AOR	503.82	
16	0.13	Extra Carriage of Steel	MT	AOR	327.31	

**Notes: -**

1. These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from Jamsher/ablowl store as per availability.
2. PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
3. For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
4. GST will be applicable as per Govt. norms and will be paid extra.
5. Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.

Signature of vendor