



PUNJAB STATE TRANSMISSION CORPORATION LIMITED

Regd. Office: PSEB Head Office, The Mall Patiala-147001, Punjab, India.

Corporate Identity Number: U40109PB2010SGC033814 (www.pstcl.org)

(O/o CAO/Finance & Audit/Commercial & Regulatory Cell, 3rd Floor, Shakti Sadan, Patiala)

Fax/Ph.No. 0175-2970183 Email: fa@pstcl.org

To

✓ Registrar,
Punjab State Electricity Regulatory Commission,
Site No. 3, Sector 18-A, Madhya Marg,
Chandigarh. Pincode-160018.
Tel No. 0172-2861800

Memo No. 842 / CAO/F&A/Comml./CIP- 3rd

Dated: 21/09/2022

Subject: Interim Order in Petition No. 50 of 2022 (Approval of PSTCL's Business Plan including Capital Investment Plan for MYT Control Period (FY 2023-24 TO FY 2025-26) under Regulation 9 of PSERC (Terms and Conditions of Determination of Generation, Transmission, Wheeling and Retail Supply Tariff) Regulations, 2019).

Please refer to your office email dated 09.09.2022 vide which Interim Order dated 06.09.2022 on above cited subject was sent.

In this regard, additional information/clarifications as desired by the Commission are attached herewith for the kind consideration of the Hon'ble PSERC.

DA/As above(12 copies)

Judhij
CAO/Finance & Audit,
PSTCL, Patiala.

PSTCL Business Plan and Capital Investment Plan for 3rd Control Period- Additional information/clarification

1. PSTCL to submit the scheme wise data in excel format

PSTCL Reply: Scheme wise data is enclosed in CD attached, moreover the same has also been sent via email dated 22.09.2022.

2. Regulation 9.4 of the MYT Tariff Regulations, 2019 specifies that the business plan of the transmission business should include the following:

- "a) Future plans of the company including efficiency improvement measures proposed to be introduced and technical requirement such as meeting reactive power requirements;
- (b) Plan for reduction in transmission losses;
- (c) Plan for improvement in quality of transmission service and reliability, metering arrangements and any other new measure to be initiated by the Licensee, e.g. automation, IT initiatives etc.;
- (d) Capital Investment Plan based on the above;
- (e) Man Power Plan."

It is observed that the Business Plan submitted by PSTCL for its Transmission and SLDC business does not contain Future plans, Loss Reduction Plan, Man Power Plan etc. PSTCL is required to submit the details of various components of the business plan in line with the above Regulation.

PSTCL Reply: It is only after consideration of all the points above, that PSTCL has framed its extensive capital expenditure requirements. The said CIP gives timelines for completion of spill-over schemes. Apart from the above, PSTCL has given its entire philosophy/considerations of future load growth in the state, intrastate generation capacity and requirement of power to be procured from interstate generating stations. Keeping the above in mind, PSTCL has undertaken load flow studies, wherein system constraints have been identified and augmentation/strengthening/upgradation has been proposed appropriately in due consideration of technical standards prescribed by CEA/Honourable PSERC. The load flow simulation results had already been enclosed as the part of main submission.

So far, as some of the specific elements are concerned, PSTCL submits the following:

Judhi.

- a. Future plans of the company including efficiency improvement measure proposed to be introduced and technical requirement such as meeting reactive power requirements: In line with the CPRI report on assessment of capacitor requirement in Northern region for year 2019-20 issued in March 2022, PSTCL is studying to install capacitor banks at its various substations detailed out in the report. The work has been included as under study in the proposed CIP plan 2023-26. Upon finalizing the install locations, PSTCL will propose the schemes and submit the same for kind consideration by the honourable commission. The CPRI report is enclosed as **Annexure - 1**.
- b. Plan for reduction in transmission losses: Transmission losses of PSTCL are 2.31% against all India average of 2.31%. In case pursuant to development of the proposed network in case the need for undertaking such measures, PSTCL shall submit such schemes in its subsequent petitions.
- c. Plan for improvement in quality of transmission service and reliability, metering arrangements and any other new measure to be initiated by the Licensee e.g. automation, IT initiatives etc.: PSTCL has already employed substation automation technology and RHMI (Remote Human Machine Interface) at two of its 400 kV substations (Dhuri and Rajpura), wherein the operation and control of 400 kV substation Dhuri is being carried out at Rajpura and the staff in shift duty at 400 kV substation has been reduced. RHMI of 3 Nos. PSTCL substations Nakodar, Makhu and Muktsar is proposed in the MYT (Annexure-B, Sr. No. 3). Automation of two substations (namely 220 kV Budhlada and Gurdaspur) is in tendering stage and automation of remaining 220 kV substations is already in the spill-over works list (Appendix-B (Spill Over), Sr. No. 72 (90 Nos. PSTCL grids (220 kV) to be provided with SAS. Report already sent for PSDF funding, if approved, these stations will be upgraded.)). However, these capital plans have been linked with PSDF funding at this moment. In addition, improvement in metering arrangement for all interface points is being carried out under SAMAST project through which existing energy meters will be replaced with Advanced Metering Infrastructure (AMI) for remote metering of all interface points. The project is expected to be completed in 2023-24. The major ongoing projects of SLDC are related to Implementation of SAMAST scheme and installation of RTUs

Judhi.

which are covered under spillover of 2nd MYT Control Period. Major future projects of SLDC are related to upgradation of SCADA system under ULDC Phase-III, the modalities of which are under discussion stage being held with MoP/FOLD with all Northern States. This project is to be implemented by CTU through PGCIL and will be covered under Capital works only if proposal of execution through Tariff mode is rejected. Other future projects are related to improving Cyber Security posture of SLDC, which may involve purchase of IT Hardware/Software for Cyber Security and/or establishment of complete Security Operation Centre(SOC), which are tentative works that may have to be carried out as per specific instructions of central agencies like NLDC, NCIIPC, CERT-IN etc. As Cyber security guidelines are still in nascent stage, the plan for the same shall be devised based on projects undertaken by central agencies like NLDC, NRLDC etc. However, Capital provisioning for the same has been kept in proposed MYT plan for 3rd Control Period.

- d. Capital Investment Plan based on the above: Appendix-C (New Works), Sr. No. 25 (Requirement of Capacitor bank at various S/Stns as per CPRI report.). Appendix-B (Spill Over), Sr. No. 72 (90 Nos. PSTCL grids (220 kV) to be provided with SAS. DPR is under submission for PSDF funding). Appendix-D (SLDC List).
- e. Man Power Plan: PSTCL submits that it has provided detailed submission on its manpower requirements in section 5.3.7 (Human Resource Development) in its original submission. In the said section, PSTCL has elaborated on the future manpower requirement together with envisaged retirements. The same may kindly be referred by the Hon'ble Commission.

3. PSTCL has not submitted the Detailed Project Reports (DPRs) of the various schemes/ works included in the CIP as per Regulation 9.8 of the MYT Tariff Regulations, 2019 which specifies as under:

"9.8 The Applicant shall submit the Detailed Project Reports (DPRs) for all the schemes as per Part (a) and (b) above which shall include:

(a) Purpose of investment;

(b) Broad Technical Specifications of the proposed investment and supporting details;

Sudhish

- (c) Capital Structure;
- (d) Capitalization Schedule;
- (e) Financing Plan, including identified sources of investment;
- (f) Physical targets;
- (g) Cost-benefit analysis;
- (h) Prioritization of proposed Investments:

Provided that DPRs will not be necessary for schemes under Rs 10 Crore for Generation and Transmission Businesses. Rs 5 Crore for Distribution Business and Rs. 1 Crore for SLDC:

Provided further that the total capital expenditure on non-DPR schemes in any year should not exceed 20% of that for DPR schemes during that year."

PSTCL Reply:

PSTCL submits that the envisaged capital expenditure is proposed to be funded through borrowings from financial institutions. Such institution mandatorily requires submission of DPR for the proposed schemes.

- 3 Nos. DPRs for the new transmission works are enclosed as **Annexure-2 to 4**.
- 2 No. DPRs for SLDC works are enclosed as **Annexure- 4A and 4B**.
- 1 No. DPR for PSDF funding works (for SAS) is enclosed as **Annexure - 5**.

DPRs for remaining works shall be submitted subsequently.

Note:- DPR for Extension of control-room building at SLDC cannot be created at this stage as it is linked with ULDC Phase-III, as such DPR will be drafted after modalities of ULDC Phase-III are finalized by PGCIL. DPR for new work i.e. "Purchase of IT equipment/software as per instructions of central agencies like NLDC, NCIIPC, CERT-IN, for cyber security etc. or any other unforeseen SLDC related works (i.e. for RTU, IT, SAMAST, etc.)" shall be formulated based on instructions of central agencies. As adoption of Cyber security guidelines at Central & State level are still in nascent stage, the DPR for this project shall be drafted based on projects undertaken by central agencies like NLDC, NRLDC etc. in the near future. DPRs for other SLDC works have already been submitted.

4. Regulation 9.18 of the MYT Tariff Regulations, 2019 provides as under-

Sudhanshu

"The STU shall also provide a copy of its capital investment plan to the Distribution Licensee, at the time of filing of this plan with the Commission. The copy of approved capital investment plan shall also be sent to the Distribution Licensee by the STU, immediately after approval by the Commission"

PSTCL to submit the documentary evidence of compliance of the above Regulation.

PSTCL Reply: The Business plan has been shared with PSPCL vide Memo No.813 dated 09.09.2022 copy of the same is enclosed as Annexure-12.

5. PSTCL has submitted that its actual transmission loss was 2.31% in FY 2021-22. However, a higher transmission loss i.e. 2.50% has been projected for all the years of the 3rd Control Period despite the substantial capital expenditure being proposed during the same period. This needs to be explained.

PSTCL Reply: The actual PSTCL Transmission losses for FY 2021-2022 are calculated as 2.31%. Presently, the PSTCL transmission losses are being calculated based upon manual/downloaded data of energy meters.

SLDC is in process of implementation of SAMAST project. In SAMAST project, all the existing energy meters are to be replaced with new energy meters. The meter data will be received from all grid/substations through AMR system. Further, this data will be integrated in the software being developed by the firm and software-based calculation/checking of data will be done leading to reduced manual intervention. There will also be some minor variation in calculations after SAMAST implementation.

Apart from above, additional transmission elements i.e. transmission lines/transformers and other elements will be added in coming years thereby increasing the installed MVA capacity of PSTCL system which may add in transmission losses during lean period. The direction of power flow in PSTCL system along with the outage elements/ loaded elements/lightly loaded transmission elements of future years cannot be ascertained presently so there can be some deviations in PSTCL transmission losses. Keeping in view of the above, proposed transmission loss trajectory is detailed as under:

Swaluj

Particulars	FY 2022-23	FY 2023-24	FY 2024-25	FY 2025-26
Transmission losses (%)	2.50%	2.50%	2.50%	2.50%

6. PSTCL to submit a Transmission Map updated for 2022 along with single line diagram, having distinct colour coded representation for existing, overloaded and proposed transmission network

PSTCL Reply: Transmission Map with distinct colour coding for different voltage level elements and updated till May 2022 is enclosed as **Annexure - 6**. Transmission map for proposed network is under preparation and will be submitted subsequently.

7. PSTCL in its Petition has submitted CIP of Rs. 1274.26 Crore (new works Rs. 308.29 Crore+ spillover Rs. 965.97 Crore), Rs. 1140.61 Crore (new works Rs. 580.57 Crore+ spillover Rs 560.04 Crore) and Rs. 850.47 Crore (new works Rs.681.41 Crore+ spillover Rs.169.06 Crore) for FY 2023-24, FY2024-25 and FY2025-26 respectively for its transmission & SLDC business which is not commensurate with its CIP for the 2nd Control Period. Substantial capital expenditure proposed under new schemes during the 3rd Control Period while the spillover and deferred schemes from the 1st & 2nd Control Period are still pending; PSTCL to provide justification for the same along with year wise capital expenditure made during last 5 years.

PSTCL Reply: PSTCL submits that in the current CIP the spillover schemes from previous CIP are getting implemented across the MYT period i.e. FY 23 to FY 26. The cumulative outlay on such schemes is around Rs. 1,695.07 crores. For new schemes the capital investment is Rs. 1570.27crores during the Control period. Besides the rationale for proposed capital expenditure, the works have been planned to increase the MVA capacity which will further enhance the ATC/TTC limits and load growth/load projections and the resultant capital outlay has been balanced in 3 years. The increase in capital outlay is due to the fact that the transmission system which was created at 400 kV level has been fully utilized to the installed capacity in the past years due to unprecedented increase in demand of the state post COVID-19

Sudhij.

and now there is hardly any margin in the transmission system. The details of the year wise capital expenditure made during last 5 years are enclosed as Annexure- 7.

8. PSTCL to submit detailed technical justification along with cost benefit analysis for capital expenditure proposed in respect of network addition, system strengthening and system augmentation, with details of existing network capacity (as on March 2022) and network capacity projected to be achieved by the end of 3rd Control Period.

PSTCL Reply: Technical justification for the spill-over works has already been provided to PSERC during the submission of Capital Investment Plan for MYT 2020-23. Similarly, technical justification for the new works included in the Capital Investment Plan for the MYT 2023-26 has also been provided during its submission. The details of the existing network capacity are as follows:

Voltage level	MVA capacity (ending March 2022)	Circuit km (ending March 2022)
400 kV	5390	1599.754
220 kV	29981.5	7880.135
132 kV	4335.67	3098.039

The details of the network capacity projected to be achieved by the end of 3rd Control Period (2023 - 26) are as follows:

Voltage level	MVA capacity (by the end of 3 rd CP)	Circuit km (by the end of 3 rd CP)
400 kV	9390	1701.754
220 kV	36729	9184.215
132 kV	4757.67	3307.539

9. For spillover schemes, PSTCL has projected an expenditure higher than the scheme costs. PSTCL to provide details scheme wise with respect to actual project cost, actual cost incurred during 1st & 2nd control period and projected expenditure during 3rd control period. Scheme-wise justifications for delay and spillover be provided along with reasons/ bottlenecks for consistent delay of schemes started from 1st Control Period onwards along with rationale for excess expenditure.

Sudhij.

PSTCL Reply: PSTCL submits that MYT plan for FY 2017-20 did not include the IDC and EC attributed to Capital works. The CIP proposed in this petition includes the envisaged outlay on IDC and EC. For transmission schemes, besides the technical studies and approvals for implementation the major issue is towards acquiring the right-of-way for development of transmission lines. Delay in development of such lines is therefore a known phenomenon to all the developers including PGCIL which has the largest network in the country. Besides the above, selection of suppliers and establishment of reasonability of their quotes increase the lead time in initialization of the projects. The scheme-wise justifications for delay and spillover has already been provided and the reason for excess expenditure is attached as **Annexure-8**.

10. **PSTCL to provide scheme-wise technical and financial justification for each new scheme proposed along with schemes completion dates and any spillover expenditure for proposed new schemes beyond 3rd Control period.**

PSTCL Reply: Technical justifications for all the works have already been provided. Financial justification (Cost Benefit Analysis) has been included in the submitted DPRs for the new transmission works. The spillover expenditure for proposed new schemes beyond 3rd control period is approx. Rs. 527.33 Crore (CWIP).

11. **PSTCL has considered EC @15% and IDC @ 4% in the 3rd Control Period. PSTCL to submit the rationale and detailed calculation along with documentary evidence to substantiate its claim.**

PSTCL Reply: The estimated amount of EC & IDC during the 3rd control period is tentative. The actual EC & IDC incurred will be submitted subsequently at the time of True up submission.

12. **PSTCL to submit bifurcation of spillover works and new works for the capital investment plan proposed for its SLDC business, in line with Regulation 9.7 of the MYT Tariff Regulations, 2019.**

PSTCL Reply: Bifurcation of spillover works and new works for SLDC is already submitted and is again enclosed as **Annexure-9**.

Sudhish

13. PSTCL to submit actual scheme-wise capital expenditure from FY 2020-21 to FY 2021-22 and projected capital expenditure for FY 2022-23 for Transmission & SLDC works, Further, PSTCL to also provide the proportion of Govt. grants and consumer contribution received.

PSTCL Reply: Actual scheme wise Capital expenditure for FY 2020-21, 2021-22 and projected expenditure for FY 2022-23 are enclosed as Annexure-10. PSTCL submits that no contributory work is included in the 3rd Control Period. The works being carried out with central grant under PSDF are listed at CIP nos. 172 - 175 and 180 of Table-11; 71, 72, 74 and 87 of Table-17; 7 of Table-22. As and when central funds are received and works are completed, complete details of funds and capitalization shall be submitted to the Hon'ble commission with the True-up. Likewise the details of contributory works shall also be submitted with the True-up.

14. PSTCL is required to intimate the strategy for utilization of the dismantled transformers etc. where it has proposed augmentation along with details when installed & now proposed to be dismantled and cost of transformers so dismantled.

PSTCL Reply: Transformer augmentation is purely based on the maximum demand recorded at any substation or as per requirement on real time basis. Augmentation is also undertaken in case a new connection is applied requiring augmentation of the system. All transformers which are dismantled shall be used within the system. The transformer to be dismantled is identified on case to case basis at the time of actual augmentation of the transformer. The depreciated value of the transformer so identified to be dismantled shall be calculated at the time of dismantlement and details of all such transformers shall be submitted subsequently at the time of True up submission.

15. For schemes over Rs. 50 Crore, PSTCL has sought exemption from execution of project through TBCB (Tariff based Competitive Bidding) by quoting reference of MoP letter dated 15.03.2021 However, the letter strongly recommends to adopt TBCB for development of intra state transmission system in larger interest of consumers. PSTCL is required to clarify.

PSTCL Reply: All the new works of tentative cost more than Rs 50 Crore involve upgradation of 66kV/132/220kV substations to 220/400 kV level within the pre-

Sudhij

owned land of existing networks of PSPCL/PSTCL and the transmission lines connecting these new substations are LILO of existing transmission lines and hence are only technical upgradations specific to the need of the areas of Punjab State and are Brown Field projects. Therefore, all these projects do not fall under the ambit of TBCB mode as per exemption stated in clause 7.1(7) of revised tariff policy issued by Govt. of India in January 2016 read with Govt. of India, Ministry of Power memo no. 15/2/2017-Trans-Pt(1) dated 15.03.2021 (Annexure-11).

16. PSTCL to submit the following:

- a. **Annual Audited accounts from FY 2021-22.**

PSTCL Reply: Annual Audited accounts from FY 2021-22 are placed in the enclosed CD.

- b. **A breakup of scheme-wise financing plan i.e., the breakup between debt, equity, Govt. grants and consumer contribution for each of the ongoing/ spillover/deferred and new schemes;**

PSTCL Reply: PSTCL submits that no contributory work is included in the 3rd Control Period. Complete details of funds and capitalization of the works to be carried out with central grant under PSDF shall be submitted to the Hon'ble commission with the true-up.

- c. **Actual Government grants received (if any) for the ongoing/ spillover schemes (as on March 2022) and an estimate of Government grants expected to be received from FY 2023-24 to FY 2025-26;**

PSTCL Reply: PSTCL submits that no contributory work is included in the 3rd Control Period. Complete details of funds and capitalization of the works to be carried out with central grant under PSDF shall be submitted to the Hon'ble commission with the true-up.

- d. **Summary sheet of capital expenditure and capitalization showing the cost, employee cost, IDC.**

PSTCL Reply: Summary of capital expenditure and capitalization showing the cost, employee cost, IDC is as under:

Sudhanshu

CIP proposed for 3rd Control Period (Total Schemes)							(Rs. Crore)
Sr No.	Particulars	FY 2023-24	FY 2024-25	FY 2025-26	FY 2023-24	FY 2024-25	FY 2025-26
Capital Expenditure				Capitalization			
	<u>Transmission</u>						
1	Works Cost	1045.64	944.95	716.58	1012.24	694.06	873.14
2	Employee Cost	169.28	147.99	105.06	176.34	114.96	129.80
3	IDC	59.34	47.68	28.83	69.29	42.57	36.87
4	Total	1274.26	1140.62	850.47	1257.87	851.59	1039.81
	<u>SLDC</u>						
1	Works Cost	8.28	2.13	0.93	24.79	5.96	0.93
2	Employee Cost	0.00	0.00	0.00	0.00	0.00	0.00
3	IDC	0.00	0.00	0.00	0.00	0.03	0.00
4	Total	8.28	2.13	0.93	24.79	5.99	0.93
	<u>PSTCL</u>						
1	Works Cost	1053.92	947.08	717.51	1037.03	700.02	874.07
2	Employee Cost	169.28	147.99	105.06	176.34	114.96	129.80
3	IDC	59.34	47.68	28.83	69.29	42.60	36.87
4	Total	1282.54	1142.75	851.40	1282.66	857.58	1040.74

17. It is observed that the Business Plan submitted by PSTCL for its Transmission and SLDC business does not contain consumer contribution/Govt. grants if any, towards capital expenditure. PSTCL has projected the capital expenditure for Rs.1282.54 crore, Rs.1142.74 crore and 851.40 crore during the year FY 2023-24, FY 2024-25 and FY 2025-26 respectively, for Transmission and SLDC Business (Table-26). However, equity to be infused has been shown as Rs.133.80 crore, Rs 153.36 crore and Rs.175.61 crore for FY 2023-24, FY 2024-25 and FY 2025-26 respectively (Table No-27) and loan requirement shown is Rs.947.07 crore. Rs.738.77 crore and Rs.783.7 crore for FY 2023-24, FY 2024-25 and FY 2025-26 respectively (Transmission and SLDC business). The financing amount of equity and Loan does not tally with the projected capital expenditure. Hence,

Sudhij.

PSTCL to clarify how the equity amount has been derived clearly stating the receivable amount of consumer contribution/Govt grants.

PSTCL Reply: As per clause 4.5.8 of MYT Order for FY 2020-21 dated 01.06.2020, the Hon'ble Commission has decided to fund the new schemes on Capitalization basis (schemes started after 01.04.2020) and fund the spill over schemes (i.e. schemes before 01.04.2020) on Capital expenditure basis. Therefore, although the Capital Expenditure for 3rd Control Period is Rs. 1282.54 crore, Rs. 1142.74 crore and Rs. 851.40 during FY 2023-24, 2024-25 & FY 2025-26 respectively, however, funding required is Rs. 1057.57 crore, Rs. 886.14 crore and Rs. 958.38 crore respectively considering Capital Expenditure for Spill over schemes and Capitalisation of New Schemes. Detailed Funding is shown as below:-

Funding Requirement for Capital Investment for 3 rd Control Period				(Rs. Crore)
Sr. No.	Particulars	FY 2023-24	FY 2024-25	FY 2025-26
A	Transmission			
1	CAPEX of Spill over Schemes from 1st Control Period (Excluding Contributory & PSDF)	196.31	80.96	61.57
2	Capitalization of New Schemes from 2nd Control Period and New Works for 3rd Control Period (Excluding Contributory & PSDF)	861.26	805.18	896.81
3	Directly Capitalised	0.00	0.00	0.00
4	Total funding for CAPEX	1057.57	886.14	958.38
4a	Funding through Equity (New Schemes) (As per Table - 27)	133.80	153.36	175.61
4b	Funding through Loan	923.77	732.78	782.77
5	Total Capital Expenditure	1274.26	1140.61	850.47
6	Total funding for CAPEX	1057.57	886.14	958.38
7(5-6)	Balance CAPEX of New Schemes (Not Capitalized yet/ Capitalized balance of previous years)	216.69	254.47	-107.91

Sudh.

B	SLDC			
1	CAPEX of Spill over Schemes from 1st Control Period (Excluding Contributory & PSDF)	0.78	0.40	0.00
2	Capitalization of New Schemes from 2nd Control Period and New Works for 3rd Control Period (Excluding Contributory & PSDF)	22.52	5.59	0.93
3	Directly Capitalised	0.00	0.00	0.00
4	Total funding for CAPEX	23.30	5.99	0.93
4a	Funding through Equity	0.00	0.00	0.00
4b	Funding through Loan	23.30	5.99	0.93
5	Total Capital Expenditure	8.28	2.13	0.93
6	Total funding for CAPEX	23.30	5.99	0.93
7(5-6)	CAPEX of New Schemes (Capitalized balance of previous years)	-15.02	-3.86	0

Further, during 3rd Control Period, Out of total fund requirement of Rs. 1057.87 crore, Rs. 886.14 crore and Rs. 958.38 crore respectively, funding through equity is the amount of ROE of previous year, which can be invested in current year e.g. ROE of FY 2022-23 is the equity invested/funding from equity during FY 2023-24. Calculation of ROE is as below:-

Calculation of Return on Equity (Rs Crore)

Sr. No.	Particulars	2021-22	2022-23	2023-24	2024-25	2025-26
1	Opening Equity for the year	726.36	803.92	922.52	1056.32	1209.68
2	Addition of Equity during the year	77.56	118.60	133.80	153.36	175.61
3	Closing Equity for the year	803.92	922.52	1056.32	1209.68	1385.29
4	Rate of RoE	15.50%	15.50%	15.50%	15.50%	15.50%
5	Return on Equity	118.60	133.80	153.36	175.61	201.11

18. It has also been observed that Rs.7.17 crore, Rs.2.96 crore and Rs 2.24 crore have been shown as the interest capitalization for FY 2023-24, FY 2024-25 and FY2025-26 respectively. PSTCL to clarify the basis on which interest capitalization has been worked out towards capital works.

Sudhir

PSTCL Reply: Capitalization of Interest during 3rd Control Period is based on actual figures of interest capitalized for FY 2021-22. During the FY 2021-22, total Capitalization of Interest amounting Rs. 11.70 crore is against Total Capital Expenditure of Rs. 321.40 crore. Relation between Interest Capitalized & Capital expenditure is 3.64% (11.70/321.40) for FY 2021-22.

During 3rd Control Period Capitalization of interest is considered only on Spill over works only, as Hon'ble Commission considers capital expenditure on Spill over schemes and Capitalization for new schemes for funding purpose. Therefore, Same 3.64% has been applied to the Capital Expenditure on Spill over works during 3rd Control Period to derive the figure of Interest Capitalized.

19. PSTCL in table No. 33 has shown the payment of arrear of Pay to employees and Pensioners to the tune of Rs.202.02 crore and Rs 115.34 crore respectively during FY 2022-23. However, PSTCL in petition No.67 of 2021 has claimed Rs.55.72 crores (FY 2021-22) and Rs. 25.43 crore (FY 2022-23) (Table-89 & 90 page-76 of the Tariff Order dated 31.03 2022) towards Pay revision impact for PSTCL and SLDC. PSTCL to intimate the reasons/basis for such rise in pay revision arrears amounting to Rs.317.36 (202.02+115.34) crore payable in FY 2022-23 from Rs.25.43 crore.

PSTCL Reply: Impact of Pay Revision claimed in petition no. 67 of 2021 amounting to Rs. 55.72 crore (FY 2021-22) and Rs. 25.43 crore (FY 2022-23) is on the account of Pay revision impact w.e.f 01.07.2021 i.e. from the date of implementation of Pay Commission report by GOP. However, in CIP & BP Petition for 3rd Control Period payment of arrear of Pay to employee and Pensioners amounting to Rs. 202.02 crore and Rs 115.34 crore respectively on account of Arrears of Pay Commission w.e.f 01.01.2016 to 30.06.2021. However will be paid only as per notification issued by the Government of Punjab regarding it.

Sudhij

		Detail of works						SLDC	
Sr. No.	Particulars	TS		P&M		Total		No. of Works	Total Cost as per Previous CIP (In Cr.)
		No. of Works	Total Cost as per previous CIP (In Cr.)	No. of Works	Total Cost as per Previous CIP (In Cr.) *	No. of Works	Total Cost as per Previous CIP (In Cr.) *		
		1	Works Envisaged in Previous CIP						
	Works completed	42	140.116	8	17.52	50	157.636	-	-
	Works to be completed by 31.03.2023	29	322.901	1	0.28	30	323.181	-	-
	Works dropped/deleted/shifted	19	132.319	4	34.62	23	166.939	-	-
	Total	90	595.336	13	52.42	103	647.756		
2	Detail of works approved outside 2nd CIP								
	Works completed	1	12.09	0	0	1	12.09	1	0.28
	Works to be completed by 31.03.2023	3	95.773	1	0.45	4	96.223	0	0
	Works dropped/deleted/shifted	1	6.3	0	0	1	6.3	0	0
	Total	5	114.163	1	0.45	6	114.613	1	0.28

Appendix-A
(Transmission Works)

Appendix-D
(SLDC Works)

Abstract of Capex of FY 2023-24 to 2025-26 (Transmission)						Total Cost (In Cr.)	
Sr. No.	Particulars	No. of Works	FY 2023-24	FY 2024-25	FY 2025-26		
1	Spill over works approved from previous CIP & Spill over works approved from previous control period approved outside CIP	101	965.97	560.04	169.06	1,695.07	Appendix-B (Transmission Works)
2	New Works for 3rd Control Period	98	308.29	580.57	681.41	1,570.27	Appendix-C (New Works)
	Total	199	1274.26	1140.61	850.47	3,265.34	

Abstract of Capex of FY 2023-24 to 2025-26 (for SLDC)						Total Cost (In Cr.)	
Sr. No.	Particulars	No. of Works	FY 2023-24	FY 2024-25	FY 2025-26		
1	Spill over works approved from previous CIP & Spill over works approved from previous control	6	7.78	1.63	0.43	9.84	Appendix-D
2	New Works for 3rd Control Period	2	0.50	0.50	0.50	1.50	
	Total	8	8.28	2.13	0.93	11.34	

AS

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
Table-11 of 2nd CIP Order- Works of 1st Control Period								
1	A	Unforeseen Expenditure on works on 2018-19		6.88		2020-21	2020-21	Work is completed. Not spillover.
2	39	Bus Bar Protection scheme for 45 no S/S/Ins. (90% funding Under Power System Development Fund (PSDF), 10% amount accounted for in FY 2017-18		1.11	1.82	12-2019	2021-22	Work is completed. Not spillover.
3	60	220 kV S/S Derabassi		1.11	9	14.12.2015	2018-19	Work is completed. Not spillover.
4	62	400 kV S/Stn. Makhu		30.39	29.6	21.11.2019	2021-22	Work is completed. Not spillover.
5	89	220 kV S/S Dhandhari Kalan 1 and 2	Provision of 220 kV Double bus bar arrangement	5.01	9.23	Project shifted to CIP No. 10		Scope of work revised at Sr. No. of 10 of MYT 2020-23. So, this work will not spillover. CWIP for 2020-21 has also been shifted to Sr. No. 10.
6	90	220 kV S/S Sahnewal		0.2	2.2	28/4/2017	2022-23	As 220 kV S/S Sahnewal caters mainly Industrial area so very few shutdowns are being approved but multiple shutdowns are required to complete this work which causes delay in completion of work. The scope of work also needs to be revised. So, the work is proposed to be foreclosed and new work with revised scope of work has been added in new MYT 2023-26.
7	102	New Civil Works in respect of 5 no. stores such as sheds, plinths and Boundry walls etc.		4.23		2022-23	2022-23	Work is completed. Not spillover.
8	104	Procurement of Hardwares, Server, Furniture, IT Space renovation (Civil Works) & Unforeseen Capital Investment		2.58		01-2022	04-2022	Work is completed. Not spillover.
9	107	220 kV S/Stn Sadiq		0.35	8.81	07-2020	2021-22	Work is completed. Not spillover.
10	108	220 kV S/Stn Bajakhana		0.35	8.81	20/03/2020	06-2022	Work is completed. Not spillover.
11	110	220 kV S/Stn Ghubaya		0.35	8.81	07.10.2019	2022-23	Work is completed. Not spillover.

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
12	116	220 kV S/StnBanga (U/G from 132 kV)		1x100 MVA, 220/132 kV T/F as spared from 220 kV S/StnMahilpur	2.79	8.19	01-2019 Dec 2022	Work is completed. Not spillover.
13	119	220 kV Line bays at 220 kV S/StnBanga (Proposed)		2 Nos. (cost of 1no. Line bay already included in s/stn.	0.33	1.3	01-2019 May 2022	Work is completed. Not spillover.
14	129	LILO of one ckt. of 400 kVJalandhar-Kurukshetra D/C line f at 400 kV Dhanansu(Quad Moose)	LILO length =5 km(approx)		12.04	17.00(approx.)	10-2021 3.2023	Erection of towers got completed except one tower. Work will be completed by 3/23.
15	131	220 kV Banur- Mohali (GMADA) DC line	4 km Line Length ACSR ZEBRA Conductor		3.48		Work dropped	Work to be dropped due to non availability/hand over of land from GMADA and non deposit of requisite funds.
16	134	400 kV Grid Dhanansu (near Doraha)	220 kV DC line from 400 kV Grid near Doraha to 220 kV Ikolaha 12 km (approx.)/ 420 sq mm DC ACSR Zebra				Dropped	Work dropped vide Amendment No.16/2021-22 Dated 27.07.2021
17-20	137-140	1. Aug/Strengthening of bus bars 2. Extension in Switchyard buildings, Provision for AC etc. 3. Provision for Reactive Compensation 4. Addition of bays/system strengthening required on account of RE generation	0		3.41	3.275	2020-21 2022-23	Work completed. Not spillover.

69

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project			Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
21	142	Replacement of Disc Insulators of 400 kV PSTCL lines with Polymer Insulators			105.45		4.21	03-23	Due to tripping of 400 kV lines in foggy season with porcelain insulators, PSTCL started washing of porcelain discs before foggy season which reduced tripping of 400 kV lines. After considering results of washing, BODs decided that all existing strings may not be replaced with polymer insulators and washing of discs be carried out twice a year. As per BODs decision washing is being done twice a year, once before foggy season and once after the wheat harvesting. Further it was decided to replace porcelain disc insulators with Polymer disc insulators at strategic locations for which 1000 polymer disc insulators have been replaced during this Control Period and 1000 polymer discs are under procurement for replacement in 2nd CP. Depending upon needs of the future, porcelain disc insulators will be replaced with Polymer Long Rod for which provision of Rs. 10 Cr. has been made in the MYT of 3rd CP.
22	143	220 kV DC line from 220 kV S/Stn Gaunsgarh to 220 kV S/StnLadhowal.			1.11	13.92	05-2018	12-22	Work is completed. Not spillover.
23 to26	152-155	1. Aug/Strengthening of bus bars 2. Extension in Switchyard buildings, Provision for AC etc. 3. Provision for Reactive Compensation 4. Addition of bays/system strengthening required on account of RE generation			4.87	15	2020-21	2022-23	Work is completed. Not spillover.
27	163	132 kV Samadh Bhai		Construction of a new Switch House Building at a new raised level	0.67		04.08.2019	2021-22	Work is completed. Not spillover.

at

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
28	164	132 kV Pathankot		0.22		02-11-2018	22/11/2019	Work is completed. Not spillover.
29	166	220 kV S/Stn Bhawanigarh	0	6.69	7.44	04.03.2020	Sep 22	Work under progress, will be completed by 31.08.2022
30	167	220 kV S/Stn Jadla	0	6.69	7.44	03.02.2020	Dec 22	Work is completed. Not spillover.
31	168	220 kV S/Stn Botianwala (Thatha Sahib)	0	9.03	10.1	01.11.2021	March 23	Work will be completed by 03/23. Not spillover.
32	169	220 kV S/Stn Majitha	0	6.69	7.44	13.10.2020	March 23	Work under progress, will be completed by 31/03/2023. Not spillover.
33	170	132 kV S/Stn Pathankot	0	0.23	0.21	26.02.2018	Dec 19	Work is completed. Not spillover.
34	171	132 kV IGC, Bathinda	0	0	0.18	11.05.2022	06-2022	Work is completed. Not spillover.

11
AS


List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)	
35	176	Replacement of Existing conductor of 220 kV Mohali-I - Mohali-II line		0	31.14		Dropped	Mohali1-Mohali 2 circuit was having high loading. So, in order to reduce the loading and to balance out the power flows between Mohali-1, Mohali-2, Lalru and Dera Bassi, LILO of 220 kV Mohali-1 - Lalru at 220 kV Mohali-2 has been planned vide amendment no. 27/2021-22 dated 09.12.21, this effectively creating double circuit connectivity between Mohali-1 and Mohali-2. Therefore Mohali-1 - Mohali-2 HTLS is not required now.	
36	180	220 kV DC line from 400 kV Jalandhar (PGCIL) to 220 kV Kartarpur	Augmentation of existing conductor of both circuits with HTLS conductor of min 1200 A capacity	0	41.83	05-2022	03-2023	Work under progress. 1st circuit completed and 2nd circuit to be completed by 3/23.	
Total					289.23				
Table 13 of 2nd CIP Order- Works approved outside 1st CIP									
37	2b	132 kV Sihora-132 kV Seh SC line		2 no. 132 kV line bays (one at each end)	1.11	1	01-2020	01-21	Work is completed. Not spillover
38	3a	400 kV S/StnNakodar (2x315 MVA, 400/220 kV) (Amendment no. 43 /2018-19)			16.17	14.5	Dropped		This work has been revised and approved vide PSERC Petition No. 37 of 2020 and the revised work is in the Work approved by Petition list. So, hence work is deleted from here.
39	3b	Cost of dismantlement of 1x315 MVA, 400/220 kV ICT at 400 kV Nakodar			0.58	0.5			

72

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project			Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
40	5	400 kV Rajpura-220 kV Bassi Pathana DC Link. (Amendment no. 13 /2019-20)	220kV DC Line from 400 kV Rajpura to 220 kV Bassi- Pathana (Line length 2 X 20 km)		17.06		Work dropped		This work is deleted from here as new work is planned vide Amendment No. 16/2022-23 and The expenditure for Amend 16/22-23 shall be adjusted to the cost allocated for the work listed at Sr. No. 5 of Table 13 of MYT 2020-23 (which is to be deleted). Further it is submitted that work of replacement of existing conductor of 220 kV Gobindgarh-400kV Rajpura (D/C) line with HTLS conductor of suitable capacity was intended to be carried out under PSDF scheme and the work of 400kV Rajpura-Bassi Pathana (D/C) link was planned as an alternate in case PSDF grant is not obtained for the 220kV Gobindgarh-400kV Rajpura (D/C) HTLS work. PSDF grant has been approved for the 220kV Gobindgarh-400kV Rajpura (D/C) HTLS work & thus work of 400kV Rajpura-Bassi Pathana (D/C) link is no longer needed.
		4no. 220 kV Bays			5.89				
		220 kV Side bus extension arrangement to be made at 400 kV Rajpura for providing suitable space for 2 Nos 220 kV Bays			0.1				
41	8	220 kV Patti		Replacement of 1x100 MVA, 220/66 kV to 1x160 MVA, 220/66 kV T/F.	8.44	8.54	25.08.2021	06-2022	Work is completed. Not spillover.
42	9	220 kV Ferozepur road Ludhiana		Replacement of 1x100 MVA, 220/66 kV to 1x160 MVA, 220/66 kV T/F.	8.44	8.54	11-2019	Jul-21	Work is completed. Not spillover.
Table 15 of 2nd CIP Order-Works already planned for 2020-23									
43	1	1 No. 400kV ICT bay, 1 No. 400 kV Tie bay, 1 No. 400 kV Future bay, 1 No. 220 kV ICT bay at 400 kV Rajpura. Amendment No. 20/ 2018-19	0	0	32.27	28	01-2022	08-2022	Work is under progress .Minor Civil Works pending. Will be completed by 15.08.2022. Not spillover.
44	2	Jumping arrangement on tower no. T.L 290 for Termination of direct link 220 kV between Lalton Kalan Sahnewal (Amendment no. 04 / 2021-22)	0	In order to have PGCIL Ludhiana-220 kV Sahnewal as D/C (so as to avoid direct link between 220 kV Lalton Kalan-Sahnewal), termination shall be done at terminal tower at 220 kV LALton Kalan end.	0.06		sept 21	Dec 21	Work completed on 31.10.2021. Not spillover

SL


List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)	
45	3	400kV, 200MW Permanent Power to Guru Gobind Singh Polymer Addition Project- HPCL Mittal Energy Limited. (Amendment no. 21 (ii,iii& iv) / 2018-19)		1	29		2020-21	As this is Contributory work and is present at contributory work list and the work is completed on March 21.	
Table 17 : New Works planned for the 2nd Control Period from FY 2020-21 to 2022-23									
46	11	220 kV Kharar		Replacement of 2x20MVA, 132/11 kV with 2x20MVA, 66/11kV T/F	3.65	3.28	26/12/2017	31/07/2021	Work completed. Not spillover.
47	12	220 kV Banga		a) Addl. 1x100 MVA, 220/66 kV T/F.			work deleted		Scope revised vide Amendment No. 09/21-22 dated 28.06.21 and ratified by BOD.
48	13	220 kV Banga		b) Replacement of 2x20MVA, 132/11 kV T/F with 2x20 MVA, 66/11kV T/F.			Work deleted		
49	25	220 kV Nawanpind (new grid in the premises of 66 kV S/s Nawanpind)Includind SAS for RS 1cr. Amedment No. 17/21-22	220 kV Bays= 4 Nos			5.28	To be deleted		Scope revised on basis of request from PSPCL and Amendment No. 17/21-22 dated 24.08.21 issued and ratified by BOD. Right to use from PSPCL is pending
50	26		132 kV Bays= 2 Nos				To be deleted		
51	28	Additional link		220 kV double bus bar at 220 KV Ghubaya	0.17	0.96 0.15	To be deleted Deleted		
52	31	New 220 kV Jhoke HariHar (New)	LILO of 220 kV Sadiq- Talwandi Bhai line at 220 kV Jhoke Harihar (New) (LILO length 13 km approx, 0.4 sq inch DC on DC)		16.794		6.2022	3.2023	Work completed by 03/23. Not spillover
53	34	220 kV Dhaleke (GIS) including SAS of RS 1 cr	LILO of both ckts of 220 kV Talwandi Bhai Dharmkot, conductor size 0.4sq", LILO length 10	To be deleted from Sr No. 34 to 36	13.17		Dropped		Work was planned with 220/132kV T/Fs. PSPCL has demanded 220/66kV T/F. Since 100MVA 220/66kV T/F at Singhawala has been planned as such this work is to be dropped.
54	35		0	2x100 MVA, 220/132 kV T/F. including 4 no. 220 kV bays	33.27	39.47			

HL

AS

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)	
55	37	132 kVSwadi Kalan		L.ILO of 132kV SC on DC line from Jamalpur to Moga at 132 kVswadi kalan ,conductor size 0.2sq", L.ILO length 4.5 km(approx)	2.33		4-2022	03-2023	Work will be completed by 03/23.
56	38			2 no. 132 kV bays	1.11		10-11-2021	31/03/2023	
57	40	ii) 220 kV Abohar	0	Addl. 12.5 MVA, 66/11 kV T/F.			2022-23	2022-23	Work will be completed by 31.10.2022.
58	41	iii) 220 kV Passiana	0	Addl. 12.5 MVA, 66/11 kV T/F.	2.269		18.06.2020	2022-23	Work is completed. Not spillover.
					2.269				
59	42	iv) 220 kV Dhuri	0	Aug. of 12.5 MVA, 66/11 kV to 20 MVA, 66/11 kV T/F.			11.05.2022	2022-23	Not spillover.
60	43	v) 220 kV Mohali - I	0	Replacement of 1x100 MVA, 220/66 kV to 1x160 MVA, 220/66 kV T/F.	2.02		09-2020	31/08/2022	Work is completed. Not spillover.
					9.84				
61	44	vi) 220 kV Banur	0	Addl. 20 MVA, 66/11 kV T/F.			07-2021	31/03/2023	Not spillover.
					2.28				
62	47	ix) 220 kV Mahilpur	0	Addl. 12.5 MVA, 66/11 kV T/F.			07.09.2020	2021-22	Work is completed. Not spillover.
					2.269				
63	48	x) 220 kV Kartarpur	0	Addl. 12.5 MVA, 66/11 kV T/F.			30.04.2021	2021-22	Work under progress, target date 30.09.2022
					2.269				

5 L
AB

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project	Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
64	49	xi) 220 kV Badsahpur	0	8.56	07-2022	2022-23	Work to be completed by 03/23
65	50	xii) 220 kV Butari	0	2.269	30.04.2021	2022-23	Work under progress, target date 30.11.2022. Not spillover.
66	51	xiii) 220 kV Udhoke	0	8.56	05-2019	2022-23	Work under progress, target date 30.11.2022. Not spillover.
67	52	xiv) 220 kV Pakhowal	0	9.84	01-2022	27/06/2022	Work is completed. Not spillover.
68	53	xv) 220 kV Jagraon	0	1.71	12-2020	2021-22	Work is completed. Not spillover.
69	55	xvii) 220 kV Kohara	0	2.02		Work deleted	Work dropped as work of aug. of 20 MVA to 31.5 MVA has been planned.
70	56	xviii) 220 kV Doraha	0	2.269	07-2021	2021-22	Work is completed. Not spillover.
71	57	xix) 220 kV Baghapurana	0	2.269	01-2021	2021-22	Work is completed. Not spillover.
72	58	xx) 132KV SmadhBhai	0	3.81	08.06.2021	2022-23	Work is completed. Not spillover.

94

AS

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)	
73	59	xxj) 132kV Faridkot	0	Aug. of 12.5 MVA, 132/11 kV to 20 MVA, 132/11 kV T/F.		2022-23	2022-23	Not spillover.	
74	64	xxvii) 132kV Bhikhiwind	0	Aug. of 12.5 MVA, 132/11 kV to 20 MVA, 132/11 kV T/F.	2.82	02-2022	2022-23	Work is completed. Not spillover.	
75	65	xxviii) 132kV Shri Hargobindpur	0	Addl. 20 MVA, 132/11 kV T/F.	3.81	10.02.2022	2022-23	Not spillover.	
76	66	xxx) 132kV Phillour		Aug. of 12.5 MVA, 132/11 kV to 20 MVA, 132/11 kV T/F	2.82	01-2022	2021-22	Work is completed. Not spillover.	
77	67	xxxi) 132kV Bilaspur		Aug. of 12.5 MVA, 132/11 kV to 20 MVA, 132/11 kV T/F.	2.82	2022-23	2022-23	Not spillover.	
78	68	xxxi) 132kV Tangra		Addl. 12.5 MVA, 132/11 kV T/F	3.81	01-2022	2022-23	Work under progress, target date 31.12.2022	
79	73	Digitization of existing 220 kV S/s Passiana.		Case already approved. PSDF funding have been applied. Total cost = 11 Cr.s, out of which 90% PSDF funding & remaining 10% through capital investment.	1.27	Dropped		As per BODs 61st meeting dated 14.08.2020, work has been dropped.	
80	76	132 kV S/s Kotkapura-I		Addl. 1x20 MVA, 132/11kV T/F	3.69	3.31	16/12/2021	2022-23	Work is completed. Not spillover.
81	79	132 kV Kapurthala.	0	Addl. 1x20 MVA, 132/11 kV	3.69	3.31	01-2022	2022-23	Work is completed. Not spillover.

TL

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project		Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)	
82	80	132 kV Bisan.		Replacement of 1x12.5 MVA, 132/11 kV with 1x20 MVA, 132/11 kV T/F	2.74	2.46	Deleted	Being single T/F, augmentation will affect supply, so work dropped as discussed in TPC and work of additional 20 MVA is being planned in 3rd MYT.	
83	81	132 kV Panjraian.	0	Replacement of 1x12.5 MVA, 132/11 kV with 1x20 MVA, 132/11 kV T/F	2.74	2.46	12-2021	2021-22	Work is completed. Not spillover.
84	83	IGC Bathinda (Aug)	0	Replacement of 2x12.5 MVA, 132/11 kV with 2x20 MVA, 132/11 kV	5.48	4.92	11.05.2022	2022-23	1 No. T/F augmentation work complete, for 2nd 20MVA 132/11kV T/F under procurement.
85	84	132 kV Gholian Kalan.	0	Addl. 1x20 MVA, 132/11 kV T/F	3.69	3.31	07-2021	2022-23	To be completed by 03/23
86	85	LILO of 132 kV Verka – Mal mandi SC line at 220 kV S/s Nawanpind (132 kV bus) LILO length = 1 KM appx. DC on DC.	Replacement of existing conductor of 0.25sq" with equivalent HTLS conductor (on the same supporting structure), having a minimum capacity of at least 800A.				Work deleted	Work deleted vide Amendment No. 17/21-22 dated 24.08.21 issued and ratified by BOD. Reason for deletion of work is that PSPCL requested for 66 kV system at 220 kV Nawanpind due to which scope has been revised vide Amend No. 17/21-22 dated 24.08.21 and due to 66 kV system, 132 kV lines were not needed now, hence this work deleted.	
87	86	Augmentation of 132 kV Nawanpind - Verka, 5 KM (0.2sq") and 132 kV Nawanpind - Malmandi (5KM 0.2sq") with suitable HTLS conductor.	0				Work deleted		
88	89	132 kV GT Road Amritsar & 132 kV Sakatari Bagh Asr	132 kV link between 132 kV GT Road- 132 kV Sakatri Bagh through 132 kV underground cable		18.68	16.56	08-2021	31/07/2022	WORK completed.
89	90		132 kV Bays= 2 Nos.	132 kV Bays= 2 Nos.	1.15	1	12-2021	31/07/2022	
90	92	Unforeseen emergency works			17.38	15	2021-22	2022-23	Work will be completed by 22-23

87

List of works of CIP 2nd Control Period which have been completed/ to be completed by 31.03.2023/Dropped/Shifted

Sr.No.	Sr No. as per CIP Order	Name of Project	Project cost as per CIP	Actual Project Cost	Start Date	Date of completion	Remarks (if any)
Works approved outside 2nd MYT 2020-23 by Petition/BOD approval							
91	Amendment No. 22/2021-22	39 No. substation and one SLDC building	Installation of roof top solar power plant on roofs of control room of various 400/220/132 kV substations of PSTCL.			Deleted	CAPEX scheme is dropped. Now installation of rooftop will be explored in RESCO model.
92	Amendment No. 27/2021-22	220 kV S/S Mohali-2.	LILO of 220 KV Mohali-1-Lalru at 220 KV Mohali-2(Line length- 1 KM,0.4sq" conductor)-Stringing of LILO line.	0.317	10-22	12-22	Tendering work in progress
93	Amend 03/22-23	220 KV S/S Sahnewal	Augmentation of 1 no. 100 MVA Transformer at 220 kV Sahnewal Substation to 160 MVA	35.596	2022-23	2022-23	Not spillover
		220KVS/S Bajakhana Amend 03/22-23	Augmentation of 1 no. 100 MVA Transformer at 220 KV Bajakhana Substation to 160 MVA		2022-23	2022-23	Not spillover
		220KVS/S Ghulal Amend 03/22-23	Augmentation of 1 no. 100 MVA Transformer at 220 KV Ghulal Substation to 160 MVA		2022-23	2022-23	Not spillover
94	Amendment 08/22-23	132kv Power Colony Amritsar	1 No. 3rd Additional 132/11kV, 10/12.5 MVA T/F (spare T/f from system to be used).	59.86	2022-23	2022-23	Not spillover
		220 KV Sahnewal	Aug. of 1 no. 20 MVA with 31.5 MVA, 66/11 KV		2022-23	2022-23	
95	Amendment 11/22-23	220 kV Amlah	Augmentation of 220/66 kV 100 MVA TF to 160 MVA	12.09	2022-23	2022-23	Work is complete. Not spillover.

64
AS

List of works of CIP 2nd Control Period which have been completed/

B.No.	Sr No. as per CIP Order	Name of Project		
P&M Works which have been completed or to be completed by 31.03.2023/Dropped or shifted				
Sr. No.	Sr. No. as per CIP Order	Name of Project	Total Project Cost as per CIP	Remarks
Works of First Control Period(2017-20)				
1	1	To modernise the hotline work by use of Diagnostic techniques to decrease the outage in transmission system of PSTCL.	11.14	Work completed and will be capitalized in 2nd CP of MYT
2	2	To provide SAS based DRs and ELs at six 220kV S/S as per requirements of IEGC and SGC and comply with 3rd party protection audit by CPRI.	4.05	Not started and should be dropped as TS organization is automating all 220 KV S/Ss and this work will be part of that larger work
3	3	To provide DRs and ELs in 220 kV S/S of PSTCL to comply with IEGC, SGC and 3rd party protection audit by CPRI.	19.41	Not started and should be dropped as TS organization is automating all 220 KV S/Ss and this work will be part of that larger work
4	4	To procure testing equipment to check healthiness of OPGW channels and Ethernet Switch Network in Substation automation.	0.28	Work in progress; work will be completed in 2022-23.
5	5	Tan-Delta Measurement Set (7 No.)	2.51	Work completed
6	9	Insulation Tester for new Substations	1.47	Work completed
7	12	Upgrading of 2 No. 3 Phase Relay testing kits of 400kV protection Hub and SAP Hub	0	Work has been completed
8	13	Loader cum Crane for Amritsar Circle	0.56	Work completed
9	14	Mobile oil filtration sets under P&M Circle (4 No., 6KL/H)	1.11	Work completed
10	15	Construction of Security Huts at 220/132kV Sub stations	3.09	Not approved by BOD's of PSTCL. So work will not be done.
11	16	Re-fixing of UC Fencing at top toe wall to safeguard yard area from fire.	8.07	Not approved by BOD's of PSTCL. So work will not be done.
12	17	Providing Plinths for 2 sets (20 No.) of ERS-Towers at 400kV S/S Rajpura, Nakodar and 220kV Muktsar	0.56	Work completed and capitalised
13	20	Providing AC and Furniture at Kangra Rest House	0.17	Work Completed
Works approved by BOD outside 2nd MYT				
1	-	To provide dry air generators for P&M and Grid Construction organisation	0.45	Work in progress; work will be completed in 2022-23.

Spill Over Works List

Sl. No.	Sl. No. as per C/P Order	Particulars	Network Address	Stage of Work	Project Start Date	Actual Completion Year of completion	Remarks	BID Approved for Contract Period (in Rs)	Total Cost of Project		CAPEX during 2021-22				Capitalization during 2021-22				CAPEX during 2022-23				Capitalization during 2022-23				CAPEX during 2023-24				Capitalization during 2023-24				CAPEX during 2024-25				Capitalization during 2024-25			
									CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total											
									Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total		
Spill Over Works of 1st Contract Period (From FY 2017-18 to FY 2023-24)																																										
1	130	220 KV 575kVA Shiver (Final Piling) 1000 from 60 KV grid with 220 KV cable GIS and 60 KV wire Conventional			27/11/2020	2023-24	Start of work got delayed due to shifting of 11 KV feeders and commencement of rail building work from by PMPCL. The site was started by PMPCL in March, 2021 and work is handed over to the contractor for completion of work. Now the work of tender issue and work is in progress.	4.78	10.3	14.68	1.70	0.31	18.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00							
2	131	L&O of both side of 220 KV 975kVA Substation - 220 KV 975kVA Outdoor Cable 1 line @ 220 KV 975kVA Shiver (Final Piling) (Contract No 2016-16)			1.3/2017	20-24	Price list received on dated 10.07.2022. Work adjustment to be done.	1.11	1.84	0.97	0.18	0.10	0.85	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00							
2	132	220 KV 975kVA Substation (L&O from 60 KV)			11/06/2020	20-24	Work under progress. Work to be completed by 30.06.23	2.84	20.28	1.86	0.32	0.27	2.46	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00							
4	134	220 KV 975kVA Shiver - 220 KV 975kVA Outdoor DC Line			2.3/2017	09-23	RCVM Issues. Work in progress	16.08	21.88	4.50	1.08	0.67	6.26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
5	138	400 KV 975kVA (Dasha) Phase of Village (Dharwad)			30/11/2016	2023-24	This bond was allocated by PDECC and handed over to PWD, dated 12/03/2018. The work was awarded on Tender basis in 12/2018. Work was to be completed by 05/22. This work involved major earth filling which got delayed due to raining season.	37.28	38.62	21.60	5.77	0.48	26.14	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00						
6	130	6 400 KV Bays @ 220 KV Bays @ 400 KV 975kVA Shiver			01-11-2020	Mar 2024	Work under progress. Work to be completed by 30.06.2023	24.23	22.92	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
7	132	400 KV Grid Charnera (near Dasha)					Scope revision on basis of revision of main plan of 220 KV transmission line from 400 KV Charnera and Amalgaon. No. 10/21-22 dated 27.07.21 issued and modified by PWD. Work was to be taken up after clearance of RCVM of these Dasha work sites.	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
		220 KV DC line on DC towers (L&O) from the length Dasha Charnera - Substation conductor of 400KV, 5.0 sq' and Charner Substation conductor of HTLS of 400KV				4.20	1.24	8.65	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
		220 KV DC line on both side towers (L&O) from the length from L&O part of existing Kharwa-Dharwad line (approx 5.5 km from Kharwa) (both Charnera-Substation conductor of 400KV, 5.0 sq' and Charner Substation conductor of HTLS of 400KV)				4.20	1.24	13.972	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
		Replacement of existing conductor of Kharwa with L&O part section with HTLS conductor of 400KV conductor (L&O) (5.07 km)				4.20	1.24	0.298	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
		220 KV DC line on both side towers (only string) for calculating mass of L&O of 400KV conductor line (5.5 sq' at Charnera, on both towers (L&O) on approx line length (between 0.5 sq' work)				4.20	1.24	2.937	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
		220 KV DC line on DC towers (L&O) from the length (400 km approx) from JCSR Dasha (part of main line) line length of (28.437 km, 8.811 km of already existing line shall be work)				04-2022	09-2024	26.921	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00								
9	134	L&O of 1 side of 220 KV Substation (Dasha) (Contract No of 220 KV line of 400 KV Charnera -Substation L&O length-10km 60 sq' at DC towers. (Final work)			04-2022	09-2024		16.264	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
10	136	220 KV Bays (2 Nos. @ Dasha) 975kVA @ Substation including double bus provision of 220 KV and 2 nos ICT bays @ Charnera			22/09/2022	Mar '24		14.562	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									

51 [Handwritten mark]

Spill Over Works List

Sl. No.	Sl. No. as per C/P Order	Particulars	Revised Addition	Scope of Work	Project Start Date	Actual Completion Year of completion	Remarks	C/P Approved for 3rd Contract Period (in Cro)	Total Cost of Project	CAPEX during 2021-22			Capitalization during 2021-22			CAPEX during 2022-23			Capitalization during 2022-23			CAPEX during 2023-24			Capitalization during 2023-24			CAPEX during 2024-25			Capitalization during 2024-25			CAPEX during 2025-26			Capitalization during 2025-26								
										CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total								
										Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total
31	6			Connectivity of 220 kv bus of 400 kv busbar with adding 220 kv bus of G220V-Runner with 4 Nos. Twin mason wire / Approx Length 1 km				4.95	0	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
32	6			L.L.O of one mile of 400 kv Linebus PGCL - Kolkata at proposed 400 kv Sta. Approx. L.L.O length = 1.15 km (approx.). Twin Conductor (Double)	01.04.2022	31.03.2024		30.04	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5.40	1.72	0.01	7.88	0	0	0	0	0	0	14.2	3.95	2.45	22.515	21.8	9.90	3.24	30.448	0	0	0	0								
33	7			L.L.O of 2nd mile of 400 kv Linebus PGCL - Kolkata at proposed 400 kv Sta. Approx. L.L.O length = 1.15 km (approx.). Twin Conductor (Double)	01.04.2022	31.03.2024		27.86	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	5.01	1.2	0.05	6.96	0	0	0	0	0	15.04	3.61	2.28	20.92	20.26	4.82	3.26	27.86	0	0	0	0								
34	6			400 kv bus + 2 Nos.	2023-24	2023-24		0.88	7.5	0.54	0.14	0.82	0.70	0.00	0.00	0.00	0.00	0.00	0.00	0.54	0.14	0.50	0.70	7.5	1.23	0.3	8.82	7.5	1.23	0.3	8.82	0	0	0	0	0	0	0							
35	6	400 kv Busbar (already provided)		L.L.O of 2nd mile of 400 kv Linebus PGCL - Kolkata at proposed 400 kv Sta. Approx. L.L.O length = 1.15 km (approx.). Twin Conductor (Double)	05.23	06.24	Transfer work under process.	2.37	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	1.7	0.42	0.20	2.37	1.7	0.42	0.20	2.37	0	0	0	0								
36	10			400 kv bus + 2 no	2023-24	2023-24		1.19	7.5	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	1.9	0.20	0.08	1.785	0	0	0	0	1.9	0.20	0.08	1.785	0	0	0						
37	12 (A)	220 kv bus		400 kv bus + 2 nos	07.20.22	2023-24	Order placed vide Amendment No. 0923-22 dated 08.08.21 and modified by 060	12.07	0.50	0.00	0.00	0.00	0.00	0.00	1.20	0.03	0.01	0.24	0.44	0.05	0.51	0.50	10	1.9	0.4	11.2	10	1.9	0.4	11.8	0	0	0	0	0	0	0								
38	14	220 kv G.T. Road Linebus (New GIS) in PGCL Lines (approx. 600 m)		220 kv G.T. Road Linebus (New GIS) in PGCL Lines (approx. 600 m) at 220 kv G.T. Road Linebus. L.L.O length = 700 m (approx.). Twin Conductor (Double) (2000 m)	Under Study	Under Study	Under study due to completion of ROW. Trade is being decided by using revenue machinery data incorporated in the GIS. Once the trade is finalized, PPERC will be approached through public during the course of next FY.	38.38	31.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0									
39	10			L.L.O of 220 kv Linebus - Dumurk (2000 m) bus with 220 kv G.T. Road Linebus. L.L.O length = 700 m (approx.). Twin Conductor (Double) (2000 m)	0			12.41	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0.2	0.03	0.08	0.26	0.2	0.03	0.08	0.26	0	0	0	0								
40	18			220 kv bus + 4 Nos.				12.30	10.56	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0										
41	17			80 kv bus + 4 Nos.				0.81	1.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0										
42	18	220 kv Substation (2000 m) bus		220 kv G.T. Road Linebus (New GIS) in PGCL Lines (approx. 600 m) at 220 kv G.T. Road Linebus. L.L.O length = 700 m (approx.). Twin Conductor (Double) (2000 m)	2024-25	2025-26	Purchase of land from PPERC in process.	34.58	31.54	0.00	0.00	0.00	0.00	0.00	0.00	0.18	4.76	0	0	0	0	0	10	1.3	0.4	11.9	8	1.2	0.32	8.32	16	2.4	0.94	19.04	4	0.8	0.18	4.76							
43	19			L.L.O of 220 kv Linebus - Dumurk (2000 m) bus with 220 kv G.T. Road Linebus. L.L.O length = 700 m (approx.). Twin Conductor (Double) (2000 m)	5.2023	3.2024		0.19	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	1	0.26	0.15	1.4	0	0	0	1	0.26	0.15	1.4									

Handwritten marks/signatures.

Spill Over Works List

SI No	SI No. as per CIP Order	Particulars	Network Address	Scope of Work	Project Start Date	Actual Completion Year of completion	Remarks	CIP approved by Ref. Center Part No. (SI-CI)	Total Cost of Project	CAPEX during 2021-23			Capitalization during 2021-23			CAPEX during 2023-25			Capitalization during 2023-25			CAPEX during 2025-28			Capitalization during 2025-28											
										CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total			CAPEX Total			Capitalization Total					
										Works	EC	ICC	Works	EC	ICC	Works	EC	ICC	Works	EC	ICC	Works	EC	ICC	Works	EC	ICC	Works	EC	ICC	Works	EC	ICC	Works	EC	ICC
										Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	Total	
44	20	L.O of 220 KV GGGSP (Completed at 220 KV Cutlumber phase, L.O length 1.54 km) 1.5 kv conductor, OC in DC.			3.3023	3.3024			6.14	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
45	21	220 KV bays + 4NA.			2024-25	2025-26			3.03	2.84	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
46	22	220 KV bays + 8 NA.			2024-25	2025-26			2.64	2.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
47	23	220 KV Havershill (new 4NA in the premises of 220 KV HV Havershill) (Completed CAG for RS for Amendment No. 1121-22)			2022-23	2024-25	Scope revised on basis of request from PPRCL, and Amendment No. 1121-22 dated 24.08.21 issued and notified by DCCL. Right to use not finalized.		16.99	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
48	24	L.O of 220 KV Nepal - Haverhill (new 4NA in the premises of 220 KV HV Haverhill) (Completed CAG for RS for Amendment No. 1121-22)			3.3023	4.3024			2.74	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
49	25	448km/4NA			4.3023	3.3025	Work not started due to unavailability of scope at 220 KV Cutlumber.		1.73	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
50	26	Agreement/contract/letter of intent at 220/220 KV level.			21.22	24.25	Work in progress.		37.53	9.44	1.98	0.04	10.57	8.40	1.28	0.04	10.54	10.00	1.50	0.48	11.30	10	1.5	0.4	11.8	10	1.5	0.4								
51	28	New 220 KV (Slope) including 5.63 of RS 1st.			2025-24	2025-26	Proposal of up gradation has been received from CIL/Coal and CEPR/PRCL to de-rate 220 KV HV (Slope) to 110KV, release of new connections to Kargal area and add 220 KV (Slope) Ducts. Under study due to completion of ROW. Details to be finalized by using modern technology like non-conductor/multi-core lines. Once the route is finalized, PPRCL will be approached through pattern during the course of next MYT.		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
52	31	New 220 KV (Slope) (Haverhill)			2025-24	2025-26	Under study		18.86	26	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
53	32	220 KV Cutlumber including CAG of RS 1st.			13.3020	05-2024	Grid work has to be done in hand only after the completion of the New ROW in place, as grid work has started at site.		6.41	7.27	3.48	0.63	0.51	4.77	0.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
54	33	220 KV Cutlumber including CAG of RS 1st.			2023-23	2023-24			23.48	26.17	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										

59 AS

Spill Over Works List

Sl No	Sl No. as per CIP Order	Particulars	Network Address	Scope of Work	Project Start Date	Actual Completion Year of completion	Remarks	CIP approved for 2nd Contract Part (In C1)	Total Cost of Project	CAPEX during 2021-22				Capitalization during 2021-22				CAPEX during 2022-23				Capitalization during 2022-23				CAPEX during 2023-24				Capitalization during 2023-24				CAPEX during 2024-25				Capitalization during 2024-25				CAPEX during 2025-26				Capitalization during 2025-26			
										CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total			
										Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total
50	36	220 KV Outlets (20) including SA4 of 10.		112 x 14 Meter 1. Double CC bar arrangement by existing one of existing network conductor size 3.2uc (4.0 uc length 7 kbps) etc	2018-20	2023-26		2.47	1.11	-0.01	0.00	0.00	-0.21	0.00	0.00	0.00	0.00	0.25	0.06	0.01	0.32	0	0	0	0	0.20	0.00	0.01	0.21	0	0	0	0	0.25	0.06	0.01	0.32	0.25	0.06	0.01	0.32	0.25	0.06	0.01	0.32				
51	37	9 220 KV Transformers		Asst. 1x110 MVA, 220KV KV TF.	2023-23	2023-24	Work will be completed by 30.06.2023	8.50		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	1.22	0.32	1.64	0	0	0	0	0.20	1.025	0.33	1.615	16.36	2.405	0.94	16.466	0	0	0	0	0.20	1.025	0.33	1.615	16.36	2.405	0.94	16.466	0	0	0	0	
57	46	48 220 KV Phases		Aug. of 12.5 MVA, 8011 KV to 20 MVA, 8011 KV TF.	2023-23	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.20	0.05	0.01	0.26	0.2	0.03	0.08	0.28	2	0.3	0.08	2.36	2	0.3	0.08	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
58	48	48 220 KV Phases		Aug. of 12.5 MVA, 8011 KV to 20 MVA, 8011 KV TF.	2023-23	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.20	0.05	0.01	0.26	0.2	0.03	0.08	0.28	2	0.3	0.08	2.36	2	0.3	0.08	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
59	54	48 220 KV Phases		Aug. of 12.5 MVA, 8011 KV to 20 MVA, 8011 KV TF.	18.06.2020	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.20	0.05	0.01	0.26	0.2	0.03	0.08	0.28	2	0.3	0.08	2.36	2	0.3	0.08	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
60	66	48 110KV Phases		Aug. of 12.5 MVA, 13211 KV to 20 MVA, 13211 KV TF.	01.08.2020	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.02	0.00	0.12	0.1	0.01	0.04	0.11	2	0.3	0.06	2.36	2	0.3	0.06	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
61	61	48 110KV Phases		Aug. of 12.5 MVA, 13211 KV to 20 MVA, 13211 KV TF.	21.06.2020	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.02	0.00	0.12	0.1	0.01	0.04	0.11	2	0.3	0.06	2.36	2	0.3	0.06	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
62	62	48 110KV Phases		Aug. of 12.5 MVA, 8011 KV to 20 MVA, 8011 KV TF.	2023-24	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	2	0.3	0.06	2.36	2	0.3	0.06	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
63	63	48 110KV Phases		Aug. of 12.5 MVA, 13211 KV to 20 MVA, 13211 KV TF.	2023-23	2023-24	Due to COVID, availability of CRGO material has reduced and Transformers landing process slowed down. SC, Transformer supply get affected.	1.81		0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.10	0.02	0.00	0.12	0.1	0.01	0.04	0.11	2	0.3	0.06	2.36	2	0.3	0.06	2.36	0	0	0	0	0	0	0	0	0	0	0	0	0	0			
64	88	Repositioning of bus bars, enclosure in control room building, providing room for electrical storage for station battery etc.		For strengthening of bus - bar arrangement, relocation in control room building for bus adding 200132KV - cables of PSTCL, and per the requirement of Field from West to time, a provision of about 25 Cr. is Rs. 7.2 Cr. a per year has been made.	04-20	25-28	Work under progress. will complete.	23.15	20	1.96	0.46	0.14	2.54	1.52	0.46	0.20	2.20	0.15	1.26	0.40	1.91	0.64	1.23	3.38	10.194	9	1.35	0.36	10.71	9	1.36	0.36	10.71	1	0.15	0.04	1.19	1	0.15	0.04	1.19	0	0	0	0	0	0	0	
65	79	Additional 200132KV bus bars added with feasibility cases or as per PSTCL requirement.		As per the requirement of PSTCL for the feed referred through feasibility cases, a provision of about 25 Cr. a per year has been made for erection of 80x13220 KV bus at various place of PSTCL, Rs. 6.8 Cr. a per year.	04-20	25-28	Work under progress. will complete.	26.85	25	2.47	0.33	0.10	3.00	3.11	0.37	0.20	3.57	11.20	1.85	0.64	13.20	11.88	1.88	0.40	13.70	11.5	1.70	0.40	13.60	11.5	1.70	0.40	13.60	0.5	0.075	0.02	1.50	0.5	0.075	0.02	1.50	0	0	0	0	0	0	0	
66	71	Second source of battery at station 200132 KV bus of PSTCL.		Substance work for 48 bus poles out of these 30 poles are 220 KV & remaining 18 poles are 132 KV bus. Total cost = 13 Cr. a with 20% PSTCL loading & remaining to be arranged through capital investment.	2023-24	2024-25	PSTCL loading sanctioned in the month of March 22 for 87 No. Cables. PSTCL loading is 15 Minutes project date 11.05, PSTCL sanctioned date.	5.21	4.5	0.50	0.50	0.00	1.00	0.50	0.50	0.00	1.00	0.50	0.50	1.00	1	0.15	0.04	1.19	4	0.6	0.16	1.70	3.50	0.80	0.22	4.50	1	0.15	0.04	1.19	1	0.15	0.04	1.19	0	0	0	0	0	0	0		
67	72	80 nos PSTCL poles (200 KV) to be provided with SAC Report already sent for PSTCL loading & approval. These stations will be upgraded.		Cost of one station for SAC Report already sent for PSTCL loading & approval. These stations will be upgraded.	2023-24	25-28	OPR for PSTCL loading referred by M.C.C. POSCOO. Now OPR is being submitted for PSTCL loading.	102.58	108	0.50	0.50	0.00	1.00	0.50	0.50	0.00	1.00	0.50	0.50	1.00	0	0	0	0	30	3	0.8	25.4	30	3	0.8	25.4	40	4	1.6	41.8	40	4	1.6	41.8	20	4.5	1.2	26.7	20	4.5	1.2	26.7	

98

Spill Over Works List

Sl. No.	Sl. No. as per CIP Order	Particulars	Network Address	Scope of Work	Project Start Date	Actual Completion Year of completion	Remarks	CIP approved for Spill Overwork Part (in \$M)	Total Cost of Project	CAPEX during 2021-22				Capitalization during 2021-22				CAPEX during 2022-23				Capitalization during 2022-23				CAPEX during 2023-24				Capitalization during 2023-24				CAPEX during 2024-25				Capitalization during 2024-25				CAPEX during 2025-26				Capitalization during 2025-26			
										CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total			
										Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total				
										0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
		220KV S/S Dandhwa	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Kabanawa	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Kothari	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Sathan Wala	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Himmatpura	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Akshar	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Charanval	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Mahana Jalar	1 No. 500 capacitor between 220 bus bar-1 & bus bar-2																																														
		220KV S/S Kabanawa	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														
		220KV S/S Sathan Wala	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														
		220KV S/S Tahandi Sabar	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														
		220KV S/S Minna	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														
		220KV S/S Himmatpura	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														
		220KV S/S Jaganm	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														
		220KV S/S Akshar	1 No. 500 capacitor between 66 KV bus bar-1 & bus bar-2																																														

6-2

Spill Over Works List

Sl. No.	Sl No. as per C/P Order	Particulars	Network Address	Scope of Work	Project Start Date	Actual Completion Year of completion	Remarks	C/P approved for 2nd Control Panel (in Cr)	Total Cost of Project	CAPEX during 2021-22				Capitalization during 2021-22				CAPEX during 2023-24				Capitalization during 2023-24				CAPEX during 2024-25				Capitalization during 2024-25				CAPEX during 2025-26				Capitalization during 2025-26			
										CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total			
										Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total
										0.14	0.02	0.00	0.21	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.19	0.02	0	0.21	0.2	0.01	0.00	0.20	0.2	0.01	0.00	0.24	0	0	0	0	0	0	0
		220V 50 Lubin Kaban	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		220V 50 Chennakkal	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		220V 50 Mand Chathupok-G-1	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		220V 50 Chaji	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		220V 50 Dhar	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		220V 50 Madak Kaban	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		220V 50 Bedabathur	1 No. bus coupler between 80 kV bus bar-1 & busbar-2																																						
		132V 50 Mags-2 (Chathakkal)	1 No. bus coupler between 100MVA 132kV 117 T-1 & 20MVA 132kV 117 T-2																																						
		132V 50 Samsath Shee	1 No. bus coupler between 20 MVA 132kV 117 T-1 & 1000MVA 132kV 117																																						
		220 kV 50 Katabrenak	1 No. bus coupler between 20 MVA 220kV 101 T-1 & 101 T-2 MVA 220kV 101 T-1																																						
		220 kV 50 Piyakkas	1 No. 11 kV bus coupler																																						
		220 kV 50 Nigale	1 No. 11 kV bus coupler																																						
3	Amendments No. 14/2021-22	Upgradation of 66 kV substation Chhatra to 220 kV substation.	220103 MVA, 220/66 kV 7F 100.2 No. 220 kV bus bars, 3 No. 7F bays and 1No. Bus coupler bay		2023-24	2025-26	RCV work is undertaken. Substation will be moved from after RCV and right to use by PSCCL.		01.21	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00				
		14.0 of one C/P of 220 kV Substation. Details see C/P on DC 19 bus (after conductor 400 mm ²).			A.2022	03-2023			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00					

Spill Over Works List

Proj. No.	SP No. or SP Code	Facilities	Account Address	Start of Work	Project Start Date	Actual Completion Date	Remarks	SP No. or SP Code	SP Description	2002-03												2003-04															
										Budget during 2002-03				Expenditure during 2002-03				CAPEX during 2002-03				Capitalization during 2002-03				CAPEX during 2003-04				Capitalization during 2003-04							
										Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total				
			From SP1 to Page 3 math for SPs for Tabular work, Meter & GNDP							0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8	Amendments No. 23(2002-03)	220 KV S/S Meter	Approximation of 1 No. 100 Amps 1P or 220KV S/S Meter to 180 MVA.		2023-24	2023-24	Tender for procurement of TP under process.		11.87	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9	Amendments No. 23(2002-03)	220 KV Live Vapour Pad	Shifting of 220 KV S/S Meter Vapour Pad from 220 KV Vapour to 800 KV (under 20KV, 4 Bay)		8/2002	3/2004	Tendering work in progress.		3.50	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	2.41	0.17	0.36	3.54	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
10	Amendments No. 23(2002-03)	220 KV S/S Meter 2	220 KV 2 No. Bay		2023-24	2024-25	Work completed by 24.25		5.13	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
11	Amendments No. 23(2002-03)	220 KV S/S Winding G-connection	Additional Set 220KV S/S 100 MVA, Aux. TP		2023-24	2023-24	Tender for procurement of TP under process.		11.32	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	10.30	1.55	0.41	12.26	10.30	1.55	0.41	12.26	0.00	0.00	0.00	0.00
12	Amendments No. 23(2002-03)	Installation of capacitor banks at various S/S					Work in progress		12.36	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	4.35	0.45	0.17	5.18	4.35	0.45	0.17	5.18	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		22KV S/S Corals	4010.880 MVAR, 88 KV Capacitor Bank at 22KV S/S Corals		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Sandman	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Charnival	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Bower	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Omeze	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Yelow	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Cheques	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Cheta Sable	2010.880 MVAR, 88 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
		22KV S/S Binge	2010.880 MVAR, 132 KV Capacitor Bank		2022-23	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	

16
AS

Spill Over Works List

R/In.	R/In. as per CP Code	Particulars	Network Address	Scope of Work	Project Start Date	Actual Anticipated Year of completion	Remarks	CIP Approved for this Contract Part of (R/In. CP)	Total Cost of Project	CAPEX during 2021-22		CAPEX during 2022-23				CAPEX during 2023-24				CAPEX during 2024-25				CAPEX during 2025-26				CAPEX during 2026-27									
										CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total		CAPEX Total		Capitalization Total					
										Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total
										0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
		22KV S/S Busbar	2015.00010001.132 KV Capacitor Bank		2021-22	2023-24																															
		22KV S/S Handcoper	2015.00010001.00 KV Capacitor Bank		2021-23	2023-24																															
		28 KV S/S Sub-Range	2015.00010001.120KV Capacitor Bank		2021-23	2023-24																															
13	Amendment No. 01/2023-23	22KV Substation (SAC) Bus at KV substation (understand)	ERC of 22 KV Substation to 220 KV with installation of 22KV SPSA, 220KV S/S Handcoper (SAC) Bus at KV) (S.S. Length: 2.1 Km approx., S.F., SFC on SAC)		2023-24	2024-25	Right to use sought from PSPCL. SCS will be constructed after obtaining right to use and ROW issues as SCS will be in congested area of Discom.		26.148	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
			S.S. Length: 2.1 Km approx., S.F., SFC on SAC		19-23	2023-24			4.498	0.00	0.00	0.00	0.00	0.00	0.00	0.00	1.90	0.36	0.24	2.22	1.8	0.36	0.24	2.22	1.4	0.36	0.24	2.22	1.4	0.36	0.24	2.22					
			Substation Antennas (Three SAC) (S.S. - 1 Km.)		2023-24	2023-24			1.21	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
14	Amendment No. 03/2023-23	22KV S/S Busbar	Upgradation of 2 nos. 220 KV SPSA Transformers at 220 KV Substation Bus to 780 KV SPSA		2023-24	2023-24	TF procurement under process		11.524	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
15	Amend 04/23-23	22KV SPSA, Antenna	Shifting of 22KV SPSA Transformer from Bus 220KV to Bus 220KV (S.S. Length: 2.1 Km approx., S.F., SFC on SAC)		1.2022	1.2024	Survey tender work in process.		0.476	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
16	Amend 06/23-23	22KV SPSA SCS	Upgradation of 2 nos. 220 KV SPSA Transformers at 220 KV Substation MOD-1 to 380 KV SPSA		2023-23	2023-24	TF procurement under process.		25.648	0.00	0.00	0.00	0.00	0.00	0.00	0.00	10.00	1.50	0.40	11.80	10	1.5	0.4	11.9	10.3	1.53	0.408	12.136	10.3	1.53	0.408	12.136					
17	Amend 07/23-23	22KV S/S Check (SAC) Bus at KV	Creation of 220 KV Check Bus at KV substation with 1.1 KV SPSA S/S Bus from SAC of 220 KV SPSA Bus. (S.S. Length: 1.137 Km and 1 SAC bus)		2023-24	2024-25	Right to use not finalized.		27.175	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
			S.S. Length: 1.137 Km and 1 SAC bus		4.2020	3.2024	Survey tender work in process.		0.330	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
18	Amendment No. 05-23	22KV SPSA	1 No. 24 A.M.B. at 220 KV SPSA (S.S. Length: 1.137 Km)		2023-24	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
		22KV S/S Range	1 No. 24 A.M.B. at 220 KV SPSA (S.S. Length: 1.137 Km)		2023-24	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
		22KV S/S Cover	1 No. 24 A.M.B. at 220 KV SPSA (S.S. Length: 1.137 Km)		2023-24	2023-24			0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									

92

Spill Over Works List

S.No.	S/No. of SP CSP Draw	Particulars	Element Address	Start & End Dates	Period Start Date	Period End Date	CSP Approved by the Director Period (in Rs)	Total Cost of Project	CAPEX during 2023-24				Capitalization during 2023-24				CAPEX during 2024-25				Capitalization during 2024-25				CAPEX during 2025-26				Capitalization during 2025-26												
									CAPEX Year		Capitalization Year		CAPEX Year		Capitalization Year		CAPEX Year		Capitalization Year		CAPEX Year		Capitalization Year		CAPEX Year		Capitalization Year														
									Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total	Works	EC	EC	Total					
	226 KV Stepdown Drip)	1 No. 20 MVA M21 EV 3T	2023-24	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Step-3 (Dripless)	1 No. 3rd Additional 20 MVA 2001 EV20	2023-24	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
	226 KV Step-4	1 No. 3rd Additional 20 MVA 2001 EV20P	2023-24	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Overpass	1 No. 06 Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Steel Poles	1 No. 3rd Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Handover	1 No. 3rd Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Aerial	1 No. 3rd Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Chokers	Aug of 1 no. 20 MVA with 21.5 MVA, M21 EV	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Poles	1 No. 06 Additional 20 MVA 2001 EV20P	2023-24	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Handover (Over Bank)	Aug of 1 no. 20 MVA with 21.5 MVA, M21 EV	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Stone	1 No. 06 Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Overpass	1 No. 3rd Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Poles	Aug of 1 no. 20 MVA with 21.5 MVA, M21 EV (Additional 22 MVA, M21 EV SP SP planned by MYTC-2024-25. No. 21 may be considered as added)	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
	226 KV Overpass Handover	1 No. 3rd Additional 20 MVA 2001 EV20P	2023-23	2023-24					0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

93 AB

Spill Over Works List

Sl. No.	Sl. No. as per CP Order	Particulars	Network Addition	Category of Work	Project Start Date	Actual Anticipated Year of completion	Remarks	GIP approved for 3rd Central Plan (PCC)	Total Cost of Project	CAPEX during 2021-22				Capitalization during 2021-22				CAPEX during 2022-23				Capitalization during 2022-23				CAPEX during 2023-24				Capitalization during 2023-24				CAPEX during 2024-25				Capitalization during 2024-25				CAPEX during 2025-26				Capitalization during 2025-26			
										CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total				CAPEX Total				Capitalization Total			
										Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total	Works	EC	ICC	Total				
19	Amendments WPS-23	Development of amenability of Transmission Line in PNHK Circle to extend the existing overloading of cables line					Vendor for cable survey is being finalized		34,883	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		A. Transferring 228 KV Pigeon - 400 KV Pigeon (Single strand at 228 KV) (Length: 1.00 km)			4-22	2023-24				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		B. Connecting 228 KV (Single strand at 228 KV) Pigeon (Length: 1.00 km)			4-20	2023-24				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		C. Connecting 400 KV Pigeon to 228 KV Pigeon (Including one set of approx. 1 km length, ICC as per GIP)			4-22	2023-24				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		D. Connecting 400 KV Pigeon to 228 KV (Single strand at 228 KV) Pigeon (Including one set of approx. 1 km length, ICC as per GIP)			4-20	2023-24				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		E. 7 Nos. 228 KV taps at 400 KV Pigeon			2023-24	2023-24				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		F. 228 KV 100m line extension (including one set of approx. 1 km length, ICC as per GIP)			2023-24	2023-24				0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		Total (D)							769.20	1.00	0.12	0.05	1.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00												
										0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00												
GRAND TOTAL										769.20	1.00	0.12	0.05	1.23	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									
P&M Works																																																	
1	4	Top Talker and detection for the testing of transformer oil					Work is in progress. Vendor under consideration of OCP/PAAL work will call over to 3rd CP of all		6.15	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
2	3	PSCV testing for the GPTL					Work will call over to 3rd CP of all items of this work as indicated and above list could not be arranged due to COVID in GPTL		0.30	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
3	5	Removal Central operation of 400KV S/S, Muzkur, Mahabub and Mahabub stations					Work will call over to 3rd CP of all items of this work as indicated and above list could not be arranged due to COVID in GPTL		1.76	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
4	10	Online partially discharge 10 equipment for 400 KV S/S at 400KV S/S (14 Nos)					Work will call over to 3rd CP of all items of this work as indicated and above list could not be arranged due to COVID in GPTL		10.20	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
5	11	OMM Control Panel over measurement meter for maintenance pump					Work will call over to 3rd CP of all items of this work as indicated and above list could not be arranged due to COVID in GPTL		1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00										
6	10	Flashing ICC Meter at 220KV S/S to facilitate movement of heavy vehicle loadoff with equipment					At end of 31-3-23 the expenditure will be Rs 7.21 Cr and below cost of 3.7 Cr will call over to 3rd CP		30.81	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11											
7	10	Flashing ICC to be put into in 220KV S/S					At end of 31-3-23 the expenditure will be Rs 0.80 Cr and below cost of 0.40 Cr will call over to 3rd CP		10.00	0.10	0.00	0.00	0.10	0.10	0.00	0.00	0.10	0.10	0.00	0.00	0.10	0.10	0.00	0.00	0.10	0.10	0.00	0.00	0.10	0.10	0.00	0.00	0.10	0.10	0.00	0.00	0.10	0.10											
8	7	Test of 1000 kV CPTM test by PGDA under average 1/4 for other South working bank					Work is being done by PGDA and will call over to 3rd CP. Further approved by PGRCL on 26.03.2024 as per 7.2 Cr and being called for E&M at communication Designing has been offered to P&M reg		1.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00											
		Total (E)							47.71	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11	0.11	0.00	0.00	0.11												
Total Spill over of Transmission works										1232.64	1.11	0.12	0.05	1.34	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00									

nb
AS

New Transmission Works Planned for 3rd Control Period (2023-26)

Sr. No.	Substation Name	Scope of work	Remarks	CAPEX CDS1																CAPITALISATION COST																	
				Project Cost				TOTAL Exp. in 2023-24				TOTAL Exp. in 2024-25				TOTAL Exp. in 2025-26				Grand TOTAL																	
				Cost	ECR 15%	ECR 4%	TOTAL (T1)	Cost	ECR 15%	ECR 4%	TOTAL (T2)	Cost	ECR 15%	ECR 4%	TOTAL (T3)	T1+T2+T3	Cost	ECR 15%	ECR 4%	TOTAL (T1)	Cost	ECR 15%	ECR 4%	TOTAL (T2)	Cost	ECR 15%	ECR 4%	TOTAL (T3)	T1+T2+T3								
TS Works																																					
1	220 KV S/S GNDTP	Additional 100 MVA, 220/66 KV transformer including 66KV busbar extension (25CMVA 132/66KV will be spared)	The local Bethwa-Giddabaha-Makut area is primarily fed from 220 KV Makur, Muktesar and GNDTP substations via 132 KV sub-stations of this area. In case of failure of any one source, the total supply falls, leading to blackout. So to give relief to 132 KV system, 66 KV feeds are planned to be shifted from 132 KV system to 220 KV systems. This will also eliminate one additional step of 132/66 KV transformers thereby reducing transformation losses.	12.36	1.85	0.48	14.71	12.36	1.85	0.49	14.71	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	12.36	1.85	0.49	14.71									14.71	
2	Upgradation of 66 KV Bhalsana to 220 KV sub-station	Creation of 220KV Bhalsana with 2x100MVA, 220/66KV T/F (2 line bays, 2 T/F bays & 1 no. Bus Coupler bay) LILO of 5VC 220 KV Muktesar - 220 KV Makut line (L/LO Length 1km, 0.45%)	This S/S has been proposed by PSPCL & is situated in the center of Muktesar & Bethwa. The S/S will give relief to 132KV Muktesar, GNDTP, Makut & 220KV Muktesar. PSPCL will connect 66 KV link from Bhalsana to Dode and Kandi to deliver 5x100 MVA, 220/132 KV auto transformers at 220 KV Muktesar along with 132 KV link lines between 220 KV Muktesar and 132 KV Muktesar. At this S/S the 2nd 100 MVA T/F will be installed after sparing 100 MVA Power T/F from some other work where the augmentation of 100MVA to 160MVA is planned.	26.99	4.05	1.06	32.12	2.70	0.40	0.11	3.21	5.40	0.81	0.22	6.42	8.10	1.21	0.32	9.64																		8.89
3	Upgradation of 66 KV Guru Hari Sahel to 220 KV sub-station	Creation of 220KV Guru Har-Sahel with 2x100MVA, 220/66KV T/F (4 line bays at Guru Hari Sahel, 2bays each at Ghubays & Jhoke Hari Har, 2 T/F bays & 1 no. Bus coupler bay) DC line from 220 KV Ghubays and DC line from 220 KV Jhoke Hari Har (Line length 35km & 30km, 0.45%)	PSPCL had proposed upgradation of 66 KV S/S Jwan Arjan to 220 KV S/S to deliver 220 KV S/S Ghubays but as the transfer of land owned by Village Panchayat has not been made for upgradation of 220 KV S/S Jwan Arjan as nearby 66 KV Guru Hansahal was agreed upon for upgradation to a 220 KV S/S by both PSTCL and PSPCL to deliver Ghubays and Seelki in TPC meeting dated 19.07.2022. This S/S would be connected by DC from 220 KV Ghubays and 220 KV Jhoke Hari Har. At this S/S the 2nd 100 MVA T/F will be installed after sparing 100 MVA Power T/F from some other work where the augmentation of 100MVA to 160MVA is planned. The initial towers at Guru Hansahal will be multi circuit towers to address the issue of ROW. As per PSEIC notification dated 5/11/2018 (Annexure-A) intra-state-transmission project costing more than Rs. 50Cr. are to be developed through TDCB. Cost of this project is more than 50Cr, but work being a brown field project and technical upgradation as such exemption may be given from TDCB in line with Ministry of Power, Govt. of India Letter no. 15/2020 (1) Trans-RIU dated 15.3.2021 (Annexure-B)	111.28	16.66	4.45	132.40	11.13	1.67	0.45	13.24	22.25	3.34	0.80	26.46	33.38	5.01	1.34	39.72																		0.00
4	Upgradation of 132 KV Samadh Bhel to 220 KV level	Creation of 220KV Samadh Bhel with 1x100MVA, 220/132KV T/F (4 line bays, 1 T/F bay & 1 no. Bus Coupler Bay) LILO of both circuits of 220 KV Bigharpuram - Bajbarhane line (L/LO Length - 8km, 0.45%)	This S/S will give relief to 220 KV Hirvatpura by shifting of load of 66 KV Deena Sahel and 66 KV Pallo Hira. In addition, it will provide second source of supply to 132 KV Ghobar Kalan and Smadh Bhel, which are now regularly fed from 220 KV Moga and face blackout in case of tripping of 132 KV S/C line from 220 KV Moga	33.78	5.06	1.35	40.17	6.75	1.01	0.27	8.03	10.13	1.52	0.41	12.05	16.66	2.53	0.66	20.09																		46.17
5	Upgradation of 66 KV Chaheru to 220 KV level (2nd 100MVA, 220/66KV T/F for N-1)	Creation of 220KV Chaheru with 2x100MVA, 220/66KV T/F (4 line bays, 2 T/F bays & 1 no. Bus coupler bay) LILO of 400 KV Heliodar - 220 KV Hosharpur and Nekojar - Rahana Jarban 220 KV Cts at Proposed 220KV S/S Chaheru (L/LO Length - 6km, 0.45%)	This S/S is proposed by PSPCL, to cater load growth and to give relief to Jarbaner, Phagwara and Rahana Jarban as agreed upon in the TPC meeting (Sr. no. 9 of Table-15). At this S/S the 2nd 100 MVA T/F will be installed after sparing 100 MVA Power T/F from some other work where the augmentation of 100MVA to 160MVA is planned.	42.87	6.43	1.71	51.82	4.29	0.64	0.17	5.10	8.57	1.26	0.34	10.20	12.86	1.90	0.51	15.30																		8.89

95
AS

Sr. No.	Substation Name	Scope of work	Remarks	Total Cost	CAPEX COST												CAPITULATION COST															
					ECG 15%				ECG 4%				Project Cost				TOTAL Exp. in 2023-24				TOTAL Exp. in 2024-25				TOTAL Exp. in 2025-26				Grand TOTAL			
					Cost	ECG 15%	ECG 4%	TOTAL (T1)	Cost	ECG 15%	ECG 4%	TOTAL (T2)	Cost	ECG 15%	ECG 4%	TOTAL (T3)	T1+T2+T3	Cost	ECG 15%	ECG 4%	TOTAL (T1)	Cost	ECG 15%	ECG 4%	TOTAL (T2)	Cost	ECG 15%	ECG 4%	TOTAL (T3)	T1+T2+T3		
10	Upgradation of 66 KV Toot to 220 KV level.	Creation of 220KV Toot with 2x100MVA, 220/66KV T/F (2 line bays, 2 T/F bays & 1no. Bus Coupler Bay) LLO of one circuit of 400 KV Main/220 KV Algor line at Proposed 220KV 66 KV Toot (7km, 0.45q)	Proposed by PSPCL to give relief to 220KV Palli and additionally no space is available at 220 KV Palli to establish a 66 KV bay for second circuit to 66 KV Toot from 220 KV Palli S/S. The proposal was agreed upon in the TPC meeting by both PSPCL and PSTCL (Sr. No. 12 of Table-6) At this S/S the 3rd 100 MVA T/F will be installed after spacing 100 MVA Power T/F from some other work where the augmentation of 100MVA to 160MVA is planned.	34.18	5.13	1.37	40.67	3.42	0.51	0.14	4.07	8.84	1.03	0.27	8.13	10.25	1.54	0.41	12.20	24.40									9.00			
11	Double bus arrangement at 220 KV Island Gobindgarh - 2		Proposed by Chief Engineer/P&M, PSTCL to provide reliability of supply to industrial consumers by providing a 220 KV double bus bar as per the CEA norms as in case of failure of single available bus there is a complete blackout.	14.98	2.10	0.56	18.64	0.00	0.00	0.00	0.00	0.00	0.00	0.00	14.00	2.10	0.56	16.66	16.66									16.66				
12	Upgradation of 132 KV Jandiala Guru to 220 KV level	Creation of 220KV Jandiala Guru with 2x100MVA, 220/132KV T/F (2 line bays, 2 T/F bays & 1no. Bus Coupler Bay) LLO of 220 KV Butari - Verpal circuit on multi-circuit Tower/Modern techniques at Jandiala Guru (4km, 0.45q)	To address the problems in the vested city of Amritsar a committee was constituted by Director/IT. As per recommendation of committee to give reliable supply to Amritsar city it was proposed to upgrade Jandiala by shifting auto transformer 220/132 KV 100 MVA being spinned from Butari to island power at Verpal to provide reliable supply in event of constraints in Butari-Verpal DIC line or 132 KV bus at Verpal. PSTCL & PSPCL agreed to the proposal in the TPC meeting (Sr. No. 6 of Table-6 of MOM) In this case the 1 No. 220/132 KV auto T/F will be shifted from Butari, after the commissioning of 220 KV Beas.	35.12	5.27	1.40	41.79	7.02	1.00	0.28	8.36	10.54	1.58	0.42	12.54	17.56	2.83	0.70	20.50	41.79									35.12			
13	Upgradation of 132 KV Tandi to 220 KV level	Creation of 220KV Tandi with 1x100MVA, 220/132KV T/F and 1x100MVA, 220/66KV T/F (2 line bays, 2 T/F bays & 1no. Bus Coupler Bay) LLO of SIC 220 KV BDMB Jalandhar-Deoghar line (4.5km, 0.45q)	Proposed by P&M, PSTCL with one 220/132 KV auto-transformer, to provide cushioning effect to the sharp drop in voltage at MPT/Tandi/Bhogpur areas. This voltage drop sometimes leads to tripping of machines causing blackout. In addition to it, it will give relief to the 132 KV system in Tandi/Bhogpur but when there is no generation at MPT as being a run of the river plant, it faces frequent problems of out. Apart from 2 other bus sources feeding this area are almost fully loaded i.e. BDMB Jalandhar and 132 KV Haripur-Chahal line. PSPCL agreed that 132.66 KV transformers at Bhogpur are fully loaded i.e. more than 90% and two 66KV stations Jandiala Jullana and Kalyapur will be shifted from 132 KV Bhogpur to 132 KV Tandi, for which one 100 MVA, 220/66 KV T/F is also required.	36.71	5.51	1.47	43.69	7.34	1.10	0.29	8.74	11.01	1.66	0.44	13.11	18.36	2.75	0.73	21.84	43.69									36.71			

76

AS

Sr. No.	Substation Name	Scope of work	Remarks	CAPEX COST														CAPITALISATION COST																								
				Total Cost		ECR	DCR	Project Cost		TOTAL Exp. In 2023-24			TOTAL Exp. In 2024-25			TOTAL Exp. In 2025-26			Grand TOTAL	TOTAL Exp. In 2023-24			TOTAL Exp. In 2024-25			TOTAL Exp. In 2025-26			Grand TOTAL													
						%	%																																			
				Cost	ECR 15%	DCR 4%	TOTAL (T1)	Cost	ECR 15%	DCR 4%	TOTAL (T2)	Cost	ECR 15%	DCR 4%	TOTAL (T3)	T1+T2+T3	Cost	ECR 15%	DCR 4%	TOTAL (T1)	Cost	ECR 15%	DCR 4%	TOTAL (T2)	Cost	ECR 15%	DCR 4%	TOTAL (T3)	T1+T2+T3													
14	Upgradation of 132 KV Sri Hargobindpur to 220 KV level (1X100 MVA, 220/132 KV + 1x100 MVA, 220/90 KV T/Fs (2 line bays, 2 T/F bays & 1 no. Bus Coupler Bay)	Creation of 220KV Sri Hargobindpur with 1x100MVA, 220/132KV & 1x100MVA, 220/90KV T/Fs (2 line bays, 2 T/F bays & 1 no. Bus Coupler Bay)	This work is required for evacuation of downstream network of 400 KV Wadala Granthan. In addition it will address the problems of constraints at MSF when all the machines are shut due to low water or high salt at MSF is a run off the river project. PSTCL & PSPCL agreed on this as per Sr. no. 2 of Table-D and Sr. No 9 of supplementary agenda in MOM of TPC. Apart from this auto-transformers at Wadala granthan are fully loaded.	67.31	10.10	2.89	88.18	6.73	1.01	0.27	8.01	13.46	2.02	0.54	16.02	20.19	3.03	0.81	24.03	48.86																						
	220 KV D/C Line From Proposed 400 KV S/S Wadala Granthan (28km, 0.45q)	Keeping in view the ROW issues, some towers near the S/S will be multi circuit towers and the work of substation shall be taken in hand when major work of transmission line is complete.																																								
	132 KV line from W/S and 132/66 KV T/Fs will be spared)	As per PSERC notification dated 5/11/2018 (Annexure-A) Intra-state transmission project costing more than Rs. 50Cr. are to be developed through TBCS. Cost of this project is more than 50Cr. but work being a brown field project and technical upgradation as such exemption may be given from TBCS Mode in line with Ministry of Power, Govt. of India Letter no. 15/2017-Tra-PS (1) dated 15.3.2021 (Annexure-B)																																								
18	Re-arrangement to provide 2nd connectivity to 220 KV S/S Narsingah	Double circuit from 220KV Khessa-Chogawan, 12 Km, 0.4 Sq"	As per report of Committee constituted to provide reliable supply to the city of Ambar, the committee recommended to provide second source of supply to 220 KV Narsingah which is now a radial station because in case towers of the existing line fail, there will be complete black out in major part of Ambar city. So a re-arrangement has been proposed to further link Narsingah to Chogawan/Civil Lines.	48.44	6.82	1.82	54.87	8.00	1.36	0.36	10.81	13.63	2.04	0.55	16.22	22.72	3.41	0.91	27.04	54.87	9.08	1.36	0.36	10.81	13.63	2.04	0.55	16.22	22.72	3.41	0.91	27.04	54.87									
	Disconnecting 220KV Khessa - Civil Line ASR circuit and Chogawan- Khessa circuit from Khessa and diverting them to Narsingah																																									
	1 no. circuit between 220KV Chogawan - Narsingah and 1 no. circuit between 220KV Civil Line ASR - Narsingah, D/C line with 12.5 Km 0.45q"																																									
16	220 KV S/S Bajalthana	Double bus arrangement at Bajalthana	Bayethane evacuates power from GHTP and PGCL Mags, so to provide reliability of supply, double busbar of 220 KV is proposed as per the requirement of Chief Engineer PLM, PSTCL.	16.59	2.48	0.66	19.84	8.25	1.24	0.33	9.82	8.25	1.24	0.33	9.82	0.00	0.00	0.00	0.00	19.84																						
17	220KV S/S Goraya (Add. 220/90KV 100MVA T/F for N-1 compliance)	Connectivity of 220KV Nuumahal with 220KV Goraya with D/C line (length - 25km, 0.45q") (LLO of both circuits of BBMB Jalandhar-Jamalur line at Goraya subject to approval of Power Sub-committee of BBMB)	To provide 2nd source of supply to Nuumahal as now it is fed radially from 400 KV Nalokar. In case towers of the existing line fail, there will be complete black out in Nuumahal area. Apart from this when ORSSDTP roped is down, Goraya is fed from Jalandhar via Kotla-Junga-Kartapur-PGCL, Jalandhar. If Nuumahal is connected to 400 KV Nalokar via Nuumahal, then from Jalandhar will reduce and it will give relief to 220 KV PGCL, Jalandhar-Kartapur D/C line LLO of both circuits of BBMB Jalandhar-Jamalur line at Goraya (if approved by Power Sub-committee of BBMB) will give relief to both Jalandhar and Ludhiana local points/industrial belts when generation of BBMB is been period is down i.e. at Pong, Bhakra, Gangwal and Dabur.	43.97	6.60	1.76	52.33	8.79	1.32	0.36	10.47	21.96	3.30	0.88	26.16	13.19	1.98	0.53	15.70	52.33																						

86


Sr. No.	Substation Name	Scope of work	Remarks	Project Cost			CAPEX COST													CAPITULATION COST																			
				Total Cost	ECG	15%	ECG	4%	TOTAL Exp. in 2023-24			TOTAL Exp. in 2024-25			TOTAL Exp. in 2025-26			Grand TOTAL	TOTAL Exp. in 2023-24			TOTAL Exp. in 2024-25			TOTAL Exp. in 2025-26			Grand TOTAL											
								Cost	ECG	15%	ECG	4%	TOTAL (T1)	Cost	ECG	15%	ECG	4%	TOTAL (T2)	Cost	ECG	15%	ECG	4%	TOTAL (T3)	T1+T2+T3	Cost	ECG	15%	ECG	4%	TOTAL (T2)	Cost	ECG	15%	ECG	4%	TOTAL (T3)	T1+T2+T3
18	400KV Wadale Granthin	<p>Stage 1: Creation of 400KV Wadale Granthin with 2x500MVA, 400/220KV ICTs (2no. 400 KV line bays, 2no. 400 KV ICT bays, 2 no. 400 KV Tie Bays, 4 no. 220 KV Line bays, 4 no. 220 KV bus interconnection bay, 2 no. 220 KV ICT bays, 1 no. 220 KV TBC bay, 1 no. 220 KV BC bay)</p> <p>LILO of 1 circuit of 400 KV Moga - Kishanpur line (20km, Quad Moose)</p> <p>Stage 2: Add: 1X500 MVA, 400/220 KV ICT (2 line bays, 1 ICT bays & 2 no. Tie Bays)</p> <p>LILO of 2nd circuit of 400 KV Moga - Kishanpur line (20km, Quad moose)</p>	To enhance ATC/ITC limit of Purjab.	363.22	45.48	12.13	340.83	0.00	0.00	0.00	75.81	11.37	3.03	90.21	75.81	11.37	3.03	90.21	186.42																				
<p>Cost of this project is more than 50 Cr. but work being a brown field project (land of existing 220KV SIS Wadale Granthin is to be used) and technical upgradation as such exemption may be given from competitive bidding in line with Ministry of Power, Govt. of India Letter no. 15/02011-Trans-P(1) dated 15.3.2021 (Annexure-B) (Expenditure: 25% in 2024-25; 25% in 2025-26 and balance 50% to split over in 26-27.)</p>																																							
19	400 KV Mektu	To give second ISTS connectivity	Under Study	8.88	0.00	0.00	8.88	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
20	220 KV Sulapur	LILO of one circuit 220 KV Karaj-Science city at 220 KV Sulapur with Moose conductor (28Kms, 0.5 Sq)	To provide 2nd source of supply to 220 KV Science city as now it is fed radially from 220 KV Karaj. In case towers of the existing line fail, there will be complete black out in some areas of Jalnagar.	48.44	6.09	1.62	48.31	0.00	0.00	0.00	0.00	20.30	3.05	0.81	24.16	20.30	3.05	0.81	24.16	48.31																			
21	To provide second source to 220 KV SIS Badvi Kalan		Under study	8.88	0.00	0.00	8.88	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
22	220 KV Jada	LILO of MISS Ganguwal-Dhanrau at Jada (2 km, 0.4")	When GGSSTP stoper is down Gonyu/Banga/Jada are fed from Jamher via Kolla Junga -Kartarpur -PGCIL, Jalnagar, thereby overloading the system. This will give additional source of power especially to Jada/ Barga SS's from Ganguwal and 400 KV Dhanrau	4.85	0.73	0.19	5.77	0.00	0.00	0.00	0.00	2.43	0.36	0.10	2.89	2.43	0.36	0.10	2.89	5.77																			
23	220KV PGCL Panchkula (Barwala) - Darabasi Line	220KV PGCL Panchkula (Barwala) -Darabasi Line (DC) (14km, 0.45Sq)	To feed upcoming loads in Lahu, Mubarnapur, Dera Basal etc. additional source of supply is required to give relief to 400 KV Rajgadh-Lahu circuit and Hothgadh-Mohal circuits. Tripping of Mohal-2 to Lahu circuit will cause constraint on Lahu-Dera Basal-Mubarnapur-Mohal-2 S/C line. Subject to the approval of NRPC.	22.23	3.33	0.88	26.45	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	22.23	3.33	0.88	26.45	26.45																			
24	Strengthening of Verla-Mal Mandi Link and to establish link with CIVL Lines ASR	<p>(A) Disconnecting 132 KV Verla - Mal Mandi link and 132 KV Verla - Jyotipura link.</p> <p>(B) Connecting 132 KV Mal Mandi with 132 KV Jyotipura.</p> <p>(C) Connecting 132 KV CIVL lines ASR with 132 KV Verla (overhead 15 km + 1 km modern techniques)</p> <p>(D) Connecting 132 KV CIVL lines ASR with 132 KV Mal Mandi. (overhead 26 km + 1 km underground)</p>	In case of failure of supply from Verla, additional source of power from spare available capacity at 220 KV CIVL Lines Jyotipura not only to Mal Mandi but also Kuthnangal and Jyotipura to de-load 132 KV Sarana-Gundapur Line.	8.88	0.00	0.00	8.88	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00				
				16.59	2.49	0.66	19.74	16.59	2.49	0.66	19.74									19.74	16.59	2.49	0.66	19.74															
				12.88	1.81	0.48	14.38	12.08	1.81	0.48	14.38									14.38	12.08	1.81	0.48	14.38															
				26.89	4.03	1.08	32.00					26.89	4.03	1.08	32.00					32.00	26.89	4.03	1.08	32.00															

66

Sr. No.	Substation Name	Scope of work	Remarks	CAPEX COST																CAPITALISATION COST												
				Total Cost			Project Cost			TOTAL Exp. In 2023-24				TOTAL Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL		TOTAL Exp. In 2023-24			TOTAL Exp. In 2024-25			TOTAL Exp. In 2025-26		Grand TOTAL
				ECR15%	ECR4%		Cost	ECR15%	ECR4%	TOTAL (T1)	Cost	ECR15%	ECR4%	TOTAL (T2)	Cost	ECR15%	ECR4%	TOTAL (T3)	T1+T2+T3	Cost	ECR15%	ECR4%	TOTAL (T1)	Cost	ECR15%	ECR4%	TOTAL (T2)	Cost	ECR15%	ECR4%	TOTAL (T3)	T1+T2+T3
25	Requirement of Capacitor bank at various S/Ss as per CPRI report	Under study as per CPRI report	Final CPRI report on system studies of capacitor requirement in Northern region for the year 2019-20 has been received when in additional net capacitor banks for Punjab at various sub-stations has been recommended. In view of this, PSTCL is working to finalise the net requirement of capacitor banks to meet with the requirement of above recommendations. Further, PSTCL has started the installation of available 132 kV capacitor banks at various substations of PSTCL. PSDF funding shall also be explored.	9.80	0.00	0.00	9.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
26	400 KV Rupura	4th 500 MVA additional T/F	To achieve AT/GTTC limit of 5000/10000 MW	32.88	4.80	1.28	38.88	5.00	0.75	0.20	5.95	27.00	4.05	1.08	32.13	0.00	0.00	0.00	38.88	32.00	4.80	1.28	38.08							38.88		
27	To curtail overloading during W-1 conditions of Shimen-Kangra-Patnaht corridor	Under Study	PSDF funding, if permissible shall be availed.	9.80	0.00	0.00	9.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00															
28	S/C on DIC line from 400 KV Dhuri to 220 KV Bhawanigarh. Buy available at 400 KV Dhuri (18 km)		To provide 2nd source of supply to 220 KV Bhawanigarh as now it is fed solely from 220 KV Mahpur. To avoid any blackout at Bhawanigarh due to emergency an existing Bhawanigarh-Mahpur circuit.	20.07	3.01	0.80	23.88	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	20.07	3.01	0.80	23.88								20.07	3.01	0.80	23.88	
29	220 KV Hooshiarpur	2nd source connectivity to Hooshiarpur via DIC on DIC line 220 KV Deogarh-Hooshiarpur (40 km, 0.4 sq*) & using existing MCH Towers	To provide 2nd source of supply to Hooshiarpur as now it is fed solely from 400 KV Mahpur. In case losses any emergency on existing line, there will be complete blackout in areas of Hooshiarpur. Existing main circuit towers will be used at entry point of Hooshiarpur and 132 KV Bhogal line will be bypassed to Mahpur by using one circuit of Mahpur DIC line. Similarly 132 KV Chohal circuit will be bypassed to Mahpur by using second circuit of Mahpur DIC line. The work being specific to the PSTCL needs, required to be executed urgently to maintain continuity of supply, exemption may be given from TBCB Mode.	52.82	7.82	2.11	62.86	10.56	1.58	0.42	12.57	16.86	2.38	0.63	18.86	20.41	3.98	1.05	31.43	62.86								52.82	7.82	2.11	62.86	
30	220 KV Barga (Nawasherah)	Replacement of 2x50MVA 132KV 1V transformers with 2x100MVA 220KV 1V transformers	As per requirement of PSPCL, because 1320 MVA-132KV 1V, 1320KV 1V is now overloaded. So work has been agreed upon as per Sr. no. 4 of Table-4 of MCM of TPC meeting. 66 KV buses will be connected through UGI Power Cable.	18.23	2.73	0.73	21.69	0.00	0.00	0.00	0.00	9.12	1.37	0.36	10.85	9.12	1.37	0.36	21.69									9.12	1.37	0.36	10.85	
31	220 KV S/S Chajki	Augmentation of 66 KV single bus bar from double conductor to quadruple conductor	Proposal received from CEP&M, PSTCL to increase the loading capacity.	9.50	0.08	0.02	9.60	0.50	0.08	0.02	0.60	0.00	0.00	0.00	0.00	0.00	0.00	0.00	9.60	0.50	0.08	0.02	0.60							0.60		
32	400KV Dhuri to 400KV Patran	To increase ISTS point of draw for AT/GTTC and injection of nuclear Power from Patranhead via TBCB Patran	Under study	9.80	0.00	0.00	9.80	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	9.80													
33	Double bus bar arrangement at 220 KV Butari	Making 220 KV Bus of Butari as double and shifting of 220/132 KV T/F at Butari to 220 KV Jandila	For reliability of supply to consumers and Railways	1.30	0.27	0.07	2.14	0.90	0.14	0.04	1.07	0.90	0.14	0.04	1.07	0.00	0.00	0.00	2.14								1.80	0.27	0.07	2.14		

Sr. No.	Substation Name	Scope of work	Remarks	Total Cost	CAPEX COST																CAPITALISATION COST														
					EC@15%	EC@4%	Project Cost	TOTAL Exp. In 2023-24				TOTAL Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL	TOTAL Exp. In 2023-24				TOTAL Exp. In 2025-26				Grand TOTAL						
								Cost	EC@15%	EC@4%	TOTAL (T1)	Cost	EC@15%	EC@4%	TOTAL (T2)	Cost	EC@15%	EC@4%	TOTAL (T3)		T1+T2+T3	Cost	EC@15%	EC@4%	TOTAL (T1)	Cost	EC@15%	EC@4%		TOTAL (T2)	Cost	EC@15%	EC@4%	TOTAL (T3)	T1+T2+T3
34	220 KV D/C link between 220 KV S/S Badli and 400 KV S/S Wadala Gandhin.	220 KV D/C Link between 220 KV S/S Badli and 400 KV S/S Wadala Gandhin, (35 km, 0.4 Sq' conductor)	To provide N-1 reliability in case of tripping of proposed 220 KV Jamnala-Vadpal section or 220 KV PGCIL Jamnala-Bans section and for downstream evacuation plan of 400 KV substation Wadala Gandhin.	44.38	6.88	1.78	\$2.81	0.00	0.00	0.00	0.00	11.10	1.66	0.44	13.20	22.19	3.33	0.69	26.41	39.61									0.00	0.00	0.00	0.00	0.00		
35	Upgradation of 66 KV Apsara to 220 KV level	Creation of 220 KV Apsara with 1X100MVA + 1X100 MVA, 220/66 KV T/Fs (2 line bays, 2 T/F bays & 1no. Bus Coupler Bay)	Proposed by PSPCL for reliable supply to consumers in the border areas of Amritsar District and to de-load 220 KV Fatehgarh Churian, upgradation of 66 KV Apsara was agreed upon by both PSPCL and PSCIL as per Table 4. Sr. No. 3 of TPC meeting held on dated 19/07/2022. At this S/S, the 2nd 100 MVA T/F will be installed after spacing 100 MVA Power T/F from some other work where the augmentation of 100MVA to 180MVA is planned.	48.64	7.30	1.95	\$7.89	4.87	0.73	0.18	5.78	9.73	1.46	0.38	11.58	14.80	2.19	0.58	17.37	34.74									0.00	0.00	0.00	0.00	0.00		
		L/O of SAC line 220 KV Fatehgarh Churian - 220 KV Civil Lines Amritsar (L/O length 18 km, 0.45Sq')																														0.00			
36	Upgradation of 66 KV Bhagi to 220 KV level	Creation of 220KV Bhagi Sheela with 1X160MVA + 1X100MVA, 220/66KV T/Fs (4 line bays, 2 T/F bays & 1no. Bus Coupler Bay)	Up-gradation of Bhagathal Ka to 220KV proposed by PSPCL to give relief to 2X180 MVA overloaded power T/Fs at GHTP Lahore district. PSPCL plans to shift T/Fs at GHTP to Bhagathal. As per proposal submitted by PSPCL to GECIS (West), PSCIL agreed for the same in the TPC meeting as this will also give relief to 220 KV Bhagathal. At this S/S the 2nd 100 MVA T/F will be installed after spacing 100 MVA Power T/F from some other work where the augmentation of 100MVA to 180MVA is planned. As per PSERC notification dated 5/1/2018 (Annexure-A) inter-state transmission project costing more than Rs. 50Cr. are to be developed through TBCB. Cost of this project is more than 50Cr., but work being a brown field project and technical upgradation as such exemption may be given from TBCB made in line with Ministry of Power, Govt. of India Letter no. 15/2017-TT-Trans-PI(I) dated 15.3.2021 (Annexure-B)	88.87	6.85	2.36	76.17	5.90	0.68	0.24	7.02	11.79	1.77	0.47	14.03	17.89	2.65	0.71	21.05	42.18													0.00		
		L/O of both circuits of 220 KV Himmatpura - GHTP Line (Line length 24 km, 0.45sq')																														0.00			
37	Upgradation of 66 KV Aerocity to 220 KV level (GIS substation)	Under Study	Proposed by PSPCL to feed upcoming loads in Mohali area as per MOM of TPC Meeting at Sr. no. 10 of Table-9	8.00	0.00	0.00	8.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	8.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
38	Upgradation of 66 KV Kurak to 220 KV level	Under Study	Proposed by PSPCL in TPC Meeting to de-load 220 KV Pwara by shifting Morinda S/S to Kurak Table-15	8.00	0.00	0.00	8.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	8.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00			
39	Upgradation of 66 KV Bhabat to 220 KV level	Under Study	As proposed by PSPCL in TPC meeting held on 19.7.2022	6.00																6.00															
40	220 KV MG-3	Aug. of 2x100 220/66 KV T/F with 2x160MVA, 220/66 KV T/F	As per Sr. No. 8 of Table-14 of MOM of TPC Meeting and due to N-1 loading as discussed in FCC meeting on 26.7.2022	21.88	3.16	0.84	25.88	10.54	1.58	0.42	12.54				10.54	1.58	0.42	12.54	25.88	10.54	1.58	0.42	12.54								10.54	1.58	0.42	12.54	25.88
41	220 KV Masr	Add. 220/66 KV 100 MVA T/F	Proposed by PSPCL as per Sr. no. 5 of Table-3 of MOM of TPC meeting as loading has crossed 80% and violation of N-1 condition being a single transformer	9.12	1.37	0.36	10.85					9.12	1.37	0.36	10.85				10.85								9.12	1.37	0.36	10.85				10.85	

101



Sr. No.	Substation Name	Scope of work	Remarks	Total Cost	ECR 15%	ECR 4%	Project Cost	CAPEX COST												CAPITILISATION COST															
								TOTAL Exp. In 2023-24				Total Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL	TOTAL Exp. In 2023-24				Total Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL		
								Cost	ECR 15%	ECR 4%	TOTAL (T1)	Cost	ECR 15%	ECR 4%	TOTAL (T2)	Cost	ECR 15%	ECR 4%	TOTAL (T3)		Cost	ECR 15%	ECR 4%	TOTAL (T1)	Cost	ECR 15%	ECR 4%	TOTAL (T2)	Cost	ECR 15%	ECR 4%	TOTAL (T3)			
42	220 KV Kirtapur	Aug. of 100 MVA, 220/66 KV T4 to 100 MVA	As per sr. no. 7 of Table-4 of MOM of TPC Meeting held on 19.07.2022 loading has crossed 80%	10.53	1.58	0.42	12.53					10.53	1.58	0.42	12.53					12.53					10.53	1.58	0.42	12.53					12.53		
43	220 KV S/S Jholas herher (Amend No. 11/2021-22)	1 No. Additional 220/66 KV 100 MVA T/F		9.12	1.37	0.36	10.85									9.12	1.37	0.36	10.85	10.85									9.12	1.37	0.36	10.85	10.85		
44	220 KV Masr	Add. 66/11 KV, 20 MVA T/F	Proposed by PSPCL as per sr. no. 11 of Table-2 of MOM of TPC Meeting as loading has crossed 80%	3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57					3.57					3.00	0.45	0.12	3.57				3.57			
45	220 KV Tahwand sabo	Aug. of 66/11 KV, 12.5 MVA T/F to 20 MVA	Proposed by PSPCL as per sr. no. 3 of Table-2 of MOM of TPC Meeting held on 19.07.2022 as loading has crossed 80%	2.73	0.41	0.11	3.25	2.73	0.41	0.11	3.25									3.25	2.73	0.41	0.11	3.25								3.25			
46	220 KV Botiamewa	Aug. of 66/11 KV, 12.5 MVA T/F to 20 MVA	P&M/STCL proposal as loading has crossed 80%	2.73	0.41	0.11	3.25									2.73	0.41	0.11	3.25	3.25											2.73	0.41	0.11	3.25	3.25
47	220 KV Baghapurana	Aug. of 66/11 KV, 12.5 MVA T/F to 20 MVA	P&M/STCL proposal as loading has crossed 80%	2.73	0.41	0.11	3.25					2.73	0.41	0.11	3.25					3.25					2.73	0.41	0.11	3.25				3.25			
48	132 KV Bhogpur	Aug. of 132/11 KV, 12.5 MVA to 20 MVA	Proposed by PSPCL as per sr. no. 8 of Table-5 of MOM of TPC Meeting as loading has crossed 80%	2.80	0.39	0.10	3.09					2.80	0.39	0.10	3.09					3.09					2.80	0.39	0.10	3.09				3.09			
49	132 KV Soan	Add 12.5 MVA, 132/11 V T/F with CR Extension	As per sr. no. 13 of Table-2 of MOM of TPC Meeting, installation of additional 132/11 KV, 10*12.5 MVA, instead of already planned augmentation of single 12.5 MVA T/F to 20 MVA should be installed to meet with N-1 contingency conditions.	3.66	0.53	0.14	4.22	3.66	0.53	0.14	4.22									4.22	3.66	0.53	0.14	4.22								4.22			
50	220 KV Devgarh	Add 66/11 KV, 12.5 MVA T/F with CR Extension	As per sr. no. 1 of Table-10 of MOM of TPC Meeting as loading has crossed 80%	3.00	0.45	0.12	3.57	3.00	0.45	0.12	3.57									3.57	3.00	0.45	0.12	3.57								3.57			
51	132 KV Chankaur Sahb	1 No. 12.5 MVA, 66/11 KV T/F with CR extension	As per sr. no. 8 of Table-10 of MOM of TPC Meeting as loading has crossed 80%	3.00	0.45	0.12	3.57	3.00	0.45	0.12	3.57									3.57	3.00	0.45	0.12	3.57								3.57			

5/10/20


Sr. No.	Substation Name	Scope of work	Remarks	CAPEX COST												CAPITILISATION COST																	
				Total Cost			Project Cost			TOTAL Exp. In 2023-24				Total Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL											
				Cost	ECR 15%	DCR 4%	Cost	ECR 15%	DCR 4%	Cost	ECR 15%	DCR 4%	Cost	ECR 15%	DCR 4%	Cost	ECR 15%	DCR 4%	Cost	ECR 15%	DCR 4%	T1+T2+T3											
				TOTAL (T1)			TOTAL (T2)			TOTAL (T3)			T1+T2+T3			TOTAL (T1)			TOTAL (T2)			TOTAL (T3)			T1+T2+T3								
82	132 KV Kotakpura-1	Aug. of 12.5 MVA, 13211 KV T/F to 20 MVA, 6611 KV T/F	As per Sr. No. 8 of Table-2 of MOM of TPC Meeting held on 18.07.2022	2.62	0.39	0.10	3.12					2.62	0.39	0.10	3.12					2.62	0.39	0.10	3.12						3.12				
83	220 KV Koldaror	Addl. 6611 KV, 12.5 MVA T/F including CR Extension	As per Sr. No. 12 of Table-2 of MOM of TPC Meeting held on 19.07.2022	3.00	0.45	0.12	3.57	3.00	0.45	0.12	3.57									3.00	0.45	0.12	3.57						3.57				
84	220 KV Badni Kalan	Addl. 6611 KV, 20 MVA T/F including CR Extension	As per Sr. No. 3 of Table-13 of MOM of TPC Meeting	3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57						3.57				
85	220 KV Barnala (Handkays)	Addl. 1012.5 MVA, 6611 KV T/F	As per Sr. No. 8 of Table-6 of MOM of TPC Meeting	3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57						3.57				
86	220 KV Dhanouli	Addl. 1012.5 MVA, 6611 KV T/F with CR extension	As per Sr. No. 4 of Table-10 of MOM of TPC Meeting	3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57					3.00	0.45	0.12	3.57						3.57				
87	220 KV Pashowal	Aug. of 1012.5 MVA, 6611 KV with 20 MVA, 6611 KV T/F	As per Sr. No. 9 of Table-13 of MOM of TPC Meeting	2.73	0.41	0.11	3.25					2.73	0.41	0.11	3.25					2.73	0.41	0.11	3.25						3.25				
88	220 KV Hosharpur (Hosharpur-Chahal Loading)	To replace 12.5 MVA and 20 MVA, 13211 KV T/F with 2000 MVA, 6611 KV T/Fs	To control loading of 132 KV Hosharpur - Chahal section	6.24	0.79	0.21	6.24	2.62	0.39	0.10	3.12					2.62	0.39	0.10	3.12	6.24	2.62	0.39	0.10	3.12	0.00	0.00	0.00	0.00	2.62	0.39	0.10	3.1178	6.24

103

Sr. No.	Substation Name	Scope of work	Remarks	Total Cost	CAPEX COST												CAPITALEX COST																
					EC@15%				EC@4%				Project Cost				TOTAL Exp. in 2023-24				Total Exp.in 2024-25				TOTAL Exp. in 2025-26				Grand TOTAL				
					Cost	EC@15%	EC@4%	TOTAL (T1)	Cost	EC@15%	EC@4%	TOTAL (T2)	Cost	EC@15%	EC@4%	TOTAL (T3)	T1+T2+T3	Cost	EC@15%	EC@4%	TOTAL (T1)	Cost	EC@15%	EC@4%	TOTAL (T2)	Cost	EC@15%	EC@4%	TOTAL (T3)	T1+T2+T3			
66	Replacement of Disc Insulators of 400 KV PSTCL lines with Polymer Insulators			10.00	1.50	0.40	11.90	2.00	0.30	0.08	2.38	4.00	0.60	0.16	4.76	4.00	0.60	0.16	4.76	11.90	2.00	0.30	0.08	2.38	4.00	0.60	0.16	4.76	4.00	0.60	0.16	4.76	11.90
67	Makhu, Rajpura, Muktabar/ Balman, Jassa Singh (Maliana), and Dhanarsu	Arise 400 KV, 125 MVAR Reactors	To Control Over voltages in Northern region, matter is being deliberated in CMEIS Meetings. PSDF Funding shall also be explored.	0.00																0.00													
68	Miscellaneous	Augmentation of bus bars, extension in control room building, providing room for second source for station battery etc	Miscellaneous	30.60	4.50	1.20	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70
69	Miscellaneous	Augmentation/additions of T/ls at 220/132/66 KV KV S/Strs of PSTCL	Miscellaneous	30.60	4.50	1.20	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70
70	Miscellaneous	Additional 220/132/66 KV line bays related with feasibility cases or as per PSPCL/PSTCL Requirement	Miscellaneous	30.60	4.50	1.20	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70
71	Miscellaneous	Unforeseen emergency works	Miscellaneous	30.60	4.50	1.20	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	10.00	1.50	0.40	11.90	35.70
Total (A)				1621.09			1929.09				298.43				565.52				666.66	1530.60				153.24				223.32			626.71	1003.27	

Note - Attached copy of TPC minutes may be considered as Annexure-C

MSLD Works		HR,IT, S&D Organisation work		0.12		0.12		0.00		0.00		0.12		0.00		0.00		0.00		0.12		0.00		0.00		0.00		0.00		0.00		
72	Procurement of Fork lifter for Jansher Store and Procurement of Weighing Machine for PSTCL Stores			0.12	0.00	0.00	0.12	0.00	0.00	0.12	0.00	0.00	0.12	0.00	0.00	0.12	0.00	0.00	0.12	0.12	0.00	0.00	0.12	0.00	0.00	0.00	0.00	0.00	0.00	0.12		
73	Procurement of IT related Hardware Items, Software Licences, Cyber security related and unforeseen Capital expenditure	Procurement of IT related Hardware Items, Software Licences, Cyber security related and unforeseen Capital expenditure		3.90	0.00	0.00	3.90	1.00	0.00	0.00	1.00	1.00	0.00	0.00	1.00	1.00	0.00	0.00	1.00	3.90	1.00	0.00	0.00	1.00	1.00	0.00	0.00	1.00	1.00	0.00	0.00	3.90
Total (B)				3.12			3.12				1.12				1.00				1.00	3.12				1.12			1.00			1.00	3.12	

501


Sr. No.	Substation Name	Scope of work	Remarks	CAPEX COST																CAPITALISATION COST																	
				Total Cost	Project Cost			TOTAL Exp. In 2023-24				TOTAL Exp. In 2024-25				Grand TOTAL	TOTAL Exp. In 2023-24				TOTAL Exp. In 2024-25			TOTAL Exp. In 2025-26			Grand TOTAL										
					ECR 15%	ECR 4%		Cost	ECR 15%	ECR 4%	TOTAL (T1)	Cost	ECR 15%	ECR 4%	TOTAL (T2)		Cost	ECR 15%	ECR 4%	TOTAL (T3)	Cost	ECR 15%	ECR 4%	TOTAL (T1)	Cost	ECR 15%		ECR 4%	TOTAL (T2)	Cost	ECR 15%	ECR 4%	TOTAL (T3)	T1+T2+T3			
P&M Works				1.50			1.50	0.5	0	0	0.5	0.5	0	0	0.5	0.5	0	0	0.5	1.50	0.5	0	0	0.5	0.5	0	0	0.5	0.5	0	0	0.5	0.5	0	0	0.5	1.50
74		To provide/replace ACBs in existing 220 KV & 400 KV S/S's	To maintain temperatures for numerical relays																2.50	2.5	0	0	2.5	0	0	0	0	0	0	0	0	0	0	0	0	0	2.50
75		To provide main filter cum working platform at new 400 KV S/Ss La Behman Jassa Singh, Dharmraj and Roper	For doing work on equipment installed at 400 KV sub-stations	2.50			2.50	2.5	0	0	2.5	0	0	0	0	0	0	0	1.20	0.4	0	0	0.4	0.4	0	0	0.4	0.4	0	0	0.4	0.4	0	0	0.4	1.20	
76		15 KV Insulation Tester for new 400 KV & 220 KV S/Ss (15 Nos.)	Insulation Testers for new and up-coming Sub-stations	1.20			1.20	0.4	0	0	0.4	0.4	0	0	0.4	0.4	0	0	0.60	0.2	0	0	0.2	0.2	0	0	0.2	0.2	0	0	0.2	0.2	0	0	0.2	0.60	
77		T&P for new upcoming S/Ss and existing S/Ss	Required to maintain the 400 Kv, 220 Kv sub-stations by manpower	0.60			0.60	0.2	0	0	0.2	0.2	0	0	0.2	0.2	0	0	0.60	0.2	0	0	0.2	0.2	0	0	0.2	0.2	0	0	0.2	0.2	0	0	0.2	0.60	
78		T&P for new upcoming S/Ss and existing lines inc. new HTLS lines	Required to maintain the 400 Kv, 220 Kv transmission lines by the manpower	0.60			0.60	0.2	0	0	0.2	0.2	0	0	0.2	0.2	0	0	0.25	0.25	0	0	0.25	0	0	0	0	0	0	0	0	0	0	0	0.25		
79		Cameras for testing porcelain disc insulators (One No.)	Required for testing of porcelain insulator discs for live tightness in online mode	0.25			0.25	0.25	0	0	0.25	0	0	0	0	0	0	0	0.15	0	0	0	0.15	0	0	0	0.15	0	0	0	0	0	0	0	0.15		
80		Tower footing resistance suits (5 Nos. i.e. one per circle)	To measure the transmission line tower footing resistance by AEE/TL	0.15			0.15	0	0	0	0	0.15	0	0	0.15	0	0	0	0.15	0.15	0	0	0.15	0	0	0	0	0	0	0	0	0	0	0	0.15		
81		High end Contact resistance meter (1 No.)	For the measurement of contact resistance of solenoids circuit breakers etc at 400 KV sub-stations.	0.15			0.15	0.15	0	0	0.15	0	0	0	0	0	0	0	0.20	0.2	0	0	0.2	0	0	0	0.2	0	0	0	0	0	0	0	0.20		
82		High end Earth tester cum soil resistivity measurement (1 No.)	For use at 400 KV sub-stations	0.20			0.20	0.2	0	0	0.2	0	0	0	0	0	0	0	0.06	0.06	0	0	0.06	0	0	0	0.06	0	0	0	0	0	0	0	0.06		
83		Up-gradation of existing EDV kits (2 Nos.) from OEM as per new IEC standards for ODTL	Required for Oil & Diagnostic Testing Lab due to change in IS/IEC oil testing standards.	0.06			0.06	0.06	0	0	0.06	0	0	0	0	0	0	0	0.30	0.3	0	0	0.3	0	0	0	0.3	0	0	0	0	0	0	0	0.30		
84		PCB (polychlorinated Biphenyl) test kit for oil as per new IEC standards	Required for Oil & Diagnostic Testing Lab due to change in IS/IEC oil testing standards	0.30			0.30	0.3	0	0	0.3	0	0	0	0	0	0	0	0.15	0.15	0	0	0.15	0	0	0	0.15	0	0	0	0	0	0	0	0.15		
85		Up-gradation of HPLC kit of ODTL from OEM to conduct additional oil tests of metal passivator and DBDS as per new IEC standards	Required for Oil & Diagnostic Testing Lab due to change in IS/IEC oil testing standards	0.15			0.15	0.15	0	0	0.15	0	0	0	0	0	0	0	0.10	0.1	0	0	0.1	0	0	0	0.1	0	0	0	0	0	0	0	0.10		
86		Up-gradation of two existing distance relay test kits for advanced distance relay testing functions	For accurate testing of distance protection relays of all makes using OEM testing tool/ files at 400 KV level	0.10			0.10	0.1	0	0	0.1	0	0	0	0	0	0	0	0.10	0.1	0	0	0.1	0	0	0	0.1	0	0	0	0	0	0	0	0.10		

2901-38

Sr. No.	Substation Name	Scope of work	Remarks	Total Cost	CAPEX COST													CAPITILISATION COST																												
					EC@15%	EC@4%	Project Cost	TOTAL Exp. In 2023-24				Total Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL	TOTAL Exp. In 2023-24				Total Exp. In 2024-25				TOTAL Exp. In 2025-26				Grand TOTAL													
								Cost	EC@15%	EC@4%	TOTAL (T1)	Cost	EC@15%	EC@4%	TOTAL (T2)	Cost	EC@15%	EC@4%	TOTAL (T3)		T1+T2+T3	Cost	EC@15%	EC@4%	TOTAL (T1)	Cost	EC@15%	EC@4%	TOTAL (T2)	Cost	EC@15%	EC@4%		TOTAL (T3)	T1+T2+T3											
87		OTDR (1) for T&C Cell under Communication circle	For testing of OPGW	0.28				0.28	0	0	0	0.28	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.28				0.28	0	0	0	0.28	0	0	0	0	0	0	0	0	0.28
88		Medium end Earth testers (25)	For all P&M Divisions to check earth resistance of GIS yard and various other switchgears	0.50				0	0	0	0	0	0	0	0	0	0.5	0	0	0.5	0	0	0	0	0.50	0	0	0	0	0	0	0	0	0	0	0	0	0	0.5	0	0	0.5	0.50			
88		Low end thermo-vision cameras for TL gangs (5)	To detect hot points	0.50				0	0	0	0	0	0	0	0	0	0.5	0	0	0.5	0	0	0	0	0.50	0	0	0	0	0	0	0	0	0	0.5	0	0	0.5	0.50							
89		Cable fault locator	For newly laid 132 KV cable at Amritsar	2.00				0	0	0	0	2	0	0	2	0	0	0	0	0	0	0	0	2.00	0	0	0	0	2	0	0	2	0	0	0	0	2	0	0	0	2.00					
91		Cable analyser	For power cables of 132 KV at Amritsar	4.00				0	0	0	0	0	0	0	0	4	0	0	4	4	0	0	4	4.00	0	0	0	0	0	0	0	0	0	4	0	0	4	4.00								
92		Up-gradation of old ULDC fibre optic system (Comm.)	For reliable telemetry data to SLDC	5.25				1.25	0	0	1.25	2	0	0	2	2	0	0	2	2	0	0	2	5.25	1.25	0	0	1.25	2	0	0	2	2	2	0	0	2	5.25								
93		Remote Control Operation along with VMS of 400KV S/S's of Behman Jassa Singh, Dhansu and Ropar	For RCM operation of 400 KV S/S's- and to reduce operational manpower	3.00				0	0	0	0	0	0	0	0	3	0	0	3	3	0	0	3	3.00	0	0	0	0	0	0	0	0	0	3	0	0	3	3.00								
94		Up-gradation of server cum gateways of existing SAS equipped sub-stations with IEC 60870-5-104 licenses	To improve reliability of data telemetry to SLDC as per 104 protocol for seamless flow of data	0.20				0.2	0	0	0.2	0	0	0	0	0	0	0	0	0	0	0	0	0.20	0.2	0	0	0.2	0	0	0	0	0	0	0	0	0	0.2	0	0	0.2					
95		SAS software along with relevant licenses and associated hardware	For trouble shooting fault detections in SAS networking without disturbing online SAS system in automated S/S's	0.60				0	0	0	0	0.6	0	0	0.6	0	0	0	0	0	0	0	0	0.60	0	0	0	0	0.6	0	0	0	0.6	0	0	0	0	0.6	0	0	0.6					
96		For Cyber Security- intrusion detection system and hardware based firewall for SAS equipped S/S's	For cyber security threats of SAS equipped 400 KV S/S's of PSTCL	6.00				0	0	0	0	6	0	0	6	0	0	0	0	0	0	0	0	6.00	0	0	0	0	6	0	0	6	6	0	0	0	6	0	0	0	6.00					
97		Construction of safety walls between transformers in adjacent bays	For safety of power transformers in case of fire	6.00				2	0	0	2	2	0	0	2	2	2	0	4	2	2	0	4	6.00	2	0	0	2	2	2	0	4	2	2	0	0	2	6.00								
98		Transformer diagnosis system with facility of all types of major tests - in-built in one kit	Proposed as a pilot project for one protection gang	0.45				0	0	0	0	0	0	0	0	0.45	0	0	0.45	0.45	0	0	0.45	0.45	0	0	0	0	0	0	0	0	0	0.45	0	0	0.45	0.45								
Total (C)				36.54				36.54				8.74				14.05				13.75				36.54				8.74				14.05				13.75	36.54									
Total [A+B+C]				1660.75				1968.75				580.57				681.41				1570.26				163.10				238.37				641.46				1042.93										

401

AS

SLDC Works list

Sl. No. as per CIP Order	Particulars	Scope of Work	BIP approved for the said Contract Period (In %)	Total Cost of Project	Project Start Date	Actual Anticipated Year of completion	CAPEX during 2021-22			Capitalization during 2021-22			CAPEX during 2022-23			Capitalization during 2022-23			CAPEX during 2023-24			Capitalization during 2023-24			CAPEX during 2024-25			Capitalization during 2024-25			Remarks												
							Total			Total			Total			Total			Total			Total			Total																		
							Works Exp	EC	IOC	Works Exp	EC	IOC	Works Exp	EC	IOC	Works Exp	EC	IOC	Works Exp	EC	IOC	Works Exp	EC	IOC	Works Exp	EC	IOC	Works Exp	EC	IOC		Works Exp	EC	IOC									
Works which have been Completed or likely to be completed on or before 31.03.2023																																											
1	Procurement of 80 Nos Energy meters (Smart Meter Approved through Pulsion No. 65021)	80 Nos. Intelligent Energy meters were procured to 305.122 at amongst with for spanning existing distribution network and for completion of S&S Project by P&M. This work approved by MCO and P&S&C vide order dated 02.03.2022 against petition no. 63/2021. Material has been received and is being installed on meter base.	0.58	0.380	12.07.2021	2023-23	0.1184	0	0	0.119	0.6517	0	0	0.063	0.1808	0	0	0.1808	0.2273	0	0	0.227	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000						
(A) Split Over Works of 1st MFT Control Period (From FY 2017-18)																																											
1	Schedule for providing 45 Nos Remote Terminal Units for SCADA/EMS systems at 223 132 KV Substation of PSTCL in Punjab (Split over from 1st MFT)	Supply and installation of 45 nos. RTUs.	0.480	0.72 (As per VCO)	22.05.18	2023-24	0.5609	0	0.028	0.578	0	0	0	0.75	0	0.003	0.775	1.5	0	0.023	1.828	0.650	0.000	0.028	0.075	1.271	0.000	0.000	1.271	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000				
2	Centralized AC system, Furniture & Fixtures (including office ACs) (split over from 1st MFT)	Centralized AC system, Furniture & Fixtures (including office ACs) (split over from 1st MFT)	1.760	1.82 (Tentative)	02.06.17	2024-25	0.0478	0	0.046	0.0478	0	0	0.048	0.3	0	0	0.3	0	0	0	0	0.700	0.000	0.000	0.700	1.000	0.000	1.000	0.000	0.400	0.000	0.000	0.400	0.000	0.000	0.000	0.000	0.000	0.000	0.000			
3	IT equipments including Server, computer, Display, software etc. for S.L.D.C. Web site and its offices. (Split over from 1st MFT)	IT equipments including Server, computer, Display, software etc. for S.L.D.C. Web site and its offices. (Split over from 1st MFT)	0.380	0.43 (Tentative)	11.12.18	2022-23	0	0	0	0	0	0	0	0.3	0	0	0.3	0	0	0	0	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000				
(B) Split Over Works of 2nd MFT Control Period (From FY 2020-21)																																											
4	Implementation of SAMST scheme in Punjab (Procurement of mobile, communication equipments and hardware and software for Scheduling, Accounting, Billing and settlement of Invoicing of Electrification over from 2nd MFT)	Implementation of SAMST scheme in Punjab	22.820	22.820	04.03.22	2023-24	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	4.800	0.000	0.000	4.800	22.820	0.000	0.000	22.820	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000				
5	Procurement of RTUs for various substations of PSTCL (80 nos. RTUs) (Split over from 2nd MFT)	Out of 80 Nos. 45 Nos. RTU have been procured out of which 40 nos. have been installed. Fresh tender enquiry shall be floated for remaining 21 nos. RTUs + 9 nos more RTUs against fully mode re-allocated RTUs.	13.640	0.68 (Tentative)	26.02.22	2024-25	0.2672	0	0	0.267	0.1348	0	0	0.116	1.5	0	0.023	1.528	0.2808	0	0.023	0.2808	2.500	0.000	0.000	2.500	0.000	0.000	0.000	2.880	0.200	0.000	0.028	0.228	3.080	0.000	0.000	0.000	0.000	0.000	0.000	0.000	
6	Extension of SLDC Building (Split over from 2nd MFT)	Extension of building shall be required for equipment under U.D.C. Phase 3 (New Parking Stand, U.D.C. (Indoor Management System) project	1.830	1.83 (Tentative)	01.04.23	2025-26	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.500	0.000	0.000	0.500	0.000	0.000	0.500	1.000	0.000	0.000	1.500	0.430	0.000	0.000	0.430	0.430	0.000	0.000	0.430	0.000	0.000	0.430
New works for MFT 2023-24																																											
1	Purchase of equipment/software as per specifications of contract agencies like M.D.C. M.C.P.C. CERT-N, for cyber security etc. or any other software SLDC related work (i.e. for RTU, IT, SAMST, etc.)	Purchase of IT equipments/software as per specifications of contract agencies like M.D.C. M.C.P.C. CERT-N, for cyber security etc. or any other software SLDC related work (i.e. for RTU, IT, SAMST, etc.)	NIL	1.5 (Tentative)	01.04.23	2025-26	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	0.400	0.000	0.000	0.000	0.000	0.000	0.000	0.500	0.500	0.000	0.000	0.500	0.500	0.000	0.000	0.500	0.500					
2	U.D.C. Phase II (Under Shift)	Replacement of SCADA System. The proposal for this work is under review at tender level. This work will be covered under capital work only in case proposal of execution through bid mode is rejected.	NIL	As per M&P, this project is to be implemented by CTU (P&C), the mode/line of which are under discussion stage.																																							
Total (D) (New Works Cost)																									0.5	0	0.5	0.5	1	0.5	0.5												

801
AS



Punjab Government Gazette

EXTRAORDINARY

Published by Authority

CHANDIGARH, MONDAY, NOVEMBER 5, 2018 (KARTIKA 14, 1940 SAKA)

PUNJAB STATE ELECTRICITY REGULATORY COMMISSION
NOTIFICATION

The 5th November, 2018

No. PSERC/Secy/132.-In accordance with para 5.3 of National Tariff Policy, the Punjab State Electricity Regulatory Commission hereby decides that intra-state transmission projects costing more than Rs. 50 Crore shall be developed by State Govt./STU through tariff based competitive bidding.

By order of the Commission
Sd/-
SECRETARY

1634/11-2018/Pb. Govt. Press, S.A.S. Nagar

(13337)

[Handwritten signature]

109

No. 15/2/2017-Trans-Pt(1)
 Government of India
 Ministry of Power
 Shram Shakti Bhawan, Rafi Marg, New Delhi- 110001

To

Dated, 15th March, 2021

Addl. Chief Secretaries/ Pr. Secretaries/
 Secretaries of Power/ Energy Departments
 of all the States and UTs.

Subject: Adoption of Tariff Based Competitive Bidding (TBCB) for intra-State transmission projects- reg.

Sir,

You are aware that Electricity Act 2003 has created conducive environment for investments in all segments of the electricity industry, both for public and private sectors, by removing barrier to entry in different segments. Section 63 of the Electricity Act provides for participation of private sector on competitive basis in different segments so as to encourage private sector investment.

2. National Electricity Policy 2005, envisages that role of private participation in generation, transmission and distribution would become increasingly important in view of the rapidly growing investment needs of the sector. It also states that the Central Government and the State Governments need to develop workable and successful models for public private partnership for leveraging private investment with the public sector finances.

3. In continuation of the National Electricity Policy 2005, Tariff Policy was notified by the Central Government in 2006 for ensuring optimal development of the transmission network to promote efficient utilization of generation and transmission assets in the country, as well as for attracting the required investments in the transmission sector and providing adequate returns.

4. In line with above policy framework, Ministry of Power notified "Tariff Based Competitive Bidding (TBCB) Guidelines for Transmission Service" and "Guidelines for Encouraging Competition in Development of Transmission Projects" under section 63 of the Electricity Act, 2003 on April 13, 2006. Subsequently, Standard Bidding Documents, viz. Request for Qualification (RfQ), Request for Proposal (RfP) and Transmission Service Agreement (TSA), were notified by Ministry of Power, Govt. of India in the year 2008, followed by subsequent amendments in these documents. With this, tariff based competitive bidding started for development of inter-state transmission sector since 2010.

5. Subsequently, the Central Government notified revised Tariff Policy in January 2016 with following provisions regarding Transmission System:

7.1 (6) :Investment by transmission developer including CTU/STUs would be invited through competitive bids in accordance with the guidelines issued by the Central Government from time to time.

7.1 (7) While all future inter-state transmission projects shall, ordinarily, be developed through competitive bidding process, the Central Government may give exemption from competitive bidding for (a) specific category of projects of strategic importance, technical upgradation etc. or (b) works required to be done to cater to an urgent situation on a case to case basis.

6. In line with provisions of the Tariff Policy 2016, generally inter-state transmission systems are developed through competitive bidding only, except for certain categories of transmission system as specified in the Tariff Policy 2016. With adoption of Tariff Based Competitive Bidding for development of transmission system, following key benefits have been observed:

- (i) Lower Tariff compared to Cost Plus: With large number of bidders participating in development of a transmission project, discovered tariff for a transmission project can be lower than cost-plus tariff by about 30-40%
- (ii) Less burden on government finances: It will attract private investments for development of projects, and scarce government fund can be spared for other priority sectors
- (iii) Risk sharing: It encourage risk sharing with private sector. Innovative Technology: It encourages use of advanced technology for improving cost and efficiency

7. As intra-state transmission system has major share in the transmission sector in the country, adoption of Tariff Based Competitive Bidding (TBCB) in development of intra-state transmission system can effectively reduce burden on State Governments' finances as well as reduce tariff of intra-State transmission system, leading to consumers' benefit. The matter was also discussed in a meeting taken by Hon'ble Union Minister of State (Independent Charge) for Power and New and Renewable Energy on 03.02.2021 and it was decided to request the State/UT Governments to adopt TBCB in development of intra-State transmission system.

8. In light of above and in the larger interest of consumers, it is strongly recommended that tariff based competitive bidding may be adopted for development of Intra-State Transmission system also.

9. This issues with the approval of Competent Authority.

Yours faithfully,

MUN
15.03.2021
(Mritunjay Kr. Narayan)
Joint Secretary to the Govt. of India

Copy to

1. Chairpersons of all SERCs and JERCs.
2. Chairperson, CEA, New Delhi.
3. PS to Hon'ble MoSP (IC) / Sr PPS/ PPS/ PS to Secretary (Power) / AS (SKGR) / AS (VKD) / AS&FA / Sr Advisor/ All JSs/ CE(Th), MoP
4. Technical Director, NIC, Ministry of Power- with the request to host this letter on the website of Ministry of Power

JF

Minutes of Transmission Planning Committee Meeting

Meeting of the Transmission Planning Committee was held on 19.07.2022 at PSTCL Conference Room at Head office, Mall Road, Patiala.
Following officers were present:-

1. Chief Engineer/TS,PSTCL,Patiala
2. Chief Engineer/P&M,PSTCL , Ludhiana
3. Chief Engineer/West Zone,PSPCL,Bathinda
4. Chief Engineer/South Zone,PSPCL,Patiala
5. Chief Engineer/Central Zone,PSPCL,Ludhiana
6. Chief Engineer/Border Zone, PSPCL,Amritsar
7. Chief Engineer/North Zone, PSPCL, Jalandhar
8. Chief Engineer/P&M, PSPCL,Ludhiana
9. Chief Engineer/Planning,PSPCL,Patiala
10. Chief Engineer/TS,PSPCL,Patiala
11. Dy. CE/Transmission Planning,PSPCL,Patiala
12. SE/Planning,PSTCL,Patiala
13. ASE/Procurement,P&M,PSPCL, Ludhiana
14. ASE/PO&S, PSTCL, Ludhiana
15. ASE/Planning-1,PSTCL,Patiala
16. SR.XEN./Planning,PSPCL,Patiala
17. SR.XEN./Planning,PSPCL,Patiala
18. AEE/Planning-1,PSTCL,Patiala
19. AEE/Planning-2,PSTCL,Patiala

13

AS

Agenda circulated vide SE/Planning, PSTCL, Patiala vide memo no. 403/12 dated 11/07/2012 was discussed in detail and it was decided as under:-

WEST ZONE

Sr. No.	MOM
1	<p><u>Expansion of 220 kV S/S Moga, 132 kV S/s Moga-1 & 132 kV S/S Moga-2</u> - CE/DS, West Zone, PSPCL, Bathinda apprised that it is not easy to take 66 kV line from 220 kV Moga. PSTCL asked PSPCL to set up a new 66kV S/S with initial connectivity via power cable for reliability as all the 132 KV S/Ss in Moga were overloaded and there is no long term space for expansion. CE/TS PSPCL & CE/DS (West) Bathinda informed that committee of Sr. Xen/TLSC PSPCL, SE/DS Faridkot and SE/SS Design PSPCL will study the proposal of downstream system of 66 kV at Monopoles/underground Cables for new 66kv S/S nearby Singhawala and PSPCL will send the proposal accordingly. However, PSPCL stressed upon PSTCL for installing 2 nos. 20MVA 66/11 kV T/fs along with 220/66 kV T/F and extension of control room for 11 kV loads. PSPCL also stressed upon PSTCL to expedite the installation of 20 MVA 132/11kV T/F at 132kV Dhalleke.</p>
2	<p><u>To establish new 220 kV S/S at Fazilka as approved in the 2nd MYT</u> PSTCL informed TPC that railway connection is proposed to be given to TSS Lakhewali from 66 KV Arniwala s/s by constructing a 220-KV Switching station by LILO of one circuit of 400kV Muktsar(220 KV bus)- Abohar D/C Line. Apart from this, PSTCL apprised that there is overloading on 220 KV Muktsar (400 KV) -Malout S/C line. So, to give relief to this line, load of 66 KV D/C Arniwala is proposed to be shifted to 220 kv Muktsar (400 kv)- Abohar line in the second stage at Arniwala. It was also informed to PSPCL that 66 kV Guru Hrasahai is also being upgraded to 220 KV which will give relief of about 90 MVA to 220 kv Ghubaya S/S & hence there is no urgent requirement of 220 kv near Fazilka. PSPCL informed that by up-grading Guru Hrasahai issue of overloading of 220 KV Ghubaya will be addressed but the issue of overloading of 66 KV Ladhuka/Fazilka lines will still remain. CE/DS, West Zone, PSPCL, Bathinda proposed setting up of greenfield substation at Talliwali Bodla between Arniwala- Fazilka and with this there 66 KV Line length to Fazilka will decrease by about 12-15 km in comparison to Arniwala. But still the length of 66 KV Fazilka- Tahliwal will be around 13-15 km. However, it was apprised by PSTCL that if Tahliwala Bodla is considered the length of 220 KV LILO will increase by about 12- 13 km. Moreover at the proposed land location, Panchayat is not willing to give land free of cost and was demanding lease amount of about Rs 15000- 20000/year per acre for first 10 years and subsequent increase there-off for about 10 acres. So PSTCL informed that it would be more appropriate if suitable land is made available at the load center i.e Fazilka or about 2-3 kms from it to have more benefits and consider Arniwala separately for relief to 220 KV Malout/ Katorewala.</p>
3	<p><u>220 kV S/S Jhoke Harihar-</u> Upgradation of 66 kV Jhoke Harihar has been planned vide Amend No. 11/2021-22 dated 08.07.21. PSPCL stressed upon early completion of work to address the overloading of 132/66 KV Transformers at 220 KV Ferozepur</p>

113

- 4 220 Kv S/S Jeewa Arian-
CE/DS West PSPCL had proposed upgradation of 66 kv S/S Jeew Arian to 220 kv S/S to deload 220 kv S/S Ghubaya but PSTCL apprised that upgradation of 66 kv Guru Harsahai to deload Ghubaya can be considered in 3rd MYT 2023-26 of PSTCL as the transfer of land owned by Village Panchayat has not matured for upgradation of 220 kv S/S Jeew Arian. Therefore, PSPCL agreed to the proposal for upgradation of 66 kv Guru Harsahai as it would give relief to both 220 KV Ghubaya and 220 KV Sadiq. This S/S would be connected by D/C from 220 KV Ghubaya and 220 KV Jhoke Harihar.
- 5 Upgradation of 66 kv Bhalaina to 220 KV-
Since sufficient land is not available at 66 kv S/S Kauni, so instead of upgradation of 66 kv Kauni, PSPCL proposed upgradation of 66 kv Bhalaina to 220 kv level to de-load 220 KV and 132 KV S/Ss at Muktsar. It was also agreed upon that PSPCL will plan a 66 kv link from Bhalaina to Doda and Kauni to deload 3X100 MVA, 220 /132 KV auto transformers at 220 kv Muktsar. The proposal for these links will be sent by CE/P&M, PSPCL to Planning/PSPCL.

TABLE 2

Sr.no	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	220KV Himmatpura	66/11, 2 x 12.5 MVA	89.12%	92.68%	PSTCL apprised that Aug of 12.5 MVA 66/11 kv to 20 MVA already planned at Sr. No. 54 of 2 nd MYT.
2.	132KV Ferozeshah	132/11, 2x12.5+1x20	85.37%	88.79%	PSTCL apprised that Aug of 12.5 MVA 132/11 kv to 20 MVA already planned at Sr. No. 60 of 2 nd MYT.
3.	220KV Talwandi Sabo	66/11, 20+12.5 MVA	79.38%	82.56%	PSTCL apprised that Aug of 12.5 MVA 66/11 kv to 20 MVA will be included in 3 rd MYT 2023-26.
4.	132KV Samadh Bhai	132/11, 3 x 20 MVA	85.43%	88.84%	PSTCL apprised that Addl. 12.5 MVA 132/11 kv already planned at Sr. No. 58 of 2 nd MYT.
5.	132KV Gholian Kalan	132/11, 1x20MVA	89.50%	93.00%	PSTCL apprised that Addl. 20 MVA 132/11 kv already planned at Sr. No. 84 of 2 nd MYT.
6.	220KV Baghapurana	66/11, 2x20+1x12.5	79.80%	82.99%	PSTCL apprised that Addl. 12.5 MVA 66/11 kv already planned at Sr. No. 57 of 2 nd MYT.
7.	132KV Panj Grayian	132/11, 2x12.5	90.05%	94.14%	PSTCL apprised that Aug of 12.5 MVA 132/11 kv to 20 MVA already planned at Sr. No. 81 of 2 nd MYT.
8.	132KV Kotakpura-1	132/11, 1x10/12.5	82.25%	85.54%	PSTCL agreed that proposal for augmentation of 132/11 kv, 10/12.5 MVA to 20 MVA 66/11 KV shall be included in MYT 2023-26 of PSTCL to reduce 132 KV system

9.	220KV Bajakhana	66/11, 2x20	91.42%	95.55%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
10.	220KV Mansa	66/11, 2x20	82.8%	86.16%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
11.	220KV Maur	132/11, 2x20	77.1%	80.21%	PSTCL agreed to the proposal for installation of Addl. one no. 20 MVA, 66/11 kV T/F in MYT 2023-26 of PSTCL to increase 66 KV System and decrease 132 KV system as suggested by CE/TS, PSPCL.
12.	220KV Kotkarore	66/11, 2x20	90.27%	93.88%	PSTCL agreed to the proposal for installation of additional 66/11 kV, 10/12.5 MVA in MYT 2023-26 of PSTCL.
13.	132 KV Sosan	132/11, 10/12.5	82.24%	85.5%	It was agreed for installation of additional 132/11 kV, 10/12.5 MVA instead of already planned augmentation of single 12.5 MVA T/F to 20 MVA as per request of CE/P&M PSTCL for N-1 contingency
14.	132 KV Srainaga	132/11, 2x12.5	85.9%	89.3%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
15.	132KV Kotkapura-2	132/11, 1x20	82.25%	85.54%	PSTCL apprised that there is no space available in yard and control room for additional T/F, as such PSPCL should explore some other alternative or set up a new 66 kV S/S nearby.
16.	132KV IGC Bathinda	132/11, 2x12.5	80.44%	83.65%	PSTCL apprised that Aug of 2x12.5 MVA 132/11 kV to 2x20 MVA already planned at Sr. No. 83 of 2 nd MYT.
17.	220KV Abohar	66/11, 2x20	91.12%	94.77%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV is already planned at Sr. No. 40 of 2 nd MYT.
18.	132KV Faridkot	132/11, 20+12.5	80.92%	84.16%	PSTCL apprised that Aug of 12.5 MVA 132/11 kV to 20 MVA is already planned at Sr. No. 59 of 2 nd MYT.

TABLE-3					MOM
Sr. no.	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	
1.	220KV Talwandi Sabo	220/66 KV, 1x100	89.14%	92.70%	PSTCL apprised that Addl. 100 MVA already covered in N-1 non-compliant substations list in 2 nd MYT20-23 of PSTCL.
2.	220KV Mansa	220/66 KV, 2x100 + 1x160	94.49%	98.2%	PSTCL apprised that 220 KV substation Budhlada is likely to be commissioned in next 6 months and it will de-load Mansa
3.	220KV Botianwala	220/66KV, 2x100(1X160+1X100)	88.29%	93.41%	PSTCL apprised that 1X 100 MVA, 220/66 kV transformer already stands replaced with 160 MVA T/F.
4.	220KV Ghubaya	220/66, 2x100 + 1x160	85.23%	86.92%	PSTCL apprised that upgradation of 66 kV substation Guru Har Sahai to 220 kV level is already under study. PSPCL requested for augmentation of 100 MVA to 160 MVA at 220kV Ghubhaya as upgradation of Guru HarSahai will take time but PSTCL apprised that loading is less than 90% and as and when loading crosses 90%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
5.	220KV Maur	220/66, 1x100	85.73%	89.15%	PSTCL apprised that 1 No. additional 220/66KV, 100 MVA transformers shall be included in 3 rd MYT 2023-26 to meet N-1 criteria.
6.	132KV IGC Bathinda	132/66, 2x50	81.15%	84.39%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
7.	132KV Malout	132/66, 2x25	95.12%	98.92%	PSTCL apprised that last year's maximum demand was temporary, otherwise the loading of 132/66 kV T/F is under 80% and PSPCL should shift some 66 KV sub-stations from Malout to 220 kV Katorewala. PSPCL also agreed upon this.
8.	220KV Ferozepur	132/66, 2x50	101.96%	106.03%	Regarding upgradation of Jhoke Hari Har from 66 kV to 220 kV, PSTCL requested PSPCL to give "Right to Use" to them to enable them to start work. PSPCL apprised that right to use of land case shall be put up for approval of WTDs of PSPCL. Meanwhile, PSPCL may shift some loads from 220 kV Ferozepur to nearby substations to manage the overloading at 220 kV Ferozepur.

9.	132KV Ferozeshah	132/66, 20+50	79.42%	82.60%	PSTCL apprised that loading is less than 80%, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
----	---------------------	---------------	--------	--------	--

NORTH ZONE & BORDER ZONE

TABLE 4

Sr. No.	Regarding installation of 4 th 132/11 kV, 20 MVA, PT/f at 132 kV S/S Pathankot
1	PSTCL has already planned 4 th additional 132/11 kV, 20 MVA T/F at 132 kV S/S Pathankot vide Amendment No. 21/2021-22 dated 30.9.21. PSPCL apprised that demolition of the building at 132KV S/S Pathankot and is under process. PSTCL requested PSPCL to expedite it.
2	Overloading at 132 kV S/S Nawanshahr CE/DS North Zone PSPCL Jalandhar apprised that 66 kV loads have been shifted from 132 kV Nawanshahr to 220 kV S/S Jadla to deload 132 kV Nawanshahr.
3	PSPCL request for new 220 kV S/S at Ajnala PSPCL intimated that since 220 kV Fatehgarh Churian is loaded beyond 80% in paddy 2022, so 66 kV Ajnala be upgraded to 220 kV level for reliable supply to consumers in the border areas of Amritsar District and to deload Fatehgarh Churian for which PSTCL agreed to the proposal with LILO of one circuit of Fatehgarh Churian- Civil Lines Amritsar D/C Line.
4	PSPCL request for new 220 kV S/S at Gadaipur (Jalandhar) CE/DS North Zone PSPCL Jalandhar informed that land for a new 220kV sub-station at Gadaipur proposed in last TPC meeting has been refused. So an alternate proposal is being worked out by PSPCL for a new 220 kV S/S to deload the 220 kV Kartarpur and 220 kV BBMB. PSPCL will submit the complete proposal (including 66 kV line connectivity, proposed load and status of land) to PSTCL for further action.
5	PSPCL request for new 132 kV S/S at Partapura (Jalandhar) PSTCL apprised that Upgradation of 66 kV Chitti to 220 kV to deload 220 kV S/S Badshahpur and 66 kV Chitti has already been planned vide PSTCL/Planning amendment no 7/2022-23.
6	Augmentation of 132/11 kV, 12.5 MVA to 132/11 kV at 220 kV S/S Sultanpur- PSTCL apprised that Augmentation of 132/11 kV, 12.5 MVA to 132/11 kV, 20 MVA has already been planned vide Amendment No. 07/2018-19.
7	Augmentations at 220 kV S/S Kartarpur PSPCL has requested for augmentation of 220/66 kV T/F, 100 MVA to 160 MVA as loading has reached more than 80%. PSTCL agreed for the same in the 3rd MYT. Regarding 66/11kV T/F, PSTCL apprised that one no. additional 10/12.5 MVA T/F stands planned.
8	Augmentations at 220 kV S/S BBMB Jalandhar Regarding augmentation of one no. 100 MVA 220/66kV T/F to 160 MVA, PSPCL agreed to take up the matter with BBMB as the sub-station is under their control.

6

117

9	Up-gradation of 132 kV S/S/ Tanda to 220 KV S/S It was informed by PSTCL that 132 KV Tanda is proposed to be upgraded to 220 KV S/S with LILO of one circuit of 220 KV Jalandhar-Dasuya line to address issue of low voltage as reported by CE/P&M PSTCL with one 100 MVA auto transformer. It will also provide relief if the generation is very less at MHP. CE/DS North Zone PSPCL Jalandhar apprised the committee that 132/66 KV transformers at Bhogpur are fully loaded and two 66kV stations Kandhala Jattan and Kajyanpur will be shifted from 132 kV Bhogpur to 220 kV Tanda for which one 100 MVA, 220/66 kV T/F is required. PSTCL agreed to include the proposal in the MYT of 2023-26.
10	Additional 20 MVA 132/11 kV transformer 132 kV S/S Kapurthala It was apprised the committee that an additional 20 MVA 132/11 kV transformer has already been commissioned.
11	Aug. of 1 No. 12.5 MVA to 20 MVA 132/11 kV transformer at 132 kV S/S Kathunangal-PSTCL 132/11 kV transformer has already been included in 2 nd MYT 2020-23 at Sr. No. 63.
12	Overloading at 220 kV S/S Patti- CE/DS Border Zone PSPCL Amritsar proposed up-gradation of 66 KV Toot to 220 KV with LILO of one circuit of 220 KV Makhu-Algon to give relief to 220 KV Patti. PSTCL intimated that the proposal is being included in the 3 rd MYT 2023-26. Moreover PSTCL stated that there is no space for 66 KV bay for 66 KV second circuit to Toot at Patti.
13	Addl. 20 MVA 132/11 kV T/F at 132 kV Focal Point Jalandhar- CE/DS North Zone PSPCL Jalandhar informed that maximum demand plus feasibility cases exceeds the 80% loading of 2x20MVA 132/11kV T/fs and requested for installation of addl 20MVA 132/11 kV with extension of control room. PSTCL agreed for the same subject to loading crossing 80%.
14	132 kV Kahanpur PSPCL requested for installation of 132/66 kV with extension of control room to provide 66 kV system at Kahanpur for meeting the requirement of industrial consumers. It was decided that the proposal regarding the same will be sent by CE/DS North Zone and PSTCL will examine it.

TABLE 5

Sr.no	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	220KV S/S Noormehal	66/11, 2x20	78.55%	81.69%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
2.	132KV Nakodar	132/11, 2x20	88.63%	92.17%	PSTCL apprised that Addl. 20 MVA 132/11 kV has already been planned vide Amend No. 08/22-23 dated 12.05.22.

5

3.	132KV Urban Estate	132/11, 2x20	77.95%	81.07%	PSTCL apprised that loading of the T/f is less than 80%. PSPCL also agreed and it was decided no additional T/f is required to be planned.
4.	220KV Mahilpur	132/11, 1x20 66/11, 1x20	96.60%	100.46%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV already planned at Sr. No. 47 of 2 nd MYT stands commissioned.
5.	220KV Banga	132/11, 2x20	96.30%	100.15%	PSTCL apprised that Addl. 20 MVA 132/11 kV already planned vide Amend No. 08/22-23 dated 12.05.22.
6.	220KV Kartarpur	66/11, 2x20	81.68%	84.94%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV already planned at Sr. No. 48 of 2 nd MYT and work is in progress.
7.	132KV Khera mandir	132/11, 2x20	78.50%	81.64%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
8.	132KV Bhogpur	132/11, 1x20+1x12.5	93.88%	97.63%	PSTCL apprised that Augmentation of 1 No. 12.5 MVA 132/11 KV to 20 MVA will be included in 3rd MYT 2023-26. PSPCL brought out this since M.D. on these T/fs has touched 97.63% as such planning of this work be preponed. PSTCL agreed for the same.
9.	132KV Sri Hargobindpur	132/11, 2x20	80.05%	83.25%	PSTCL apprised that Addl. 20 MVA 132/11 kV already planned at Sr. No. 65 of 2 nd MYT.
10.	220KV Butari	66/11, 2x20	82.58%	85.88%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV already planned at Sr. No. 50 of 2 nd MYT.

TABLE 6

Sr. no.	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	220KV Badshahpur	220/66, 2X100	77.60%	80.70%	PSTCL apprised that Loading was 75.10% (8.7.21) & 80.10% (4.8.21). Further Addl. 100 MVA T/F has been included in 2nd MYT under N-1 contingency, which has been installed.
2	220KV Nawanshahr	132/66, 100	96.90%	100.78%	Already Discussed in Sr. no. 2 of Table No. 4
3	220KV Kartarpur	220/66, 160+100	78.83%	81.98%	Already Discussed in Sr. no. 7 of Table No. 4
4	132KV Bhogpur	132/66, 100	90.78%	94.41%	Already Discussed in Sr. no. 9 of Table No. 4

111

9

5	132KV Sri Hargobindpur	132/66, 50+16	79.02%	82.18	PSTCL apprised that proposal for upgradation of 132 kV Sri Hargobindpur to 220 kV is under study for evacuation system of proposed 400 KV Wadala Granthian and generation issues at MHP. PSPCL agreed for including it in 3 rd MYT 2023-26.
6	220KV Dasuya	220/66, 100	88.00%	91.52%	PSTCL apprised that 2nd TF has already been installed.
7	220KV Mahilpur	220/132, 100	93.89%	97.65%	2 nd Auto T/f has already been planned at 220 kV Banga. PSPCL proposed replacement of 2X50 MVA, 132/66 KV transformers at Banga with 2X100 MVA, 220/66 KV Power Transformers to address the issue of overloading. PSTCL agreed for the same subject to the use of power cable to connect 66 KV buses
8	220KV Science City	220/132, 100	86.60%	90.06%	PSTCL apprised that there is no space available for additional T/F requested by PSPCL. So PSPCL may facilitate/arrange adjoining land in Pushpa Gujral Science city.
9.	220KV Butari	220/132, 100	86.87%	90.34%	PSTCL apprised that 220 KV Beas is already planned and an additional connectivity proposal at 220 kV Jandiala with an auto transformer is under study. PSPCL agreed for the same to provide reliable supply to consumers of Amritsar. Work for making 220 kV Bus of Butari as double and shifting of 220/132 KV T/F of Butari to 220KV Jandiala is also proposed.

BORDER ZONE					
TABLE 7					
Sr. no	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	132KV Gurdaspur	132/11, 40	78.85%	82.00%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
2.	220KV Civil Lines Asr	66/11, 2x20	81.25%	84.50%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV already planned vide Amend No. 08/22-23 dated 12.05.22.
3.	132KV Kathunangal	132/11, 1x12.5+1x20	80.86%	84.10%	PSTCL apprised that Aug of 12.5 MVA 132/11 kV to 20 MVA already planned at Sr. No. 63 of 2 nd MYT.
4.	132KV Power Colony, Asr	132/11, 2x20	80.93%	84.16%	PSTCL apprised that Addl. 12.5 MVA 132/11 kV already planned vide Amend No. 08/22-23 dated 12.05.22.

120

AB

By

5	220KV Rashiana	66/11, 7	79.38%	81.55%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
6.	132KV Bhikhiwind	132/11, 1x12.5+6/11, 1x20	85.08%	88.48%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
7.	220KV Algon Kothi	66/11, 1x12.5+1x20	79.45%	82.62%	PSTCL apprised that Aug of 12.5 MVA 66/11 kV to 20 MVA already planned at Sr. No. 46 of 2 nd MYT.
8.	220KV Chohla Sahib	66/11, 40	83.00%	86.32%	PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSPCL also agreed to the proposal.
9.	220KV Khasa	66/11, 32.5	85.57%	88.99%	PSTCL apprised that Aug of 12.5 MVA 66/11 kV to 20 MVA already planned at Sr. No. 45 of 2 nd MYT.
10	220KV Chogawan	66/11, 2x20	87.35%	90.84%	PSTCL apprised that Addl. 20 MVA 66/11 kV already planned vide Amend No. 08/22-23 dated 12.05.22.

TABLE 8

Sr no	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	220KV Tibber	220/66, 100	79.00%	82.16%	PSTCL informed that 2nd T/F has been commissioned.
2.	132KV Gurdaspur	132/66, 2X50	79.40%	82.58%	PSTCL apprised that the work of upgradation of 220 kV Gurdaspur is under progress.
3.	220KV Udhoke	220/66, 100	77.00%	80.08%	PSTCL apprised that work of Addl. 100 MVA T/F is under progress.
4.	220KV Majitha	220/66, 100	76.97%	80.05%	PSTCL apprised that Addl. 100 MVA has been included in the 2nd MYT
5.	220KV Patti	220/66, 260	93.11%	96.83%	Already discussed at Sr. No. 12 of Table-4
6.	132KV Taran	132/66, 75	80.47%	83.69%	PSTCL requested PSPCL to shift some 66 KV load from 132 kV Taran. Taran to Rashiana. PSPCL agreed for the same.

7.	220 KV Wadala Granthian	220/132, 200	100.00%	104.00%	PSTCL apprised that Addl. 3 rd 100 MVA 220/132KV has already been planned vide Amendment no. 28/2021-22 issued on 9.12.2021
8.	220 Civil Line Asr	220/132, 100	87.70% (due to temporarily load by PC Patiala)	91.21%	PSTCL apprised that 2nd T/F under N-1 already stands planned.

SOUTH ZONE

TABLE 9

Sr. No	Agenda item	MOM
1	220 kV S/S Ablowal	
	PSPCL requested for extension in 11 KV control room building but PSTCL suggested PSPCL to shift some 11 kV feeders load from 220 kV S/S Ablowal to new 66 kV S/S Thapar University which will deload 220 kV S/S Ablowal. PSPCL intimated that erection of 11 kV feeders from Thapar university is not possible and thus a new 66 kV S/S nearby is being explored. CE/TS PSPCL suggested a new 66 KV S/S at Power Colony or some other nearby place.	
2	220 kV S/S Bangan-	
	PSPCL requested for extension in 11 KV control room building along with augmentation of 20 MVA power T/F to 31.5 MVA. PSTCL apprised that 66 kV bays for Sailwala and Banarasi at 220 kV S/S Bangan have been planned vide Amendment No. 34/2021-22 dated 02.02.22 & 10/2022-23 dated 12.5.22. Further PSPCL requested to augment 20 MVA to 31.5 MVA 66/11 kV T/F along with Control room extension but PSTCL intimated that there is no space for Control room extension. CE/South PSPCL agreed for site visit at Bangan to check Control room extension or PSPCL will establish a new 66 kV S/S nearby.	
3	220 kV S/S Derabassi	
	PSPCL requested for augmentation of one 220/66 KV, 100 MVA to 160 MVA and one 66/11 KV, 20 MVA to 31.5 MVA T/Fs. PSTCL apprised that loading is less than 80 %, so no augmentation is required and as and when loading crosses 80%, PSTCL will take action accordingly. PSTCL apprised that augmentation of 1 No. 20 MVA, 66/11kV to 31.5MVA transformer at 220kV S/S Derabassi has been planned vide Amendment No. 08/2022-23 dated 12.5.22 along with control room extension.	
4	220 kV S/S Kharar	
	PSPCL requested for extension in 11 KV control room building along with augmentation of 20 MVA power T/F to 31.5 MVA. PSTCL apprised that 1 No. Addl. 20 MVA, 66/11 kV transformer at 220 kV S/S Kharar has been planned vide Amendment No. 8/2022-23 dated 12.5.22 and Augmentation of 100 MVA 220/66kV to 160 MVA has been planned vide amendment no. 25 dated 09.12.2021. PSPCL intimated that land is available near Bhukhdi village but not acquired by PSPCL till now for new 66 kV S/S. Further there is a ROW issue in the 66 kV incoming line at Bhukdi. PSPCL also intimated that there is no scope for further expansion at 220 KV Kharar, so it has proposed to PSTCL to explore the possibility of 66 kV Morinda or Kurali to 220 kV. ROW is not available at Morinda for 220 KV line but Kurali can be upgraded to 220 KV S/S. Proposal may be sent by PSPCL to shift load of Morinda to Kurali.	

122

3

5	Overloading at 132 kV S/S Ropar PSTCL apprised that 2 x 20/25 MVA, 132/66kV transformers already planned at 132kV Chamkaur Sahib vide amendment no. 30/2021-22. PSPCL has intimated that they will explore constructing a new 66 kV S/S in vacant Thermal colony
6	Up-gradation of 66 kV S/S Old Patiala (bus stand) to 220 KV- PSPCL requested for the up-gradation of 66 KV Old Patiala to 220 KV S/S. PSTCL has apprised that Up-gradation of 66 kV Old Patiala to 220 kV level is already planned vide PSTCL planning amendment no 18/2021-22. But Right to use of land is still pending from PSPCL. PSPCL has assured to expedite the same.
7	Up-gradation of 66 kV S/S Mubarakpur to 220 KV- PSPCL requested for the up-gradation of 66 KV Mubarakpur to 220 KV S/S. PSTCL has apprised that Up-gradation of 66kV Mubarikpur to 220 kV level already planned vide PSTCL planning amendment no. 1/2022-23 dated 12.5.2022. But Right to use of land is still pending from PSPCL. PSPCL has assured to expedite the same.
8	220 kV S/S Barnala (Handiaya) PSPCL has requested for additional 20 MVA 66/11 KV T/F along with control room extension. PSTCL has apprised that loading is more than 85% and agreed to include addl. 10/12.5 MVA 66/11 KV T/F in the next MYT. PSPCL has also intimated that 66 kV Khuddi Kalan has also been proposed to deload 220 kV Barnala.
9	220 kV S/S Malerkotla PSTCL has apprised that loading is within limit. PSPCL has requested for control room extension at 220 kV Malerkotla. PSTCL agreed upon this.
10	Establishing new 220 Kv S/S at Aerocity PSPCL requested that about one acre land owned by GMADA for a new 66 kV substation may be examined by PSTCL for construction of 220 kV GIS substation Aerocity. PSTCL requested PSPCL to provide a copy of the master plan of land so that the possibility of setting up a new 220 kV GIS substation may be examined.

TABLE 10

Sr. no.	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	220KV Ablowal	66/11, 2 x 20 MVA	82.325 %	85.16%	As already discussed in sr. No. 1 of Table-9
2	220 KV Devigarh	66/11, 2 x 20 MVA	84.35 %	87.72 %	PSTCL has apprised that Additional 10/12.5 MVA 66/11 KV T/f will be included in 3rd MYT 2023-26.
3	220 KV Dhuri	1x 20 MVA and 1x 12.5 MVA	87.26%	90.75 %	PSTCL has apprised that Aug of 12.5 MVA to 20 MVA already planned at Sr. No. 42 of 2 nd MYT.
4	220 KV Dhanaula	2x 20 MVA P/T/F	90 %	93.83 %	PSTCL has apprised that Additional 10/12.5 MVA 66/11 KV T/f will be included in 3rd MYT 2023-26.
5	220 KV Kharar	3x 20 MVA P/T/F	98.6%	102.5%	As already discussed in sr. No. 4 of Table-9

123

6	220 KV Bani	2x 20 MVA P/T/F	93.7%	97%	PSTCL has apprised that Addl. 20 MVA 11/11 kV already planned at Sr. No. 44 of 2 nd MYT.
7	220 KV Banga	2x 20 MVA P/T/F	81.5%	84.76%	PSTCL has apprised that Addl. 20 MVA 132/11 kV already planned vide Amend No. 08/22-23 dated 12.05.22.
8	132 KV Chamkaur Sahib	2x 132/11 KV, 20 MVA P/T/F	87.97 %	91.49%	PSTCL has apprised that 2 No. 20/25 MVA, 132/66 kV are planned vide Amend No. 30 dated 14.1.22. Further 1 No. 66/11 kV 12.5 MVA will be included in 3 rd MYT 2023-26.
9	132 KV Ropar	2x 132/11 KV, 20 MVA P/T/F+ 1x 66/11 KV P/T/F	82 %	85.31%	As already discussed in sr. No. 5 of Table-9
10	220 KV Ghulal	1x 132/11 P/T/F(12.5)+ 2x 20 MVA 66/11 P/T/F	71.42 %	74.28%	PSTCL has intimated that replacement of 132/11 kV (12.5 MVA) with 20 MVA 66/11 kV at Ghulal is already planned.
11	220 KV BBMB Sangrur	1 x16 MVA and 1x 12.5 MVA 66/11 P/T/F	71.39 %	74.22 %	In the scope of BBMB
12	220 KV Kohara	4x20 MVA 66/11 P/T/F	71.60%	82.01%	PSTCL has apprised that Aug of 20 MVA 66/11 kV to 31.5 MVA vide Amend No. 08/22-23 dated 12.05.22 is planned.
13	220 KV Malerkotla	2x20 MVA 66/11 P/T/F	78.45%	82%	As already discussed in sr. No. 9 of Table-9

Sr. no.	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1.	220 KV Toderpur (Rajla)	1x160 MVA, 1x100 MVA	75.32 %	85.21%	PSTCL apprised that the load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
2.	220 KV Kaheru (Dhuri)	3x100 MVA	73.15 %	84.61%	PSTCL apprised that the load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
3.	220 KV Malerkotla	2x160 MVA	77.69 %	82.9 %	PSTCL apprised that Recently 2X100 MVA t/fs got damaged at Malerkotla and 1X160 MVA T/f was installed in place of these two damaged transformers. 1X100 MVA T/f will be installed as and when required.

4.	220 KV Kohara	2x100 MVA	66.09 %	84.15 %	PSTCL apprised that Kohara will be deloaded with the new S/S coming up at Dhanansu.
5.	220 KV Barnala	2x100 MVA	81.64%	84.90 %	PSTCL apprised that the load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
6.	220 KV Rajpura	3x100 MVA	75.83%	85.75%	PSTCL agreed to augment 100 to 160 MVA on the request of PSPCL if loading in the current paddy season crosses 80%.
7.	220 KV Mohali -1	1x160 MVA, 2x100 MVA	86.5 %	89.96 %	PSTCL has apprised that one more 100 MVA has been augmented to 160 MVA.
8.	220 KV Kharar	1x160 MVA, 1x100 MVA	90.24%	93.85 %	PSTCL apprised that Aug. of 1x100MVA with 160 MVA vide Amendment no. 25/2021-22 issued on 9.12.2021.
9.	220 KV Banur	2x100 MVA	84.88%	88.27%	PSTCL apprised that Aug. of 1x100MVA with 160 MVA vide Amendment no. 2/2022-23 issued on 12.5.2022.
10.	220 KV Sunam	1x160 MVA, 2x100 MVA	77.01%	80.1%	PSTCL apprised that the load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
11.	132 KV Ropar	2x132/66 KV	92.8%	96.51%	Already discussed in Sr. No. 5 of Table-9
12.	220 KV Ghulal	2x100 MVA, 220/66	81%	81%	PSTCL apprised that Aug. of 1x100MVA with 160 MVA vide Amendment no. 3/2022-23 issued on 12.5.2022.

CENTRAL ZONE

TABLE 12

Sr.	220 kv S/S Amlah
No	PSTCL apprised that 1 No. Addl. 20 MVA, 66/11 kv transformer at 220 kv S/S Amlah has been planned vide Amendment No. 08/2022-23 dated 12.5.22 alongwith control room extension as per demand of PSPCL.
1	
2	220 kv S/S Ikolaha On the request of PSPCL to extend control room along with augmentation of 20 MVA T/F, PSTCL informed that there is no further scope of control room extension and PSPCL should shift some 11 kv load to its nearby substations to deload 220kv S/S Ikolaha. PSPCL informed that shifting of loads is already in process.
3	220 kv S/S Gaunsgarh On the request of PSPCL to extend control room along with augmentation of 20 MVA T/F, PSTCL apprised that 1 No. Addl. 20 MVA, 66/11 kv transformer at 220kv S/S Gaunsgarh has been planned vide Amendment No. 08/2022-23 dated 12.5.22 alongwith control room extension.
4	220 kv S/S Lalton Kalan On the request of PSPCL to extend control room along with augmentation of 20 MVA T/F, PSTCL apprised that load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.

5	<u>220 kV S/S Humbran</u> On the request of PSPCL to extend control room along with augmentation of 20 MVA T/F, PSTCL apprised that 1 No. Addl. 20 MVA, 66/11 kV transformer at 220 kV S/S Humbran has been planned vide Amendment No. 08/2022-23 dated 12.5.22 alongwith control room extension.
6	<u>220 kV S/S GIS Sherpur, Ludhiana</u> PSTCL informed that Work is in progress and work is likely to be completed by Paddy, 2023. Civil work is in progress. Work allotted in 09/2019 and was to be completed by 03/21. But start of work got delayed due to shifting of 11 kV feeders and dismantlement of old building/ water tank by PSPCL. The site was cleared by PSPCL in March, 2021 and was handed over to the contractor for execution of work. Civil Works in the scope of PSTCL got delayed due to scarcity of material (sand, gravel and good earth).
7	<u>220 kV S/S Gill Road</u> PSPCL proposed up-gradation of 66 kV Gill Road to 220 kV which will give relief to overloaded 66 KV Lalton Kalan- Gill road D/C lines as up-gradation of conductor of these lines to HTLS is not possible as line passes over very thickly populated areas. PSTCL agreed to include the work in 3 rd CP of MYT 2023-26 subject to the demolition of the 1912 complaint center and offices of DS organization. CE/DS Central & CE/P&M PSPCL gave consent to demolish/shift the complaint center 1912 to Power colony No-2 Sarabha Nagar.
8	<u>220 kV S/S Jhordan</u> PSPCL requested PSTCL to set up a new 220 KV S/S at Jhordan on land provided by panchayat to deload overloaded S/S at Pakhowal and overloaded lines from Jagraon as there is no scope for new lines from Jagraon due to ROW issues. PSTCL apprised that Amendment no. 23/2021-22 regarding creation of new 220 KV S/S Jhordan has already been issued by PSTCL. But the work could not be started as the panchayat land had not been handed over to PSTCL. PSTCL has requested to expedite the work of land handover to PSTCL. PSTCL agreed upon installation of 66/11KV T/F along with 11KV VCBs at the s/s as per MOM of CMDs of both the corporations.
9	<u>220 kV new S/S at 66 kV S/S Bhadson</u> PSPCL proposed new 220 kV S/S by upgrading 66 kV s/s Bhadson to deload 220 kV Amloh S/S to facilitate release of new connections. PSTCL intimated that this work is being included in 3 rd CIP of MYT 2023-26 to evacuate power from PGCIL Patiala as one additional 500 MVA ICT is being installed.
10	<u>220 kV S/S Pharmaceutical Park, Wazirabad</u> PSTCL apprised that this work is already included in 2 nd CIP of MYT 20-23. However, work could not be started because land to be handed over to PSTCL has not finalised by PSIEC.
11	<u>220 kV S/S Fatehgarh Neoyan</u> PSPCL proposed a new 220 kV S/S at Fatehgarh Neoyan to make alternative source of supply to 66 KV Substations fed from 220 KV S/S Mandi Gobindgarh-2 on panchayat land. PSPCL was requested to submit the complete proposal (including 66 kV line connectivity, proposed load and status of land) to PSTCL for further action.
12	<u>220 kV S/S Sahnewal</u> PSPCL requested for augmentation of one 20 MVA T/F to 31.5 MVA. PSTCL apprised that augmentation of 1 No. 20 MVA, 66/11 kV to 31.5 MVA transformer along with control room extension at 220 kV S/S Sahnewal has been planned vide Amendment No. 08/2022-23 dated 12.5.22.

13	220 kV S/S Ghulal	PSPCL requested for augmentation of one 100 MVA T/F to 160 MVA. PSTCL apprised that augmentation of 1 No 100 MVA P/T/F with 160 MVA P/T/F at 220 KV S/S Ghulal has been planned vide amendment no. 3/12.5.22
----	-------------------	--

TABLE-13					
Sr. no	Name of S/S	Capacity of T/F's	Overall %age loading of S/S	Loading anticipated	MOM
1	220KV Ajitwal	66/11, 2 x 20 MVA	88.35%	91.88%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV already planned vide Amend. No. 08/22-23 dated 12.05.22.
2	220KV Dharamkot	66/11, 2 x 20 MVA	78.35%	81.48%	PSTCL apprised that the load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
3	220KV Badhni Kalan	66/11, 2 x 20 MVA	91.49%	95.15%	PSTCL apprised that additional 20 MVA 66/11 KV T/F will be included in 3rd CP of MYT 2023-26.
4	220KV Swaddi Kalan	66/11, 2 x 20 MVA	85%	88.40%	PSTCL apprised that the load was less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this. PSPCL requested for building extension and PSTCL agreed to include the work in MYT.
5	220KV Doraha	66/11, 2 x 20 MVA	85.03%	88.43%	PSTCL apprised that Addl. 12.5 MVA 66/11 kV planned vide Sr. No. 56 of 2 nd MYT has been commissioned.
6	132KV Sihora	132/11, 2 x 20 MVA	79.07%	82.23%	PSTCL apprised that the load is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
7	220KV Lalton Kalan	66/11, 2 x 20 MVA	82.28%	85.57%	PSTCL apprised that loading is less than 80%. PSTCL will plan as and when required. PSPCL also agreed upon this.
8	220KV Sahnewal	66/11, 3 x 20MVA	83.2%	86.53%	PSTCL apprised that Aug. of 20MVA 66/11kV T/F to 31.5MVA vide Amendment no. 08/22-23 dated 12.5.2022
9	220KV Humbran	66/11, 2 x 20 MVA	77.5%	80.60%	PSTCL apprised that Addl. 20 MVA 66/11 kV has already been planned vide Amend No. 08/22-23 dated 12.05.22 along with control room extension.

127

10	220KV Pakhowal	66/11, 2 x 20 MVA, 1x12.5	76.76%	79.83%	PSTCL agreed to augment 12.5 MVA T/F to 20 MV/ in 3rd CIP of MYT
11	220KV Bassi Pathana	66/11, 2 x 20 MVA	84.08%	87.44%	PSTCL apprised that addl. 20 MVA 66/11 kv T/F has been planned vide Amend No. 08/22-23 dated 12.05.22.
12	220KV Dhandari Kalan -1	66/11, 2 x 20 MVA	78.5%	81.64%	PSTCL has intimated that Addl. T/F's can be planned at both the stations after the execution of the Double Bus bar arrangement.
13	220KV Dhandari Kalan -2	66/11, 2 x 20 MVA	80%	83.20%	
14	220KV Kohara	66/11, 2 x 20 MVA	80%	83.20%	PSTCL has apprised that Aug of 20 MVA 66/11 kv to 31.5 MVA has been planned vide Amend No. 08/22-23 dated 12.05.22.
15	220KV Goraya	66/11, 2 x 20 MVA	90.75%	94.38%	PSTCL apprised that Addl. 20 MVA 132/11 kv T/F has been planned vide Amend No. 08/22-23 dated 12.05.22.
16	220KV Gaunsgarh	66/11, 2 x 20 MVA	78.33%	81.46%	PSTCL apprised that Addl. 20 MVA 66/11 kv T/F along with control room extension has been planned vide Amend No. 08/22-23 dated 12.05.22.
17	400kv Makhu	400/200/33KV, 2 x 315 MVA (ICT-1 &2)	85.52%	88.94%	PSTCL apprised that 1 No. addl. 500 MVA ICT has already been commissioned

TABLE 14

Sr. no.	Name of S/S	MOM	
1	220 KV BBMB Jamalpur	Augmentation of 100 MVA P/T/F to 160 MVA	PSTCL apprised that Work has been completed.
2	220 KV DK-I	Augmentation of T-1 100 MVA P/T/F to 160 MVA (As per technical data in feasibility case of M/s Arora alloys (RID no. 100000015959), the percentage loading of 2 no. 100 MVA P/T/F's (220/66KV) is becoming 102.07%. The action to augment any 1 no. 100MVA P/T/F be carried out.	In the FCC meeting dated 12.05.2022, it was intimated to FCC that 1 No. 100 MVA 220/66 kv transformer at 220 kv Dhandari Kalan-1 substation can be augmented to 160 MVA by PSTCL subject to the condition that a shutdown of 100 MVA 220/66 kv T/f for 45-50 days is made available by PSPCL at the said substation. PSPCL clarified that a shutdown for so many days will not be possible. PSPCL informed in the TPC meeting that shutdown for 4-5 days may be given only after installation of 160 MVA at DK-2.

Handwritten signature or mark.

128

3	220 KV DK-II	Augmentation of 100 MVA P/T/F to 160 MVA (As per technical data in feasibility case of M/s National Industries (RID no. 100000017578) , the percentage loading of 2 no. 100 MVA P/T/F's (220/66KV) is becoming 103.03%. The action to augment any 1 no. 100MVA P/T/F with 160 MVA P/T/F be carried out)	PSTCL apprised that work has already been planned in MYT 2020 - 23
4	220 KV Ikolaha	Additional P/T/F of 160 MVA	PSTCL apprised that the addl. T/F has been planned under N-1 contingency conditions.
5	220 KV Amlah	Augmentation of Existing 1x 100 MVA P/T/F with 160 MVA or installing additional 1 no. new 1x100 MVA	PSTCL apprised that work has been completed to augment 100 MVA with 160 MVA vide Amendment no. 11/2022-23 issued on 27.5.2022
6	220 KV Sahnewal	Augmentation of Existing 1x 100 MVA P/T/F with 160 MVA (As per technical data in feasibility case of M/s Oster India Pvt. Ltd (RID no. 100000018186), the percentage loading of existing P/T/F's (220/66KV) is becoming 91.02%. The action to augment 100MVA P/T/F with 160 MVA P/T/F is carried out.)	PSTCL apprised that Aug. of 100 MVA with 160 MVA has been planned vide Amendment no. 3/2022-23 issued on 12.5.2022
7	220KV S/S G-3 Mandi Gobindgarh	As per technical data in FCC case of M/s ANJ Metal RECYCLING PVT. LTD., village Tooran, Amlah Road, Mandi Gobindgarh (RID no. 100000008284) , the percentage loading of 2 no. 100 MVA P/T/F's (220/66KV) is becoming 91.73%. The action to augment any 1 no. 100MVA P/T/F with 160 MVA P/T/F be carried out.	PSTCL agreed to include the proposal in next MYT
8	220KV S/S G-1 Mandi Gobindgarh	To expedite the proposal to augment 2 no. 220/66 P/T/F's 100 MVA with 160 MVA at 220KV S/S G-1 Mandi Gobindgarh be carried out.	PSTCL apprised that Aug. of 2x 100MVA with 160 MVA has been planned vide Amendment no. 6/2022-23 issued on 12.5.2022

3

ADDITIONAL AGENDA OF PLANNING PSPCL/PSTCL DISCUSSED IN TPC MEETING

		TABLE 15
		MOM
1(PSTCL)	Regarding planning of 66 kV bays at 220 kV S/S Sandhwan-132 kV S/S Kotkapura.	The work of 132 kV Kotakpura-Sandhwan 220 kV line has been placed at PSPCL TWL 2019-20 Sr. No. 17/WZ/2019-20/ Annexure-A, TWL 2020-21/2021-22 Sr. No. 15/WZ/2020-21 &2021-22/ Annexure-A & TWL 2022-23 Sr. No. 12/WZ/2022-23/Annex-A for which 2 No. 66 kV line bays each at 220 kV Sandhwan and 132 kV Kotakpura are to be executed by PSTCL. In this regard, clarification of 66 kV bays at 220 kV Sandhwan and 132 kV Kotakpura was sought from Dy. CE/Transmission Planning, PSPCL, Patiala. PSPCL agreed to clarify the same.
2(PSTCL)	Regarding extension of control room building at various s/stns. of PSTCL.	PSTCL informed that a proposal of extension of control room building at various 132/220 kV s/stns.(56 No.) of PSTCL has been received from CE/P&M, PSPCL, Ludhiana to accommodate installation of new VCBs for bifurcation cases/ newly erected 11 kV feeders. In the TPC meeting, PSPCL informed that they will review the list and will send the priority list again to PSTCL.
3(PSTCL)	66kV HTLS lines: PSPCL has planned replacement of ACSR conductor with HTLS conductor at certain 66kV transmission lines emanating from 220kV substations.	PSPCL agreed to provide the list of 66 kV lines which are planned to be augmented to HTLS.
4(PSPCL)	Upgradation of 66 KV Bhabat S/S to 220 KV	PSPCL was requested to send a complete proposal to include the upgradation of 66 KV Bhabat S/S to 220 KV in 3 rd MYT 2023-26.
5(PSTCL)	66 KV Line from 220 KV Kharar to 220 KV S/S Banur	This work has been placed at PSPCL TWL 2019-20 Sr. No. 91/SZ/2019-20/Annex-D, TWL 2020-21/2021-22 Sr. No. 99/SZ/2020-21 &2021-22/ Annex.-D & TWL 2022-23 Sr. No. 125/SZ/2022-23/Annex-D. 1 No. 66 KV line bay for 66 KV Ansal Plaza at 220 KV S/S Kharar has already been planned vide PSTCL amendment No. 38/2014-15 dated 11.03.15. Clarification regarding the requirement of an additional 66 kV bay at Banur has been sought from PSPCL Planning. CE/South informed that no bay is required at Kharar. Further, PSPCL/Planning will also clarify the same.

130

2

6(PSTCL)	66 KV Line from 220 KV Rashiana to 66 kV Focal Point Taran Taran	It is submitted that this work has been placed at PSPCL TWL 2019-20 Sr. No. 21/BZ/2019-20/Annexure-A, TWL 20-21/21-22 Sr. No. 21/BZ/20-21&21-22/Annex-A & TWL 2022-23 Sr. No. 13/BZ/2022-23/Annex-A. 1 No. 66 KV line bay for 66 kV Focal Point Taran Taran at 220 KV S/S Rashiana has already been planned vide PSTCL amendment No. 38/2014-15 dated 11.03.15. Clarification regarding the requirement of an additional 66 kV bay at Rashiana has been sought from PSPCL Planning. PSPCL/Planning will clarify the same.
7(PSTCL)	66 KV line line from 220 KV Patti to 66 KV Toot.	It is submitted that this work has been placed at PSPCL TWL 2019-20 Sr. No. 33/BZ/2019-20/Annex-B, TWL 20-21/21-22 Sr. No. 36/BZ/20-21&21-22/Annex-B & TWL 2022-23 Sr. No. 32/BZ/2022-23/Annex-B. It was intimated to PSPCL vide this memo No. 1711 dtd. 09/09/20 (email dtd. 10/09/20) & 1314 dtd. 03/06/21 (email dtd. 03/06/21) that there is no space available in the yard at 220 KV Patti for construction of 66 KV line bay. To give relief to Patti, up-gradation of Toot to 220 KV is being included in 3 rd CP of MYT 2023-26.
8(PSTCL)	Upgradation of 66 kV substation Chaheru to 220 kV	PSPCL requested for up-gradation of 66 KV Chaheru to 220 KV to give relief to Jamsher, Phagwara and Rihana Jattan. PSTCL apprised that upgradation of 66 kV substation Chaheru to 220 kV will be included in 3 rd CP of MYT 2023-26.

LIST OF SUBSTATIONS BEING PROPOSED IN 3rd MYT 2023-26 BY PSTCL

1	Upgradation of 132 kV Samadh Bhai to 220 kV level	LILO of both circuits of 220 kV Baghapurana – Bajakhana line (LILO Length –8km, 0.45sq").	PSTCL apprised that this S/S will give relief to Bajakhana & Himmatpura. Shifting of load of Deena Sahib and Patto Heera Singh from Himmatpura and Bhagta Bhai Ka from Bajakhana. PSPCL informed that 2X160 MVA power T/Fs are overloaded at GHTP Lehra Mohabbat also. So they need up-gradation of Bhagta Bhai Ka to 220 KV also along with Samadh Bhai. PSPCL plans to shift from GHTP two 66 KV S/Ss to Bhagta and one 66 KV S/S to Bhagta Bhai Ka as per proposal submitted by CE/P&M PSPCL & CE/DS (West). PSTCL agreed for the same
---	---	---	---

5

2	Upgradation of 66 kV Bija/Chawa to 220 kV level with installation of 2 X 100 MVA, 220/66 kV transformers.	For evacuation of Dhanansu by LILO of one circuit of Dhanansu- Doraha	PSTCL apprised that proposal of this substation was received from PSPCL for upcoming loads in and around Sahnewal/ Doraha. Therefore it will be included in 3rd CP of MYT 2023-26 by PSTCL.
3	Upgradation of 66 kV Chourwala to 220 kV level with installation of 2X160 MVA, 220/66 kV transformers.	LILO of both circuits of 400 kV Rajpura – 220 kV Gobindgarh-1 line (HTLS) (8 km, 0.45sq" equivalent)	Proposal of up-gradation has been received from CE/Central PSPCL to de-load 220 KV S/S G-1 to facilitate release of new connections. PSTCL agreed to include the upgradation of this S/S in 3rd CP of MYT.
4	Upgradation of 132 kV Jandiala Guru to 220 kV level with installation of 2 X 100 MVA, 220/132 kV transformers.	LILO of 220 kV Butari – Verpal circuit on multi-circuit/moder techniques (4km, 0.45sq")	To address the problems in the walled city of Amritsar a committee was constituted by Director/T. As per recommendation of committee to give reliable supply to Amritsar city it was proposed to upgrade Jandiala by shifting 220/132 Kv 100 MVA auto T/F from Butari to inject power at Verka to provide reliable supply in event of constraints in Batala- Verka D/C line or 132 KV bus at Verpal.
5	Upgradation of 132 kV Sri Hargobindpur to 220 kV level with installation of 1 X 100 MVA, 220/132 kV & 1X100 MVA 220/66 KV transformers.	D/C From 400 KV Wadala Granthian (28km, 0.45sq")	PSTCL apprised that this substation is required for evacuation of power as a downstream network of 400 kV Wadala Granthian. In addition it will address the problems of constraints at MHP when all the machines are shut due to low water or silt as MHP is a run off the river project. PSPCL agreed to the proposal.
6	Upgradation of 66 kV Giaspura to 220 kV level with installation of 2X160 MVA, 220/66 kV transformers.	LILO of 400 kV Ludhiana – 220 kV Dhandari Kalan (1.5km , 0.45sq") Multi circuit towers/Modern techniques	Proposal of up-gradation has been received from CE/Central and CE/P&M PSPCL to de-load 220 KV S/S Sahnewal to facilitate release of new connections in Kanganwal.area and shift 66 KV Singla Cycles. PSTCL agreed to include the upgradation of this S/S in 3rd CP of MYT.

7	400KV Wadala Granthian	LILO of both circuits of 400KV Kullu/Banala - Amritsar/Jalandhar line of PGCIL OR LILO of both circuits of 400KV Jalandhar - Samba line of PGCIL OR LILO of both circuits of 400KV Moga - Kishenpur of PGCIL	To increase ATC/TTC limit of State in future
---	------------------------	--	--

Handwritten mark

Handwritten mark