

### DNIT for Protection of Tower No. 9 of 220 KV Sarna-RSD circuit 3&4 Line

S No	Description of an item	QTY	Unit	CSR Ref	Total Rate	Rate to be quoted by contractor
1	Dismantling stone pitching stone pitching grouted with dry ballast and with natural silt and clay ( stone pitching on slope)	54.00	cum	8.2 d	334.82	
2	Dismantling cement concrete 1:2:4( tower floor)	1.25	cum	8.6 d	1341.07	
3	Earth filling under floors with surplus ordinary soil or soil containing gravel or kankar upto 40% excavated from foundation and taken only from outside the building plinth in 15cm layers including ramming, watering and consolidating lead upto 30 metres Retaining Wall	99.00	cum	6.8(c)(ii)	321.43	
4	Cement Concrete 1:6:12 with 40mm gauge stone aggregate.	3.38	cum	10.8 b(II)	2427.05	
5	Conglomerate floor 50 mm thick cement concrete topping 1:2:4	45.00	Sqm	14.7	239.26	
6	Earth work in excavation of foundations	12.00	cum	6.60	178.57	
7	Stone pitching top coping only	48.60	cum	23.43	2099.11	
8	Grouting stone filling or pitching cm 1:2:4	162.00	Sqm	23.45 b	153.57	
9	Random rubble masonry or polygonal rubble masonry (Kentish Rag) or random or polygonal rubble built to courses in foundations and plinth in cement mortar 1:6	6.00	cum	12.30	3913.31	
10	Carriage of odd job to the tower no 9 majdoor load upto 40 kg and distance upto 3 km for Coarse sand ,fine sand, crusher, stone ballast and boulder	1253.2	each	5.30	68.57	
11	Carriage of odd job to the tower no 9 majdoor load upto 40 kg and distance upto 3 km for cement	128.75	each	5.30	68.57	
12	Unskilled labour for carrying water from roadside to location of tower half man for 30 days	15.00	man per day	L 35	301.83	

13	Recovery of stone from dismantlement of pitching recoverable stone upto 18 kg-40 KG	38.88	cum	M-9	-667.25	
14	Extra Carriage and difference of material Rates					
A	Extra Carriage and difference of material for coarse sand	7.97	Cum	Annex	183.68	
B	Extra Carriage and difference of material for Crusher 13. 2mm	5.87	Cum	Annex	31.25	
C	Extra Carriage and difference of material for Crusher 11. 2mm	5.87	Cum	Annex	12.04	
D	Extra Carriage and diff of material rate for Stone Rough-tooled	6.60	cum	Annex	101.94	
E	Extra Carriage and diff of material rate for stone metal 40 mm	3.35	cum	Annex	-13.27	
F	Extra carriage for fine sand	1.67	Cum	Annex	256.80	
G	Extra carriage for cement	5.15	MT	Annex	516.66	

Notes: -

- 1 These rates are through rates exclusive of Cement & Steel that shall be issued by PSTCL from jamsher/ablowlal store(As per Availability).
- 2 Any error regarding description,reference to CSR,Quantity,rate,premium,unit,calculations omission,addition will be corrected at any stage as per CSR,AOR,Specification and drawings and no claim whatsoever shall be entertained on this account.
- 3 PWD/ PSTCL specifications will be followed for all the above items, for which ref. to CSR items and NS items is given.
- 4 For any NS item, which is not covered in DNIT, shall be allowed on the same pattern of AOR with the prior approval of Er – in – Charge.
- 5 GST will be applicable as per Govt. norms and will be paid extra.
- 6 Rates of taxes and duties if any applicable must be mentioned clearly otherwise maximum rate shall be taken into account for evaluation purposes.
- 7 At the time of final billing, the merit position w.r.t actual work done shall be prepared again and total payment to be paid to the contractor shall be restricted as per cost percentage w.r.t. departmental rates of L-1 in revised comparative statement and approved comparative statement . In case if the merit position of L-1 contractor changes, the total payment to contractor will be restricted to L-1 Cost of revised comparative statement.

Signature of vendor